

**COUNTY OF SAN MATEO  
PLANNING AND BUILDING DEPARTMENT**

**DATE:** July 26, 2023

**TO:** Planning Commission

**FROM:** Planning Staff

**SUBJECT:** EXECUTIVE SUMMARY: Consideration of the adoption of an Addendum to the Ascension Heights Subdivision Final Environmental Impact Report, and a Use Permit and Fence Height Exception, to allow construction of a new 58,929-gallon water storage tank and permit an existing 210,000-gallon water storage tank, along with associated infrastructure to serve the Ascension Heights subdivision, and to allow construction of an 8-foot tall fence where 6 feet is the maximum, located at 1452 Bel Aire Road, in the San Mateo Highlands area of unincorporated San Mateo County.

County File Number: PLN 2021-00275 (CalWater)

**PROPOSAL**

California Water Service Company (CalWater), a private utility company, proposes to construct a new 58,929-gallon water storage tank and associated infrastructure, and permit an existing 210,000-gallon water storage tank, to serve the approved Ascension Heights subdivision (PLN 2002-00517) with 19 single-family residential parcels. The proposed tank is 21 feet 6.5 inches in diameter and 24 feet 2 inches in height and would be painted a tan color (CWS Grouse Tan). The new tank would be constructed 12.2 feet northwest of the existing tank, which is 40 feet in diameter. The project involves minor grading and no additional tree removal. Associated new infrastructure includes a booster facility, a PG&E transformer, a 15-foot-wide paved access road, drainage facilities, 8-foot-tall fencing, and planting of replacement trees associated with tree removals due to tree health, winter storms, and subdivision construction. CalWater needs an additional water tank to meet the pressure requirements to serve the domestic water supply needs of the subdivision, as well as to provide additional redundancy in supply capacity needed when other CalWater tanks in the area require maintenance.

**RECOMMENDATION**

That the Planning Commission:

1. Adopt the Addendum to the Ascension Heights Subdivision Final Environmental Impact Report (EIR Addendum), pursuant to the California Environmental Quality Act (CEQA), and

2. Approve a Use Permit and Fence Height Exception, based on the findings contained in Attachment A.

## **SUMMARY**

Conformance with Zoning Regulations: The property is located in the R-1/S-8 Zoning District. The project meets the 20-foot front and rear and 5-foot side setbacks of the zoning district, with setbacks of over 30 feet from each property line. The proposed height of 24 feet 2 inches complies with the maximum height limit of 36 feet.

Conformance with Use Permit Findings: Section 6500(b) of the San Mateo County Zoning Regulations states that a Use Permit for a public utility or public service uses could be granted in any district “when found to be necessary for the public health, safety, convenience or welfare.” Staff has determined that the project is necessary to serve the Ascension Heights subdivision project and would provide domestic water supply and water for fire suppression to the 19 future residences. The subject Use Permit would also permit the existing water storage tank, which was not previously issued a Use Permit, as the construction of the water tank pre-dated the adoption of Section 6500 in 1960.

Conformance with Fence Height Exception Findings: The applicant proposes an 8-foot tall solid wood fence on the north and chainlink with green slats on all other sides. Placement of the 8-foot-high fence would screen views of the new and existing water tanks and associated infrastructure from future homes located on parcels which adjoin the CalWater site. The fence would not create any negative impacts to the neighborhood or to public welfare. At the time this report was written, no member of the public nor organization or association had submitted an objection to this request. Staff has added Condition 4 which requires the applicant to keep the fence height consistent at 8-feet on all sides for aesthetic reasons. The applicant has agreed to this condition.

Conformance with the California Environmental Quality Act (CEQA): As proposed and mitigated, the project would have similar, less-than-significant impacts on the resource areas of the site, as documented by the 2016 Final EIR for the Ascension Heights subdivision. The water tank project constitutes a minor change to the project evaluated in the Final EIR because the proposed changes would neither increase the severity of any impacts associated with the approved subdivision project nor result in new or substantially different environmental effects. Therefore, the project would not change the analyses or conclusions reached in the Final EIR and the impacts on the environmental topic areas covered by the Final EIR would remain less than significant. All mitigation measures in the Final EIR remain applicable to the revised project, with a minor update to an air quality mitigation measure.

The property recently experienced a loss of trees not evaluated in the 2016 FEIR, including 11 trees removed for the Ascension Heights subdivision construction, 5 trees that died, and 1 tree that declined and was removed after the winter storms. The failure of screening trees also made the project site more visible from all public vantage points.

The trees removed for subdivision construction are subject to a 3:1 replacement requirement, while trees that were removed due to health are only required to be replaced as needed for project screening. To replace the 11 trees removed for the subdivision, a total of 33 trees are required to be replaced. Proposed project replacement trees include 13 24-inch box Coast live oak trees. As discussed in Section 4.3.1 of the EIR Addendum, painting the new tank to match the existing tank and surrounding landscapes, proposed tree replacement, and construction of an 8-foot-high fence surrounding the property would adequately screen the water tank project such that aesthetic impacts would continue to be less-than-significant, and would not require additional mitigation. Per Condition 3, the additional 20 replacement trees are required by existing mitigation measures and shall be replaced as a part of the subdivision landscaping plan.

CML:cmc – CMLHH0208\_WCU.DOCX

**COUNTY OF SAN MATEO  
PLANNING AND BUILDING DEPARTMENT**

**DATE:** July 26, 2023

**TO:** Planning Commission

**FROM:** Planning Staff

**SUBJECT:** Consideration of the adoption of an Addendum to the Ascension Heights Subdivision Final Environmental Impact Report, pursuant to the California Environmental Quality Act (CEQA), and a Use Permit and Fence Height Exception, pursuant to Sections 6500 and 6412.2 of the Zoning Regulations, to allow construction of a new 58,929-gallon water storage tank and permit an existing 210,000-gallon water storage tank, along with associated infrastructure, to serve the Ascension Heights subdivision, and to allow construction of an 8-foot tall fence where 6 feet is the maximum, located at 1452 Bel Aire Road, in the San Mateo Highlands area of unincorporated San Mateo County. The project involves minor grading and no tree removal.

County File Number: PLN2021-00275 (CalWater)

**PROPOSAL**

California Water Service Company (CalWater), a private utility company, proposes to construct a new 58,929-gallon water storage tank and associated infrastructure, and permit an existing 210,000-gallon water storage tank, to serve the approved Ascension Heights subdivision (PLN 2002-00517) with 19 single-family residential parcels. The proposed tank is 21 feet 6.5 inches in diameter and 24 feet 2 inches in height and would be painted a tan color (CWS Grouse Tan). The new tank would be constructed 12.2 feet northwest of the existing tank, which is approximately 40 feet in diameter. The project involves minor grading and no tree removal. Associated new infrastructure includes a booster facility, a PG&E transformer, a 15-foot-wide paved access road, drainage facilities, 8-foot-tall fencing (including a solid wood fence on the north side and chainlink with green slats on all other sides), and planting of replacement trees associated with prior tree removals due to tree health, winter storms, and subdivision construction. CalWater needs an additional water tank to meet the pressure requirements to serve the domestic water supply needs of the subdivision, as well as to provide additional redundancy in supply capacity needed when other CalWater tanks in the area require maintenance. The existing use was not previously issued a Use Permit, as the construction of the water tank predated the adoption of Section 6500 in 1960.

## **RECOMMENDATION**

That the Planning Commission:

1. Adopt the Addendum to the Ascension Heights Subdivision Final Environmental Impact Report (EIR Addendum), pursuant to the California Environmental Quality Act (CEQA), and
2. Approve a Use Permit and Fence Height Exception, based on the findings contained in Attachment A.

## **BACKGROUND**

Report Prepared By: Camille Leung, Senior Planner

Applicant: Julie Huynh, P-3 Project Engineer, California Water Service Company (CalWater)

Owner: California Water Service Company

Public Notification: Ten (10) day advanced notification for the hearing was mailed to property owners within 300 feet of the project parcels and a notice for the hearing was posted in a newspaper (San Mateo Times) of general public circulation. The agenda was also sent to interested parties via email.

Location: The parcel is located in the unincorporated area of San Mateo County known as the San Mateo Highlands. The subject site is bordered on all sides by the Ascension Heights Subdivision property, which is bordered to the west by Bel Aire Road, Ascension Drive to the south, existing single-family development to the north and west.

APN: 041-111-020

Size: 22,500 sq. ft. parcel

Existing Zoning: R-1/S-8 (Single-Family Residential/7,500 sq. ft. minimum lot size)

General Plan Designation: Low Density Residential (0.3-2.3 du/net ac)

Sphere-of-Influence: City of San Mateo

Existing Land Use: Utility use; Existing potable water tank with several cellular communications facilities established on the parcel.

Flood Zone: Zone X, Area of Minimal Flood Hazard

Environmental Evaluation: Pursuant to CEQA Guidelines Section 51564, the County prepared an EIR Addendum to the Final Environmental Impact Report (Final EIR) that was certified by the Board of Supervisors on February 9, 2016. The EIR Addendum was posted on June 15, 2023 on the County’s website with a 2-week courtesy review period. The EIR Addendum demonstrates that none of the conditions described in CEQA Guidelines Section 15162 requiring preparation of a subsequent EIR are present, and that no further environmental review is required.

Setting: The site is relatively flat and surrounded on all sides by the approximately 13.25-acres (gross) Ascension Heights Subdivision site, located at the northeast corner of the intersection of Bel Aire Road and Ascension Drive. The Ascension Heights Subdivision site is surrounded by single-family dwellings, including the Baywood Park neighborhood to the northeast, the Enchanted Hills neighborhood to the southeast and southwest, and the Starlite Heights neighborhood to the northwest. The College of San Mateo campus is located less than 1/4-mile northeast of the site via Parrott Drive.

Chronology:

<u>Date</u>	<u>Action</u>
Late 1950’s	- Construction of existing 210,000-gallon water storage tank. County regulations did not require a Use Permit at the time.
February 9, 2016	- Board of Supervisors approved the Ascension Heights Subdivision (PLN 2002-00517) project, including certifying the Final Environmental Impact Report (Final EIR) for the Ascension Heights Subdivision Project (Approved Subdivision Project; State Clearinghouse No. 2013102009). The Final EIR did not include discussion of the subject proposal.
March 2016	- Petition for judicial review of approval filed.
May 2018	- Court of Appeal decision upholding County approval.
July 28, 2020	- Building permit issued with grading hard card to begin grading operations for approved subdivision.
July 20, 2021	- Use Permit application submitted.
June 5, 2023	- Applicant submits landscaping plan. Application was incomplete up to this date.
June 15, 2023	- Release of Addendum to the Ascension Heights Subdivision Final Environmental Impact Report (EIR Addendum); followed by 2-week courtesy review period.

**DISCUSSION**

A. **KEY ISSUES**

1. **Conformance with the County General Plan**

Upon review of the applicable provisions of the General Plan, staff has determined that the project complies with all applicable General Plan Policies, including the following:

Visual Quality Policy 4.14(a) (*Appearance of New Development*) requires development to promote and enhance good design, site relationships, and other aesthetic considerations. The proposed water storage tank will match the color of the existing water storage tank (CWS Grouse Tan), which is compatible with the dry grass landscape of the region. The proposed tank is 21 feet 6.5 inches in diameter and 24 feet 2 inches in height, matching the height of the existing tank. As discussed in Section 4.3.1 of the EIR Addendum, the new water storage tank would be screened by replacement trees (that were required due to prior tree removals due to tree health, winter storms, and subdivision construction), and a new 8-foot-high fence. Proposed replacement trees include 13 24-inch box Coast live oak trees.

Water Supply Policy 10.4 (*Development of Water Supplies*) calls for the County to promote the development of water supplies to serve: (1) agricultural uses, as the highest priority; (2) domestic uses; and (3) recreational uses. Water Supply Policy 10.13 (*Water Systems in Unincorporated Areas*) calls for the County to support efforts to improve water distribution and storage systems in unincorporated neighborhoods and communities. The project would support approved residential development within the Ascension Heights subdivision property.

2. **Conformance with Zoning Regulations**

*Permitted/Conditional Uses*

Pursuant to Section 6500(b) of the San Mateo County Zoning Regulations, public utility or public service uses are allowed in any district, subject to the approval of a use permit. Construction of the existing 210,000-gallon water storage tank occurred in the late 1950's; the use was not previously issued a Use Permit, as the construction of the water tank pre-dated the adoption of Section 6500 in 1960.

*Development Standards of the S-8 Combining District*

The property is located in the R-1/S-8 Zoning District. The project meets the 20-foot front and rear and 5-foot side setbacks of the zoning district, with setbacks of over 30 feet from each property line. The proposed height of 24 feet 2 inches complies with the maximum height limit of 36 feet.

3. Conformance with Use Permit Findings

CalWater needs an additional water tank to meet the pressure requirements to serve the domestic water supply needs of the Ascension Heights subdivision, as well as to provide additional redundancy in supply needed when other CalWater tanks in the area require maintenance. The existing water tank use was not previously issued a Use Permit, as the construction of the water tank pre-dated the adoption of Section 6500 in 1960, thus the subject Use Permit also includes the existing tank.

Section 6500(b) of the San Mateo County Zoning Regulations states that a Use Permit for public utility or public service uses may be granted in any district “when found to be necessary for the public health, safety, convenience or welfare.” Staff has determined that the project is necessary to serve the Ascension Heights subdivision project and would provide domestic water supply and water for fire suppression to the 19 future residences.

Additionally, Section 6503 requires that the Planning Commission find that “the establishment, maintenance and/or conducting of the use will not, under the circumstances of the particular case, result in a significant adverse impact to coastal resources, or be detrimental to the public welfare or injurious to property or improvements in said neighborhood.” As discussed, the existing and proposed water tanks are needed for domestic water supply and fire suppression for existing development in the area and for approved subdivision development. Potential environmental impacts of the new water tank were evaluated in the EIR Addendum, which concluded that the project would not result in any new or more severe environmental impacts not already disclosed in the Final EIR for the subdivision, and that no new mitigation measures are needed for the water tank project. The site is not located in the coastal zone and will not have impacts to coastal resources.

4. Conformance with Fence Height Exception Findings

The applicant proposes an 8-foot high solid wood fence on the north side only of the project site and plans to construct a 6-foot-tall chain link fence with green slats on the west, east, and south sides of the property. Section 6412.2 of the Zoning Regulations allows fences or hedges, on parcels located outside the Coastal Zone, to exceed the height limits set forth in Section 6412, a maximum of 6-feet, by up to two (2) feet, providing the project meets the following requirements (as discussed below):



- (1) Written notification of the exception request is sent to all owners of property located within 300 feet of the parcel where the fence or hedge is proposed to be placed, and to any member of the public requesting such notification: The required noticing was completed.
- (2) Written notification of the exception request is sent to all recognized organizations or associations that have been established to represent the property owners in the neighborhood surrounding the parcel where the fence or hedge is proposed to be placed, and to any organization or association requesting such notification. An organization or association shall be considered recognized if it has been in existence for at least six months and has scheduled meetings: The Highlands Community Association has been included in the project noticing.
- (3) No member of public nor organization or association has submitted to the Planning Director written objection to the exception request: As of the time this report was written, no member of public nor organization or association had submitted an objection to this request.
- (4) After consultation with the Director of Public Works, the Planning Director finds that approving the exception will not jeopardize public safety: Not applicable; the property does not adjoin any public right-of-way.
- (5) After viewing the parcel where the fence or hedge is proposed, the Planning Director finds that approving the exception will be compatible with the neighborhood surrounding that parcel and will not be detrimental to the public welfare: The placement of the 8-foot-high fence would screen views of the new and existing water tanks and associated infrastructure from future homes located on parcels which adjoin the CalWater site. The fence would not create any negative impacts to the neighborhood or to public welfare.
- (6) The Planning Commission finds that the proposed fence or hedge promotes or enhances good design, site relationships and other aesthetic considerations, in accordance with San Mateo County General Plan Policy 4.14. In order to make this determination, the Planning Director may condition the exception with certain requirements, including design, location, materials, colors, and landscaping requirements: As proposed, the applicant seeks an 8-foot-high solid wood fence on the north side only of the project site and plans to construct a 6-foot-tall chain link fence with green slats on the west, east, and south sides of the property. Staff has added Condition 4 which requires the applicant to keep the fence height

consistent at 8 feet on all sides for aesthetic reasons, such that the appearance of the fence is more consistent on all sides. The applicant has agreed to this condition. As discussed in Section 4.3.1 of the EIR Addendum, painting of the new tank to match the existing tank and surrounding landscapes, proposed tree planting, and construction of an 8-foot-high fence surrounding the property, would adequately screen the project, such that aesthetic impacts would remain less-than-significant, and would not require additional mitigation.

## B. ENVIRONMENTAL REVIEW

An Addendum to the 2016 Ascension Heights Subdivision Final Environmental Impact Report (EIR Addendum) has been prepared by the County's environmental consultant, SWCA, to evaluate whether the modifications to the Approved Subdivision Project evaluated in the 2016 EIR require the preparation of a subsequent EIR due to the potential for new or more severe environmental impacts. The scope of the Addendum focuses on the environmental effects associated with specific additions to the water supply component of the Approved Subdivision Project. Project modifications would not result in new significant impacts or a substantial increase in the severity of a previously identified significant impact; therefore, preparation of a supplemental or subsequent EIR is not required.

The EIR Addendum is an addendum to the Final Environmental Impact Report (FEIR) that was certified by the Board of Supervisors on February 9, 2016. Section 15164 of the CEQA Guidelines states that an addendum need not be circulated for public review, however, the EIR Addendum was posted on June 15, 2023 on the County's website with a 2-week courtesy review period.

As proposed and mitigated, the water tank project would have similar, less-than-significant impacts on the resource areas evaluated in the 2016 Final Environmental Impact Report. The water tank project constitutes a minor change to the Approved Subdivision Project evaluated in the Final EIR because the proposed changes would neither increase the severity of any impacts associated with the Approved Subdivision Project nor result in new or substantially different environmental effects. Therefore, the project would not change the analyses or conclusions reached in the Final EIR and the impacts on the environmental topic areas covered in the Final EIR would remain less than significant. All mitigation measures in the Final EIR remain applicable to the revised project, with a minor update to an air quality mitigation measure to accommodate the project revisions, as described below:

Mitigation 4.2-1b is revised as shown below to reflect regulatory updates to air quality best management practices that have taken effect since certification of the Final EIR, and now apply to the project.

**Mitigation Measure 4.2-1b:** *The project applicant shall ensure through contractual obligations with construction contractors that the following Best Management Practices (BMPs) shall be implemented during all stages of construction:*

- *All heavy-duty construction equipment be equipped with diesel particulate matter filters.*
- *Only low ROG coatings shall be utilized.*
- *~~The applicant shall use only Tier 2 or better heavy-duty construction equipment.~~ The project applicant shall use Tier 4 Interim engines for all 75 horsepower or greater diesel-powered equipment, except where the project applicant establishes to the satisfaction of the County that Tier 4 Interim equipment is not available.*

#### *Discussion of Potential Aesthetic Impacts*

The property recently experienced a loss of trees not evaluated in the 2016 FEIR, including 11 trees removed for the Ascension Heights subdivision construction, 5 trees that died, and 1 tree that declined and was removed after the winter storms. The failure of screening trees also made the project site more visible from all public vantage points. The trees removed for subdivision construction are subject to a 3:1 replacement requirement, while trees that were removed due to health are only required to be replaced as needed for project screening. To replace the 11 trees removed for the subdivision, a total of 33 trees are required to be replaced. Proposed project replacement trees include 13 24-inch box Coast live oak trees. As discussed in Section 4.3.1 of the EIR Addendum, painting the new tank to match the existing tank and surrounding landscapes, proposed tree replacement, and construction of an 8-foot-high fence surrounding the property would adequately screen the water tank project such that aesthetic impacts would continue to be less-than-significant, and would not require additional mitigation. Per Condition 3, the additional 20 replacement trees are required by existing mitigation measures and shall be replaced as a part of the subdivision landscaping plan.

#### C. REVIEWING AGENCIES

Building Inspection Section  
Geotechnical Section  
Drainage Section  
San Mateo County Fire Department

## **ATTACHMENTS**

- A. Recommended Findings and Conditions of Approval
- B. Vicinity Map
- C. Project Plans
- D. EIR Addendum, dated June 15, 2023

CML:cmc – CMLHH0209\_WCU.DOCX

County of San Mateo  
Planning and Building Department

**RECOMMENDED FINDINGS AND CONDITIONS OF APPROVAL**

Permit or Project File Number: PLN 2021-00275

Hearing Date: July 26, 2023

Prepared By: Camille Leung, Senior Planner For Adoption By: Planning Commission

**RECOMMENDED FINDINGS**

Regarding the Environmental Review, Find:

1. That the EIR Addendum to the Final EIR evaluates possible new or significant impacts resulting from changes to the project, and based on the results of the evaluation, provides substantial evidence that there are no new significant impacts or previously identified significant impacts made more severe which would result from the proposed project modifications.
2. That the Planning Commission has considered the EIR Addendum with the Final EIR prior to making a decision on the project and the EIR Addendum reflects the independent judgement of San Mateo County.
3. That none of the conditions described in CEQA Guidelines Section 15162 have occurred as a result of project modifications and no subsequent environmental review is required.

Regarding the Use Permit, Find:

4. That the public utility or public service use is necessary for the public health, safety, convenience or welfare. Staff has determined that the project is necessary to serve the Ascension Heights subdivision project and would provide domestic water supply and water for fire suppression to the 19 future residences.
5. That the establishment, maintenance and/or conducting of the use will not, under the circumstances of the particular case, result in a significant adverse impact to coastal resources, or be detrimental to the public welfare or injurious to property or improvements in said neighborhood. The existing and proposed water tanks are needed for domestic water supply and fire suppression for existing development in the area and for approved subdivision development. Potential environmental impacts of the new water tank are discussed in the EIR Addendum,

which demonstrates that the project would not result in any new or more severe impacts, and therefore, no new mitigation measures are needed. The site is not located in the coastal zone and will not have impacts to coastal resources.

## **RECOMMENDED CONDITIONS OF APPROVAL**

### **Current Planning Section**

1. The project shall be constructed in compliance with the plans approved by the Planning Commission on July 26, 2023. Minor modifications to the project may be approved by the Community Development Director if they are consistent with the intent of, and are in substantial conformance with, this approval. Major modifications, as determined by the Community Development Director, are subject to review and approval of the Planning Commission.
2. The Use Permit (UP) and Fence Height Exception (FHE) shall be valid for five (5) years from the date of approval, in which time a building permit shall be issued, and a completed inspection (to the satisfaction of the Building Inspector) shall have occurred within 180 days of issuance of the building permit. The UP and FHE approvals may be extended by a 1-year increment with submittal of an application for permit extension and payment of applicable extension fees sixty (60) days prior to the expiration date.
3. At the time of building permit application, the applicant shall submit building plans consistent with the approved plans, including landscaping. Trees planted on the north side shall be a minimum of 25 feet at maturity. The applicant shall work with the developer of the Ascension Heights Subdivision to plant the additional 20 replacement trees as required by existing mitigation measures. Compliance shall be confirmed prior to Planning approval of the building permit for the subdivision landscape plan under BLD 2018-00991.
4. Prior to final approval of the new water tank, the property owner shall install all approved screening landscaping (including 13 24-inch box Coast live oak trees), an 8-foot-tall solid wood fence on the north side of the property, and an 8-foot-tall chain link fence with green slats surrounding the remainder of the property.
5. Landscaping shall be maintained in perpetuity.
6. The applicant shall comply with the mitigation measures set forth in the Revised Mitigation Monitoring and Reporting Program in Appendix E of the EIR Addendum.

### **Building Inspection Section**

7. All buildings that have a street address shall have the number of that address on the building, mailbox, or other type of sign at the driveway entrance in such a

manner that the number is easily and clearly visible from either direction of travel from the street. New residential buildings shall have internally illuminated address numbers contrasting with the background so as to be seen from the public way fronting the building. Residential address numbers shall be at least 6 ft. above the finished surface of the driveway. An address sign shall be placed at each break of the road where deemed applicable by the San Mateo County Fire Department. Numerals shall be contrasting in color to their background and shall be no less than 4 inches in height and have a minimum 1/2-inch stroke. Remote signage shall be a 6-inch by 18-inch green reflective metal sign.

### Geotechnical Section

8. A Geotechnical Report shall be submitted at Building Stage; the report shall be updated to the current adopted code.

### Drainage Section

9. Project requires a building permit. At the time of building permit submittal, stamped and signed engineered plans and any required supplemental documentation must be provided.

### San Mateo County Fire Department

All fire conditions and requirements must be incorporated into your building plans prior to building permit issuance. It is your responsibility to notify your contractor, architect and engineer of these requirements.

10. Address numbers shall be a minimum of 6-inch in height on contrasting background and be visible from the road in the direction of travel. Finished height of bottom of address shall not be greater than 6 feet. Remote addressing may be required at the driveway or road entrance at intersections and road forks and shall be visible from both directions. Numbers shall be reflective and contrasting background. Equivalent to "Hy-Ko 911" signage with minimum 3-inch numbers. CFC 505.1
11. Existing private access road must be maintained. All potholes and any damaged roadway must be filled and compacted to 95% able to support fire apparatus weighing 75,000 lbs. Gravel road access shall be certified by an engineer as to the compaction and weight it will support.
12. A fuel break of defensible space is required around the perimeter of all structures, existing and new, to a distance of not less than 30 feet and may be required to a distance of 100 feet or to the property line. This is neither a requirement nor an authorization for the removal of living trees.

13. Trees located within the defensible space shall be pruned to remove dead and dying portions, and limbed up 6 feet above the ground. New trees planted in the defensible space shall be located no closer than 10 feet to adjacent trees when fully grown or at maturity.
14. A Knox padlock or key switch will be required if there is limited access to property. CFC 506.1. For application and instructions, please email [smcfdfiremarshal@fire.ca.gov](mailto:smcfdfiremarshal@fire.ca.gov). if you need further assistance, please contact the San Mateo County Fire Marshal's Office at 650/573-3846.
15. Gates shall be a minimum of 2 feet wider than the access road/driveway they serve. Overhead gate structures shall have a minimum of 15 feet of vertical clearance. Locked gates shall be provided with a Knox Box or Knox Padlock. Electric gates shall have a Knox Key Switch. Electric gates shall automatically open during power failures. CFC 503.6, 506. For application and instructions please email [smcfdfiremarshal@fire.ca.gov](mailto:smcfdfiremarshal@fire.ca.gov) if you need further assistance, please contact the San Mateo County Fire Marshal's Office at 650/573-3846.


CML:cmc – CMLHH0209\_WCU.DOCX





**COUNTY OF SAN MATEO - PLANNING AND BUILDING DEPARTMENT**

# **ATTACHMENT B**



**Figure 1. Project Location**



Figure 2. Project Area



**COUNTY OF SAN MATEO - PLANNING AND BUILDING DEPARTMENT**



**ATTACHMENT C**

# CALWATER TANK - DRAINAGE & TREATMENT PLAN BEL AIRE ROAD SAN MATEO, CALIFORNIA



## LEGEND

EXISTING	PROPOSED	DESCRIPTION
- - - - -	- - - - -	BOUNDARY
- - - - -	- - - - -	PROPERTY LINE
- - - - -	- - - - -	RETAINING WALL
- - - - -	- - - - -	LANDSCAPE RETAINING WALL
- - - - -	- - - - -	RAINWATER TIGHTLINE
- - - - -	- - - - -	SUBDRAIN LINE
- - - - -	- - - - -	TIGHTLINE
- - - - -	- - - - -	STORM DRAIN LINE
- - - - -	- - - - -	SANITARY SEWER LINE
- - - - -	- - - - -	WATER LINE
- - - - -	- - - - -	GAS LINE
- - - - -	- - - - -	PRESSURE LINE
- - - - -	- - - - -	JOINT TRENCH
- - - - -	- - - - -	SET BACK LINE
- - - - -	- - - - -	CONCRETE VALLEY GUTTER
- - - - -	- - - - -	EARTHEN SWALE
CB	CB	CATCH BASIN
JB	JB	JUNCTION BOX
Ad	Ad	AREA DRAIN
SDMH	SDMH	CURB INLET
SSMH	SSMH	STORM DRAIN MANHOLE
222.57 INV	222.57 INV	FIRE HYDRANT
222.57 INV	222.57 INV	SANITARY SEWER MANHOLE
200	200	STREET SIGN
200	200	SPOT ELEVATION
200	200	FLOW DIRECTION
200	200	DEMOLISH/REMOVE
200	200	BENCHMARK
200	200	CONTOURS
200	200	TREE TO BE REMOVED



## ABBREVIATIONS

AB	AGGREGATE BASE	MAX	MAXIMUM
AC	ASPHALT CONCRETE	MH	MANHOLE
ACC	ACCESSIBLE	MIN	MINIMUM
AD	AREA DRAIN	MON.	MONUMENT
BC	BEGINNING OF CURVE	MRO	METERED RELEASE OUTLET
B & D	BEARING & DISTANCE	(N)	NEW
BM	BENCHMARK	NO.	NUMBER
BIO	BIORETENTION AREA	NTS	NOT TO SCALE
BUB	BUBBLER BOX	O.C.	ON CENTER
BW/FG	BOTTOM OF WALL/FINISH GRADE	O/P	OVER
CB	CATCH BASIN	(PA)	PLANTING AREA
C & G	CURB AND GUTTER	PE	PEDESTRIAN
CPP	CORRUGATED PLASTIC PIPE (SMOOTH INTERIOR)	PIV	POST INDICATOR VALVE
CO	CLEANOUT	PSS	PUBLIC SERVICES EASEMENT
COTG	CLEANOUT TO GRADE	R	PROPERTY LINE
CONC	CONCRETE	PP	POWER POLE
CONST	CONSTRUCT or -TION	PUE	PUBLIC UTILITY EASEMENT
CONC COR	CONCRETE CORNER	PVC	POLYVINYL CHLORIDE
CY	CUBIC YARD	R	RADIUS
D	DIAMETER	RCP	REINFORCED CONCRETE PIPE
DI	DROP INLET	RIM	RIM ELEVATION
DIP	DUCTILE IRON PIPE	RW	RAINWATER
EA	EACH	R/W	RIGHT OF WAY
EC	END OF CURVE	S	SLOPE
EG	EXISTING GRADE	S.A.D.	SEE ARCHITECTURAL DRAWINGS
EL	ELEVATIONS	SAN	SANITARY
EQ	EDGE OF PAVEMENT	SD	STORM DRAIN
EW	EQUIPMENT	SDMH	STORM DRAIN MANHOLE
(E)	EXISTING	SHT	SHEET
FC	FACE OF CURB	SI	STREET INLET
FF	FINISHED FLOOR	S.L.D.	SEE LANDSCAPE DRAWINGS
FG	FINISHED GRADE	SPEC	SPECIFICATION
FH	FIRE HYDRANT	SS	SANITARY SEWER
FL	FLOW LINE	SSCO	SANITARY SEWER CLEANOUT
FS	FINISHED SURFACE	SSMH	SANITARY SEWER MANHOLE
G	GAS	ST	STREET
GA	GAGE OR GAUGE	STA	STATION
GB	GRADE BREAK	STD	STANDARD
HDPE	HIGH DENSITY CORRUGATED POLYETHYLENE PIPE	STRUCT	STRUCTURAL
HORIZ	HORIZONTAL	T	TELEPHONE
HI PT	HIGH POINT	TC	TOP OF CURB
H&T	HUB & TACK	TEMP	TEMPORARY
ID	INSIDE DIAMETER	TOW	TOP OF WALL
INV	INVERT ELEVATION	TP	TOP OF PAVEMENT
JB	JUNCTION BOX	TW/FG	TOP OF WALL/FINISH GRADE
JT	JOINT TRENCH	TP	TYPICAL
JP	JOINT UTILITY POLE	VC	VERTICAL CURVE
L	LENGTH	VCP	VITRIFIED CLAY PIPE
LNDG	LANDING	VERT	VERTICAL
LF	LINEAR FEET	W/ WL	WITH WATER LINE
		WM	WATER METER
		WWF	WELDED WIRE FABRIC

## NOTES

ALL DISTANCES AND DIMENSIONS ARE IN FEET AND DECIMALS.

UNDERGROUND UTILITY LOCATION IS BASED ON SURFACE EVIDENCE.

BUILDING FOOTPRINTS ARE SHOWN TO FINISHED MATERIAL (STUCCO/SIDING) AT GROUND LEVEL.

FINISH FLOOR ELEVATIONS ARE TAKEN AT DOOR THRESHOLD (EXTERIOR).

## EASEMENT NOTE

A CURRENT TITLE REPORT FOR THE SUBJECT PROPERTY HAS NOT BEEN EXAMINED BY LEA & BRAZE ENGINEERING, INC. EASEMENTS OF RECORD MAY EXIST THAT ARE NOT SHOWN ON THIS MAP.

EASEMENTS SHOWN PER ADJOINING SUBDIVISIONS.

## SITE BENCHMARK

SURVEY CONTROL POINT  
MAG AND SHINER SET IN ASPHALT  
ELEVATION = 587.30'  
(ASSUMED)

## PROJECT INFORMATION

AREA:	0.52±ACRES
ASSESSOR'S PARCEL NOS:	041-111-020
<b>UTILITY SERVICES:</b>	
STORM DRAIN:	SAN MATEO COUNTY
SANITARY SEWER:	SAN MATEO COUNTY
WATER:	CALIFORNIA WATER SERVICES
FIRE:	SAN MATEO COUNTY FIRE SERVICE
CABLE:	COMCAST
GAS & ELECTRICAL:	PACIFIC GAS & ELECTRIC (PG&E)
TELEPHONE:	AT&T



## OWNER'S INFORMATION

OWNER:  
CALIFORNIA WATER SERVICES  
408-367-8394

## REFERENCES

- THIS GRADING AND DRAINAGE PLAN IS SUPPLEMENTAL TO:
- TOPOGRAPHIC SURVEY BY LEA & BRAZE ENGINEERING, INC. ENTITLED: "TOPOGRAPHIC SURVEY" BEL AIRE DRIVE SAN MATEO, CA JOB#2161284 DATED: 9-20-17
  - SOIL REPORT BY MICHELUCCI & ASSOCIATES, INC. ENTITLED: "GEO TECHNICAL & ENGINEERING GEOLOGIC INVESTIGATION" PROPOSED ASCENSION HEIGHTS SUBDIVISION SAN MATEO COUNTY, CA JOB# 01-3186 DATE: DECEMBER 16, 2002 REVISED DATE: DECEMBER 5, 2013 SUPPLEMENT TO REPORT: AUGUST 24, 2018
  - SITE PLAN BY CALIFORNIA WATER SERVICE ENTITLED: "STATION 031 - ASCENSION DR & BEL AIR RD INSTALL TANK AND BOOSTER PUMP" BEL AIRE DRIVE SAN MATEO, CA DATED: 04-07-21

THE CONTRACTOR SHALL REFER TO THE ABOVE NOTED SURVEY AND PLAN, AND SHALL VERIFY BOTH EXISTING AND PROPOSED ITEMS ACCORDING TO THEM.

**CONTRACTOR COURTESY NOTE:**  
CONTRACTOR TO PROVIDE 72-HOUR COURTESY NOTICE FOR NOISE AND DUST (INCLUDING POINT OF CONTACT) TO COMMUNITY PRIOR TO COMMENCEMENT OF OPERATIONS.

**NOTE:**  
**FOR CONSTRUCTION STAKING SCHEDULING OR QUOTATIONS PLEASE CONTACT ALEX ABAYA AT LEA & BRAZE ENGINEERING (510)887-4086 EXT 116.**  
aabaya@leabrazze.com

## SHEET INDEX

DTP-1.0	TITLE SHEET
DTP-2.0	DRAINAGE & TREATMENT PLAN
DTP-3.0	DETAILS
DTP-4.0	SPECIFICATIONS
ER-1	EROSION CONTROL PLAN
ER-2	EROSION CONTROL DETAILS
BMP	BEST MANAGEMENT PRACTICES

**LEA & BRAZE ENGINEERING, INC.**  
CIVIL ENGINEERS • LAND SURVEYORS  
SACRAMENTO REGION  
BAY AREA REGION  
HAWAII REGION  
SAN FRANCISCO OFFICE  
SAN MATEO OFFICE  
ROSELVILLE OFFICE  
(P) (916) 966-1338  
(F) (916) 887-3019  
WWW.LEABRAZE.COM




**CALWATER TANK  
DRAINAGE & TREATMENT PLAN  
SAN MATEO, CALIFORNIA**  
(UNINCORPORATED) SAN MATEO COUNTY

TITLE SHEET

REVISIONS	BY

JOB NO: 2161285  
DATE: 02-01-23  
SCALE: AS NOTED  
DESIGN BY: AH  
DRAWN BY: MCF  
SHEET NO:

**DTP-1.0**



- STORM DRAIN KEYNOTES 1 TO 6**
- 1 INSTALL (N) ON-SITE STORM DRAIN SYSTEM. USE MINIMUM 6" HDPE (ADS N-12 W/ SMOOTH INTERIOR WALLS). MAINTAIN 24" MINIMUM COVER AND SLOPED AT 1% MINIMUM AT ALL TIMES UNLESS OTHERWISE NOTED. PROVIDE CLEANOUT TO GRADE AT MAJOR CHANGES IN DIRECTION. AVOID USING 90° BENDS AND INSTEAD USE (2) 45° BENDS AND WYE CONNECTIONS.
  - 2 INSTALL (N) SUBDRAIN. USE PERFORATED 4" PVC (SDR-35) WITH HOLES DOWN AND SLOPED AT 1% MINIMUM SURROUND WITH 3/4" DRAIN ROCK WRAPPED IN FILTER FABRIC (MIRAFI 140N). MIRADRAIN OR OTHER LEA & BRAZE PREAPPROVED DRAINAGE SYSTEM MAY ALSO BE USED. AVOID USING 90° BENDS AND INSTEAD USE (2) 45° BENDS AND WYE CONNECTIONS. PROVIDE CLEANOUT TO GRADE AT MAJOR CHANGES IN DIRECTION AND AT 100' MAXIMUM INTERVALS. SUBDRAIN SHALL REMAIN A DEDICATED SEPARATE SYSTEM UNTIL IT CONNECTS TO STORM DRAIN SYSTEM OR OUTFALL AS SHOWN.
  - 3 CONSTRUCT (N) DRAINAGE DEPRESSION SWALE SLOPED AT 1% MINIMUM TOWARDS POSITIVE OUTFALL. SEE DETAIL 2 ON SHEET DTP-3.0.
  - 4 INSTALL (N) 'CHRISTY V-12' CATCH BASIN W/ CONCRETE BOTTOM FLUSH W/ LOWEST OUTGOING INVERT. PLACE BOX ON 6" CLASS 2 AGGREGATE BASE MATERIAL. SEE DETAIL 1 ON SHEET DTP-3.0.
  - 5 INSTALL (N) BIO-RETENTION POND PER SAN MATEO COUNTY C-3/C-6 MANUAL. SEE DETAIL 3 ON SHEET DTP-3.0.
  - 6 INSTALL (N) PIPE CROSSING PROTECTION PER DETAIL 4 ON SHEET DTP-3.0.

**NOTE:**  
FOR CONSTRUCTION STAKING SCHEDULING OR QUOTATIONS PLEASE CONTACT ALEX ABBAYA AT LEA & BRAZE ENGINEERING (510)887-4086 EXT 116. aabaya@leabraze.com

**\* BUILDING PAD NOTE:**  
ADJUST PAD LEVEL AS REQUIRED. REFER TO STRUCTURAL PLANS FOR SLAB SECTION OR CRAWL SPACE DEPTH TO ESTABLISH PAD LEVEL.




**LEA & BRAZE ENGINEERING, INC.**  
CIVIL ENGINEERS • LAND SURVEYORS  
SACRAMENTO REGION  
BAY AREA REGION  
SUNOLTA REGION  
SACRAMENTO, CALIFORNIA 95615  
HAYWARD, CALIFORNIA 94545  
ROSELLE, CALIFORNIA 95661  
(P) (510) 887-4086 (F) (916) 966-1338  
(F) (510) 887-3019 (F) (916) 797-1363  
WWW.LEABRAZE.COM

**CALWATER TANK  
DRAINAGE & TREATMENT PLAN  
SAN MATEO, CALIFORNIA**  
(UNINCORPORATED) SAN MATEO COUNTY


**DRAINAGE &  
TREATMENT PLAN**

REVISIONS	BY


JOB NO: 2161285  
DATE: 02-01-23  
SCALE: AS NOTED  
DESIGN BY: AH  
DRAWN BY: MCF  
SHEET NO:




1 CATCH BASIN  
DTP-3.0 NTS




4 PIPE CROSSING  
DTP-3.0 NTS



2 DRAINAGE DEPRESSION SWALE DETAIL  
DTP-3.0 NTS



3 BIO-TREATMENT AREA  
DTP-3.0 NTS



**LEA & BRAZE ENGINEERING, INC.**  
CIVIL ENGINEERS • LAND SURVEYORS  
SACRAMENTO REGION  
1000 J STREET, SUITE 300  
ROSELAND, CALIFORNIA 94661  
(P) (916) 966-1338  
(F) (916) 887-3019  
WWW.LEA-BRAZE.COM

CALWATER TANK  
DRAINAGE & TREATMENT PLAN  
SAN MATEO, CALIFORNIA  
(UNINCORPORATED) SAN MATEO COUNTY

DETAILS

REVISIONS	BY

JOB NO: 2161285

DATE: 02-01-23

SCALE: NTS

DESIGN BY: AH

DRAWN BY: MCF

SHEET NO:

**DTP-3.0**

3 OF 7 SHEETS





**PURPOSE:**

THE PURPOSE OF THIS PLAN IS TO STABILIZE THE SITE TO PREVENT EROSION OF GRADED AREAS AND TO PREVENT SEDIMENTATION FROM LEAVING THE CONSTRUCTION AREA AND AFFECTING NEIGHBORING SITES, NATURAL AREAS, PUBLIC FACILITIES OR ANY OTHER AREA THAT MIGHT BE AFFECTED BY SEDIMENTATION. ALL MEASURES SHOWN ON THIS PLAN SHOULD BE CONSIDERED THE MINIMUM REQUIREMENTS NECESSARY. SHOULD FIELD CONDITIONS DICTATE ADDITIONAL MEASURES, SUCH MEASURES SHALL BE PER CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL AND THE CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION. LEA & BRAZE ENGINEERING SHOULD BE NOTIFIED IMMEDIATELY SHOULD CONDITIONS CHANGE.

**EROSION CONTROL NOTES:**

- IT SHALL BE THE OWNER'S/CONTRACTOR'S RESPONSIBILITY TO MAINTAIN CONTROL OF THE ENTIRE CONSTRUCTION OPERATION AND TO KEEP THE ENTIRE SITE IN COMPLIANCE WITH THIS EROSION CONTROL PLAN.
- THE INTENTION OF THIS PLAN IS FOR INTERIM EROSION AND SEDIMENT CONTROL ONLY. ALL EROSION CONTROL MEASURES SHALL CONFORM TO CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL, THE CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION, AND THE LOCAL GOVERNING AGENCY FOR THIS PROJECT.
- OWNER/CONTRACTOR SHALL BE RESPONSIBLE FOR MONITORING EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO, DURING, AND AFTER STORM EVENTS. PERSON IN CHARGE OF MAINTAINING EROSION CONTROL MEASURES SHOULD WATCH LOCAL WEATHER REPORTS AND ACT APPROPRIATELY TO MAKE SURE ALL NECESSARY MEASURES ARE IN PLACE.
- SANITARY FACILITIES SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
- DURING THE RAINY SEASON, ALL PAVED AREAS SHALL BE KEPT CLEAR OF EARTH MATERIAL AND DEBRIS. THE SITE SHALL BE MAINTAINED SO AS TO MINIMIZE SEDIMENTATION RUNOFF TO ANY STORM DRAINAGE SYSTEM, INCLUDING EXISTING DRAINAGE SWALES AND WATERCOURSES.
- CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION AND WATER POLLUTION WILL BE MINIMIZED. COMPLIANCE WITH FEDERAL, STATE AND LOCAL LAWS CONCERNING POLLUTION SHALL BE MAINTAINED AT ALL TIMES.
- CONTRACTOR SHALL PROVIDE DUST CONTROL AS REQUIRED BY THE APPROPRIATE FEDERAL, STATE AND LOCAL AGENCY REQUIREMENTS.
- ALL MATERIALS NECESSARY FOR THE APPROVED EROSION CONTROL MEASURES SHALL BE IN PLACE BY OCTOBER 15TH.
- EROSION CONTROL SYSTEMS SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE RAINY SEASON, OR FROM OCTOBER 15TH THROUGH APRIL 15TH, WHICHEVER IS LONGER.
- IN THE EVENT OF RAIN, ALL GRADING WORK IS TO CEASE IMMEDIATELY AND THE SITE IS TO BE SEALED IN ACCORDANCE WITH THE APPROVAL EROSION CONTROL MEASURES AND APPROVED EROSION CONTROL PLAN.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR CHECKING AND REPAIRING EROSION CONTROL SYSTEMS AFTER EACH STORM.
- ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY LOCAL JURISDICTION'S ENGINEERING DEPARTMENT OR BUILDING OFFICIALS.
- MEASURES SHALL BE TAKEN TO COLLECT OR CLEAN ANY ACCUMULATION OR DEPOSIT OF DIRT, MUD, SAND, ROCKS, GRAVEL OR DEBRIS ON THE SURFACE OF ANY STREET, ALLEY OR PUBLIC PLACE OR IN ANY PUBLIC STORM DRAIN SYSTEMS. THE REMOVAL OF AFORESAID SHALL BE DONE BY STREET SWEEPING OR HAND SWEEPING. WATER SHALL NOT BE USED TO WASH SEDIMENTS INTO PUBLIC OR PRIVATE DRAINAGE FACILITIES.
- EROSION CONTROL MEASURES SHALL BE ON-SITE FROM SEPTEMBER 15TH THRU APRIL 15TH.
- ALL EROSION CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE RAINY SEASON OR FROM OCTOBER 15TH THROUGH APRIL 15TH, WHICHEVER IS GREATER.
- PLANS SHALL BE DESIGNED TO MEET C3 REQUIREMENTS OF THE MUNICIPAL STORMWATER REGIONAL PERMIT("MRP") NPDES PERMIT CAS 612008.
- THE CONTRACTOR TO NPDES (NATIONAL POLLUTION DISCHARGE ELIMINATION SYSTEM) BEST MANAGEMENT PRACTICES (BMP) FOR SEDIMENTATION PREVENTION AND EROSION CONTROL TO PREVENT DELETERIOUS MATERIALS OR POLLUTANTS FROM ENTERING THE TOWN OR COUNTY STORM DRAIN SYSTEMS.
- THE CONTRACTOR MUST INSTALL ALL EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO THE INCEPTION OF ANY WORK ONSITE AND MAINTAIN THE MEASURES UNTIL THE COMPLETION OF ALL LANDSCAPING.
- THE CONTRACTOR SHALL MAINTAIN ADJACENT STREETS IN A NEAT, CLEAN DUST FREE AND SANITARY CONDITION AT ALL TIMES AND TO THE SATISFACTION OF THE TOWN INSPECTOR. THE ADJACENT STREET SHALL AT ALL TIMES BE KEPT CLEAN OF DEBRIS, WITH DUST AND OTHER NUISANCE BEING CONTROLLED AT ALL TIMES. THE CONTRACTOR BE RESPONSIBLE FOR ANY CLEAN UP ON ADJACENT STREETS AFFECTED BY THE BY THEIR CONSTRUCTION, METHOD OF STREET CLEANING SHALL BE BY DRY SWEEPING OF ALL PAVED AREAS. NO STOCKPILING OF BUILDING MATERIALS WITHIN THE TOWN RIGHT-OF-WAY.
- SEDIMENTS AND OTHER MATERIALS SHALL NOT BE TRACKED FROM THE SITE BY VEHICLE TRAFFIC. THE CONTRACTOR SHALL INSTALL A STABILIZED CONSTRUCTION ENTRANCE PRIOR TO THE INSPECTION OF ANY WORK ONSITE AND MAINTAIN IT FOR THE DURATION OF THE CONSTRUCTION PROCESS SO AS TO NOT INHIBIT SEDIMENTS FROM BEING DEPOSITED INTO THE PUBLIC RIGHT-OF-WAY UNTIL THE COMPLETION OF ALL LANDSCAPING.
- THE CONTRACTOR SHALL PROTECT DOWN SLOPE DRAINAGE COURSES, STREAMS AND STORM DRAINS WITH ROCK FILLED SAND BAGS, TEMPORARY SWALES, SILT FENCES, AND EARTH PERMS IN CONJUNCTION OF ALL LANDSCAPING.
- STOCKPILED MATERIALS SHALL BE COVERED WITH VISQUEEN OR A TARPULIN UNTIL THE MATERIAL IS REMOVED FROM THE SITE. ANY REMAINING BARE SOIL THAT EXISTS AFTER THE STOCKPILE HAS BEEN REMOVED SHALL BE COVERED UNTIL A NATURAL GROUND COVER IS ESTABLISHED OR IT IS SEEDED OR PLANTED TO PROVIDE GROUND COVER PRIOR TO THE FALL RAINY SEASON.
- EXCESS OR WASTE CONCRETE MUST NOT BE WASHED INTO THE PUBLIC RIGHT-OF-WAY OR ANY OTHER DRAINAGE SYSTEM. PROVISIONS SHALL BE MADE TO RETAIN CONCRETE WASTES ON SITE UNTIL THEY CAN BE DISPOSED OF AS SOLID WASTE.
- TRASH AND CONSTRUCTION RELATED SOLID WASTES MUST BE DEPOSITED INTO A COVERED RECEPTACLE TO PREVENT CONTAMINATION AND DISPERSAL BY WIND

**EROSION CONTROL NOTES CONTINUED:**

- FUELS, OILS, SOLVENTS AND OTHER TOXIC MATERIALS MUST BE STORED IN ACCORDANCE WITH THEIR LISTING AND ARE NOT TO CONTAMINATE THE SOIL AND SURFACE WATERS. ALL APPROVED STORAGE CONTAINERS ARE TO BE PROTECTED FROM THE WEATHER. SPILLS MUST BE CLEANED UP IMMEDIATELY AND DISPOSED OF IN A PROPER MANNER. SPILLS MUST NOT BE WASHED INTO THE DRAINAGE SYSTEM,
- DUST CONTROL SHALL BE DONE BY WATERING AND AS OFTEN AS REQUIRED BY THE TOWN INSPECTOR.
- SILT FENCE(S) AND/OR FIBER ROLL(S) SHALL BE INSTALLED PRIOR TO SEPTEMBER 15TH AND SHALL REMAIN IN PLACE UNTIL THE LANDSCAPING GROUND COVER IS INSTALLED. CONTRACTOR SHALL CONTINUOUSLY MONITOR THESE MEASURES, FOLLOWING AND DURING ALL RAIN EVENTS, TO PUBLIC OWNED FACILITIES.

**EROSION CONTROL MEASURES:**


- THE FACILITIES SHOWN ON THIS PLAN ARE DESIGNED TO CONTROL EROSION AND SEDIMENT DURING THE RAINY SEASON, OCTOBER 15TH TO APRIL 15. EROSION CONTROL FACILITIES SHALL BE IN PLACE PRIOR TO OCTOBER 15TH OF ANY YEAR. GRADING OPERATIONS DURING THE RAINY SEASON WHICH LEAVE DENUDED SLOPES SHALL BE PROTECTED WITH EROSION CONTROL MEASURES IMMEDIATELY FOLLOWING GRADING ON THE SLOPES.
- SITE CONDITIONS AT TIME OF PLACEMENT OF EROSION CONTROL MEASURES WILL VARY. APPROPRIATE ACTION INCLUDING TEMPORARY SWALES, INLETS, HYDROSEEDING, STRAW BALES, ROCK SACKS, ETC. SHALL BE TAKEN TO PREVENT EROSION AND SEDIMENTATION FROM LEAVING SITE. EROSION CONTROL MEASURES SHALL BE ADJUSTED AS THE CONDITIONS CHANGE AND THE NEED OF CONSTRUCTION SHIFT.
- CONSTRUCTION ENTRANCES SHALL BE INSTALLED PRIOR TO COMMENCEMENT OF GRADING. ALL CONSTRUCTION TRAFFIC ENTERING ONTO THE PAVED ROADS MUST CROSS THE STABILIZED CONSTRUCTION ENTRANCES. CONTRACTOR SHALL MAINTAIN STABILIZED ENTRANCE AT EACH VEHICLE ACCESS POINT TO EXISTING PAVED STREETS. ANY MUD OR DEBRIS TRACKED ONTO PUBLIC STREETS SHALL BE REMOVED DAILY AND AS REQUIRED BY THE GOVERNING AGENCY.
- EXPOSED SLOPES THAT ARE NOT VEGETATED SHALL BE HYDROSEEDDED. IF HYDROSEEDING IS NOT USED OR IS NOT EFFECTIVE BY OCTOBER 15, THEN OTHER IMMEDIATE METHODS SHALL BE IMPLEMENTED, SUCH AS EROSION CONTROL BLANKETS, OR A THREE-STEP APPLICATION OF 1) SEED, MULCH, FERTILIZER 2) BLOWN STRAW 3) TACKIFIER AND MULCH. HYDROSEEDING SHALL BE IN ACCORDANCE WITH THE PROVISIONS OF SECTION 20" EROSION CONTROL AND HIGHWAY PLANTING" OF THE STANDARD SPECIFICATION OF THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION, AS LAST REVISED. REFER TO THE EROSION CONTROL SECTION OF THE GRADING SPECIFICATIONS THAT ARE A PART OF THIS PLAN SET FOR FURTHER INFORMATION.
- INLET PROTECTION SHALL BE INSTALLED AT OPEN INLETS TO PREVENT SEDIMENT FROM ENTERING THE STORM DRAIN SYSTEM. INLETS NOT USED IN CONJUNCTION WITH EROSION CONTROL ARE TO BE BLOCKED TO PREVENT ENTRY OF SEDIMENT. MINIMUM INLET PROTECTION SHALL CONSIST OF A ROCK SACKS OR AS SHOWN ON THIS PLAN
- THIS EROSION AND SEDIMENT CONTROL PLAN MAY NOT COVER ALL THE SITUATIONS THAT MAY ARISE DURING CONSTRUCTION DUE TO UNANTICIPATED FIELD CONDITIONS. VARIATIONS AND ADDITIONS MAY BE MADE TO THIS PLAN IN THE FIELD. A REPRESENTATIVE OF LEA & BRAZE ENGINEERING SHALL PERFORM A FIELD REVIEW AND MAKE RECOMMENDATIONS AS NEEDED. CONTRACTOR IS RESPONSIBLE TO NOTIFY LEA & BRAZE ENGINEERING AND THE GOVERNING AGENCY OF ANY CHANGES.
- THE EROSION CONTROL MEASURES SHALL CONFORM TO THE LOCAL JURISDICTION'S STANDARDS AND THE APPROVAL OF THE LOCAL JURISDICTION'S ENGINEERING DEPARTMENT.
- STRAW ROLLS SHALL BE PLACED AT THE TOE OF SLOPES AND ALONG THE DOWN SLOPE PERIMETER OF THE PROJECT. THEY SHALL BE PLACED AT 25 FOOT INTERVALS ON GRADED SLOPES. PLACEMENT SHALL RUN WITH THE CONTOURS AND ROLLS SHALL BE TIGHTLY END BUTTED. CONTRACTOR SHALL REFER TO MANUFACTURERS SPECIFICATIONS FOR PLACEMENT AND INSTALLATION INSTRUCTIONS.

**REFERENCES:**



- CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL
- CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION

**PERIODIC MAINTENANCE:**

- MAINTENANCE IS TO BE PERFORMED AS FOLLOWS:
  - DAMAGES CAUSED BY SOIL EROSION OR CONSTRUCTION SHALL BE REPAIRED AT THE END OF EACH WORKING DAY.
  - SWALES SHALL BE INSPECTED PERIODICALLY AND MAINTAINED AS NEEDED.
  - SEDIMENT TRAPS, BERMS, AND SWALES ARE TO BE INSPECTED AFTER EACH STORM AND REPAIRS MADE AS NEEDED.
  - SEDIMENT SHALL BE REMOVED AND SEDIMENT TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT HAS ACCUMULATED TO A DEPTH OF 1' FOOT.
  - SEDIMENT REMOVED FROM TRAP SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.
  - RILLS AND GULLIES MUST BE REPAIRED.
- GRAVEL BAG INLET PROTECTION SHALL BE CLEANED OUT WHENEVER SEDIMENT DEPTH IS ONE HALF THE HEIGHT OF ONE GRAVEL BAG.
- STRAW ROLLS SHALL BE PERIODICALLY CHECKED TO ASSURE PROPER FUNCTION AND CLEANED OUT WHENEVER THE SEDIMENT DEPTH REACHED HALF THE HEIGHT OF THE ROLL.
- SILT FENCE SHALL BE PERIODICALLY CHECKED TO ASSURE PROPER FUNCTION AND CLEANED OUT WHENEVER THE SEDIMENT DEPTH REACHES ONE FOOT IN HEIGHT.
- CONSTRUCTION ENTRANCE SHALL BE REGRAVELED AS NECESSARY FOLLOWING SILT/SOIL BUILDUP.
- ANY OTHER EROSION CONTROL MEASURES SHOULD BE CHECKED AT REGULAR INTERVALS TO ASSURE PROPER FUNCTION



**EROSION CONTROL LEGEND**



SWPPP NOTE:  
REFER TO PROJECT SWPPP FOR ADDITIONAL INFORMATION.

NOTE:  
SEAL ALL OTHER INLETS NOT INTENDED TO ACCEPT STORM WATER AND DIRECT FLOWS TEMPORARILY TO FUNCTIONAL SEDIMENTATION BASIN INLETS. -TYP




**LEA & BRAZE ENGINEERING, INC.**  
CIVIL ENGINEERS • LAND SURVEYORS  
SACRAMENTO REGION  
2610 J STREET, WEST  
HAYWARD, CALIFORNIA 94545  
(P) (510) 887-4086 (F) (510) 887-3019  
WWW.LEABRAZE.COM

**CALWATER TANK  
DRAINAGE & TREATMENT PLAN  
SAN MATEO, CALIFORNIA**  
(UNINCORPORATED) SAN MATEO COUNTY


**EROSION CONTROL  
PLAN**

REVISIONS	BY


JOB NO: 2161285  
DATE: 02-01-23  
SCALE: 1" = 20'  
DESIGN BY: AH  
DRAWN BY: MCF  
SHEET NO:




1 INLET PROTECTION  
ER-2 NTS



2 STREET INLET PROTECTION  
ER-2 NTS




3 GRAVEL BAG AT STREET FLOW LINE  
ER-2 NTS




4 CONSTRUCTION ENTRANCE  
ER-2 NTS

**NOTES:**  
 STABILIZED CONSTRUCTION SITE ACCESS SHALL BE CONSTRUCTED OF 3" TO 4" WASHED, FRACTURED STONE AGGREGATE.  
 MATERIAL SHALL BE PLACED TO A MINIMUM THICKNESS OF 12". LENGTH OF ENTRANCE SHALL BE A MINIMUM OF 50'.  
 WIDTH SHALL BE A MIN. OF 15' OR GREATER IF NECESSARY TO COVER ALL VEHICULAR INGRESS AND EGRESS. PROVIDE AMPLE TURNING RADIUS.  
 THE ENTRANCE SHALL BE KEPT IN GOOD CONDITION BY OCCASIONAL TOP DRESSING WITH MATERIAL AS SPECIFIED IN ABOVE NOTE.  
 ACCESSES SHALL BE INSPECTED WEEKLY DURING PERIODS OF HEAVY USAGE, MONTHLY DURING NORMAL USAGE, AND AFTER EACH RAINFALL, WITH MAINTENANCE PROVIDED AS NECESSARY.  
 PERIODIC TOP DRESSING SHALL BE DONE AS NEEDED.




**NOTE:**  
 1. STRAW ROLL INSTALLATION REQUIRES THE PLACEMENT AND SECURE STAKING OF THE ROLL IN A TRENCH, 3" TO 5" DEEP, DUG ON CONTOUR. RUNOFF MUST NOT BE ALLOWED TO RUN UNDER OR AROUND ROLL.  
 2. CONTRACTOR IS RESPONSIBLE FOR REGULAR MAINTENANCE AND INSPECTION. THE SILT SHALL BE CLEANED OUT WHEN IT REACHES HALF THE HEIGHT OF THE ROLL.

5 STRAW ROLLS  
ER-2 NTS



6 CONCRETE WASHOUT  
ER-2 NTS

**NOTES:**  
 ACTUAL LAYOUT DETERMINED IN FIELD.  
 THE CONCRETE WASHOUT SIGN SHALL BE INSTALLED WITHIN 10' OF THE TEMPORARY CONCRETE WASHOUT FACILITY.



7 SILT FENCE  
ER-2 NTS

**NOTE:**  
 IT IS ESSENTIAL THAT THE WIRE/FABRIC BE FULLY EMBEDDED INTO THE GROUND SO RUN-OFF CANNOT FLOW FREELY UNDER FENCE.




**LEA & BRAZE ENGINEERING, INC.**  
 CIVIL ENGINEERS • LAND SURVEYORS  
 SACRAMENTO REGION  
 3000 JACOBSON WAY, WEST  
 SACRAMENTO, CALIFORNIA 95821  
 (P) (916) 966-1338  
 (F) (916) 966-1338  
 WWW.LEABRAZE.COM

**CALWATER TANK  
 DRAINAGE & TREATMENT PLAN  
 SAN MATEO, CALIFORNIA**  
 (UNINCORPORATED) SAN MATEO COUNTY

**EROSION CONTROL  
 DETAILS**

REVISIONS	BY




SAN MATEO COUNTYWIDE  
**Water Pollution  
Prevention Program**

Clean Water. Healthy Community.

# Construction Best Management Practices (BMPs)

Construction projects are required to implement the stormwater best management practices (BMP) on this page, as they apply to your project, all year long.

## Materials & Waste Management



### Non-Hazardous Materials

- ❑ Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or if not actively being used within 14 days.
- ❑ Use (but don't overuse) reclaimed water for dust control.

### Hazardous Materials

- ❑ Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, county, state and federal regulations.
- ❑ Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecast.
- ❑ Follow manufacturer's application instructions for hazardous materials and be careful not to use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- ❑ Arrange for appropriate disposal of all hazardous wastes.

### Waste Management

- ❑ Cover waste disposal containers securely with tarps at the end of every work day and during wet weather.
- ❑ Check waste disposal containers frequently for leaks and to make sure they are not overfilled. Never hose down a dumpster on the construction site.
- ❑ Clean or replace portable toilets, and inspect them frequently for leaks and spills.
- ❑ Dispose of all wastes and debris properly. Recycle materials and wastes that can be recycled (such as asphalt, concrete, aggregate base materials, wood, gyp board, pipe, etc.)
- ❑ Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste.

### Construction Entrances and Perimeter

- ❑ Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- ❑ Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.

## Equipment Management & Spill Control




### Maintenance and Parking

- ❑ Designate an area, fitted with appropriate BMPs, for vehicle and equipment parking and storage.
- ❑ Perform major maintenance, repair jobs, and vehicle and equipment washing off site.
- ❑ If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan or drop cloths big enough to collect fluids. Recycle or dispose of fluids as hazardous waste.
- ❑ If vehicle or equipment cleaning must be done onsite, clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or surface waters.
- ❑ Do not clean vehicle or equipment onsite using soaps, solvents, degreasers, or steam cleaning equipment.

### Spill Prevention and Control

- ❑ Keep spill cleanup materials (e.g., rags, absorbents and cat litter) available at the construction site at all times.
- ❑ Inspect vehicles and equipment frequently for and repair leaks promptly. Use drip pans to catch leaks until repairs are made.
- ❑ Clean up spills or leaks immediately and dispose of cleanup materials properly.
- ❑ Do not hose down surfaces where fluids have spilled. Use dry cleanup methods (absorbent materials, cat litter, and/or rags).
- ❑ Sweep up spilled dry materials immediately. Do not try to wash them away with water, or bury them.
- ❑ Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- ❑ Report significant spills immediately. You are required by law to report all significant releases of hazardous materials, including oil. To report a spill: 1) Dial 911 or your local emergency response number, 2) Call the Governor's Office of Emergency Services Warning Center, (800) 852-7550 (24 hours).

## Earthmoving



- ❑ Schedule grading and excavation work during dry weather.
- ❑ Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- ❑ Remove existing vegetation only when absolutely necessary, and seed or plant vegetation for erosion control on slopes or where construction is not immediately planned.
- ❑ Prevent sediment from migrating offsite and protect storm drain inlets, gutters, ditches, and drainage courses by installing and maintaining appropriate BMPs, such as fiber rolls, silt fences, sediment basins, gravel bags, berms, etc.
- ❑ Keep excavated soil on site and transfer it to dump trucks on site, not in the streets.

### Contaminated Soils

- ❑ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:
  - Unusual soil conditions, discoloration, or odor.
  - Abandoned underground tanks.
  - Abandoned wells
  - Buried barrels, debris, or trash.

## Paving/Asphalt Work




- ❑ Avoid paving and seal coating in wet weather or when rain is forecast, to prevent materials that have not cured from contacting stormwater runoff.
- ❑ Cover storm drain inlets and manholes when applying seal coat, tack coat, slurry seal, fog seal, etc.
- ❑ Collect and recycle or appropriately dispose of excess abrasive gravel or sand. Do NOT sweep or wash it into gutters.
- ❑ Do not use water to wash down fresh asphalt concrete pavement.

### Sawcutting & Asphalt/Concrete Removal


- ❑ Protect nearby storm drain inlets when saw cutting. Use filter fabric, catch basin inlet filters, or gravel bags to keep slurry out of the storm drain system.
- ❑ Shovel, absorb, or vacuum saw-cut slurry and dispose of all waste as soon as you are finished in one location or at the end of each work day (whichever is sooner!).
- ❑ If sawcut slurry enters a catch basin, clean it up immediately.

## Concrete, Grout & Mortar Application




- ❑ Store concrete, grout, and mortar away from storm drains or waterways, and on pallets under cover to protect them from rain, runoff, and wind.
- ❑ Wash out concrete equipment/trucks offsite or in a designated washout area, where the water will flow into a temporary waste pit, and in a manner that will prevent leaching into the underlying soil or onto surrounding areas. Let concrete harden and dispose of as garbage.
- ❑ When washing exposed aggregate, prevent washwater from entering storm drains. Block any inlets and vacuum gutters, hose washwater onto dirt areas, or drain onto a bermed surface to be pumped and disposed of properly.

## Landscaping



- ❑ Protect stockpiled landscaping materials from wind and rain by storing them under tarps all year-round.
- ❑ Stack bagged material on pallets and under cover.
- ❑ Discontinue application of any erodible landscape material within 2 days before a forecast rain event or during wet weather.


## Painting & Paint Removal



### Painting Cleanup and Removal

- ❑ Never clean brushes or rinse paint containers into a street, gutter, storm drain, or stream.
- ❑ For water-based paints, paint out brushes to the extent possible, and rinse into a drain that goes to the sanitary sewer. Never pour paint down a storm drain.
- ❑ For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of excess liquids as hazardous waste.
- ❑ Paint chips and dust from non-hazardous dry stripping and sand blasting may be swept up or collected in plastic drop cloths and disposed of as trash.
- ❑ Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury, or tributyltin must be disposed of as hazardous waste. Lead based paint removal requires a state-certified contractor.

## Dewatering



- ❑ Discharges of groundwater or captured runoff from dewatering operations must be properly managed and disposed. When possible send dewatering discharge to landscaped area or sanitary sewer. If discharging to the sanitary sewer call your local wastewater treatment plant.
- ❑ Divert run-on water from offsite away from all disturbed areas.
- ❑ When dewatering, notify and obtain approval from the local municipality before discharging water to a street gutter or storm drain. Filtration or diversion through a basin, tank, or sediment trap may be required.
- ❑ In areas of known or suspected contamination, call your local agency to determine whether the ground water must be tested. Pumped groundwater may need to be collected and hauled off-site for treatment and proper disposal.

**Storm drain polluters may be liable for fines of up to \$10,000 per day!**

EXISTING ANTENNA WILL BE REPLACE & MOVED TO NEW LOCATION

NO TREE PLANTING DUE TO EXISTING PIPING & FUTURE UNDERGROUND UTILITIES.

EXISTING TREE REMOVED FOR CONSTRUCTION (TYP.)




EXISTING TREES TO REMAIN (TYP.)


EXISTING DEAD TREES REMOVED DUE TO STORM DAMAGE (TYP.)

**EXISTING CONDITIONS**

SCALE: 1/8" = 1'-0"



**LEGENDS:**

-  EXISTING TREES TO REMAIN (TYP.)
-  EXISTING DEAD TREES REMOVED DUE TO STORM DAMAGE.
-  EXISTING TREE REMOVED FOR CONSTRUCTION (TYP.)



**PLANTING PLAN**

SCALE: 1/8" = 1'-0"



**SEE SHEET L-3 FOR PLANTING NOTES, LEGENDS AND DETAILS.**

**ROBERT MOWAT ASSOCIATES**  
 LANDSCAPE ARCHITECTURE + LAND PLANNING  
 1501 N. Broadway Suite 400 Walnut Creek, CA 94596  
 Phone 925.705.7424 Fax 925.954.1390  
 www.rmlandscape.com


**BEL AIRE HEIGHTS SUBDIVISION**  
 1700 S. EL CAMINO REAL, #100  
 SAN MATEO, CA 94402

**EXISTING CONDITIONS & PLANTING PLAN**

DATE 10-13-21  
 REVISIONS  
 1 PLANT & IRR. SITE PLAN REV. 5-4-23  
 2 CAL WATER COMMENTS 6-5-23

BEL AIRE HEIGHTS, SAN MATEO, CA  
 SHEET  
**L-1**  
 OF 3

© COPYRIGHT 2021 Robert Mowat Associates. No portion of this drawing may be reproduced, duplicated, or copied in any way without the express written consent of Robert Mowat Associates. This drawing is prepared for this particular site and may not be utilized for another site location.



**IRRIGATION PLAN**

SCALE: 1/8" = 1'-0"


**IRRIGATION LEGENDS**

- 6 STATIONS RAINMASTER EAGLE PLUS WITH CENTRAL COMPATABILITY W/ RAIN CLIK.
- POINT OF CONNECTION SERVICE BY OTHERS, COORDINATE EXACT LOCATION W/ CAL WATER
- 2" PLASTIC GLOBE GATE VALVE IN AMETEK BOX W/ GRAVEL.
- WATTS PRESSURE REDUCER IF REQUIRED
- REDUCED PRESSURE FEBCO 3/4" #825Y BACKFLOW PREVENTER ASSEMBLY W/ PRIME 2X PAINTED 2X DARK GREEN, GALV. STEEL ENCLOSURE WITH FROST BLANKET (OR EQ.)
- HUNTER 1" PGV VALVE WITH FLOW CONTROL AND ACCU SYNC ADJUSTABLE PRESSURE REGULATOR.
- SCH 40 - PVC MAINLINE, BURY MIN. 18" DEEP, SIZE PER PLAN, 24" FOR ROADWAYS. THE CONTRACTOR SHALL INSTALL CONC. THRUST BLOCKS AT ALL JOINTS ON 2" AND LARGER MAINLINES. IF IRRIGATION CONTRACTOR IDENTIFIES AN ALTERNATE ROUTE FOR MAINLINE, THEY SHALL NOTIFY THE OWNER & LANDSCAPE ARCHITECT FOR A MEETING, SITE OBSERVATION AND DISCUSSION BEFORE PROCEEDING WITH THE WORK.
- SCH 40 PVC LATERAL LINE BELOW GRADE - BURY 12" ±.
- SCH 40 PVC SLEEVE, BURY 24" DEEP, SIZE PER PLAN

SYMBOL	DISTRIBUTOR	TYPE	MODEL#	RADIUS	ARC	DESCRIPTION	FLOW
	HUNTER	PRS40 W/MP1000	PROS-12-PRS40-CV-MP1000360	12"	360°	12" POP-UP SHRUB MP ROTOR HEAD	.84 GPM
	HUNTER	PRS40 W/MP1000	PROS-12-PRS40-CV-MP1000210	12"	270°	12" POP-UP SHRUB MP ROTOR HEAD	.63 GPM
	HUNTER	PRS40 W/MP1000	PROS-12-PRS40-CV-MP100090	12"	180°	12" POP-UP SHRUB MP ROTOR HEAD	.42 GPM
	HUNTER	PRS40 W/MP1000	PROS-12-PRS40-CV-MP100090	12"	90°	12" POP-UP SHRUB MP ROTOR HEAD	.21 GPM
	HUNTER	BUBBLER	PCB-50	NA	360°	BUBBLER IN PREF. PIPE	0.5 GPM


**IRRIGATION NOTES**

- THIS DESIGN IS DIAGRAMMATIC. ALL PIPING, VALVES, ETC. SHOWN WITHIN THE PAVED AREAS OR BUILDINGS IS FOR DESIGN CLARIFICATION ONLY AND SHALL BE INSTALLED IN PLANTING AREAS WHERE POSSIBLE. AVOID CONFLICTS WITH PLANTING, PIPING, UTILITIES AND ARCHITECTURE WHERE POSSIBLE.
- DO NOT WILLFULLY INSTALL THE SYSTEMS SHOWN ON THE DRAWINGS WHEN IT IS OBVIOUS IN THE FIELD THAT OBSTRUCTIONS, GRADE DIFFERENCES, GPM AVAILABILITY, OR PRESSURES EXIST THAT MAY NOT HAVE BEEN INCLUDED IN THE ENGINEERING. SUCH OBSTRUCTIONS OR DIFFERENCES SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE CITY AND LAND ARCH. FOR A DECISION. IN THE EVENT THAT NOTIFICATION IS NOT PERFORMED, THE IRRIGATION CONTRACTOR SHALL ASSUME ALL RESPONSIBILITY FOR ANY REVISIONS NECESSARY.
- 120 VOLT ELECTRICAL POWER OUTLET AT THE AUTOMATIC CONTROLLER LOCATION SHALL BE PROVIDED BY OTHERS. THE IRRIGATION CONTRACTOR SHALL MAKE FINAL HOOK-UP FROM REMOTE CONTROL VALVES TO CONTROLLER.
- IT IS THE RESPONSIBILITY OF THE IRRIGATION CONTRACTOR TO FAMILIARIZE THEMSELVES WITH ALL GRADE DIFFERENCES, LOCATION OF WALLS, RETAINING WALLS, UTILITIES, PIPING, BUILDINGS, ETC. THEY SHALL COORDINATE THEIR WORK WITH THE GENERAL CONTRACTOR FOR THE INSTALLATION OR PIPE SLEEVES THROUGH WALLS, UNDER ROADWAYS, STRUCTURES, ETC.
- THE IRRIGATION SYSTEM SHALL BE INSTALLED IN CONFORMANCE WITH ALL APPLICABLE STATE AND LOCAL CODES AND ORDINANCES BY A LICENSED LANDSCAPE CONTRACTOR AND EXPERIENCED WORKMEN. CONTRACTOR TO OBTAIN AND PAY FOR ALL IRRIGATION PERMITS AND REQUIRED FEES.
- CONTRACTOR IS TO CONFIRM THE LOCATION OF EXISTING UTILITIES AND UNDERGROUND STRUCTURES PRIOR TO THE EXCAVATION OF TRENCHES. CONTRACTOR TO REPAIR ANY DAMAGE CAUSED BY, OR DURING THE PERFORMANCE OF, HIS WORK AT NO ADDITIONAL COST TO THE CITY.
- SYSTEM IS BASED UPON A STATIC MAINLINE PRESSURE OF 55 P.S.I. A PRESSURE REDUCER MAY (MAY NOT) BE REQUIRED SO THAT THE STATIC MAINLINE PRESSURE AS MEASURED AT THE POINT OF CONNECTION (AFTER THE BACK FLOW DEVICE) IS DRIP 35 P.S.I. AFTER CALCULATING PRESSURE LOSSES, THE SYSTEM IS DESIGNED TO OPERATE AT APPROXIMATELY 35-40 P.S.I. WORKING PRESSURE AT THE HEADS. THROUGH ANY ONE VALVE, THE SYSTEM IS DESIGNED TO OPERATE AT A MAXIMUM OF 18 GPM.
- CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SLEEVING REQUIRED FOR ELECTRICAL AND IRRIGATION. CONTRACTOR TO COORDINATE AND LOCATE ANY ELECTRICAL AND IRRIGATION SLEEVES PRIOR TO CONCRETE POUR. LANDSCAPE ARCHITECT TO REVIEW LAYOUT PRIOR TO CONCRETE POUR. SLEEVES TO BE SCH. 40 PVC PIPE, SET IN A 2" SAND BED CONTINUOUS AROUND ENTIRE SLEEVE, WITH MARKING TAPE AT EACH END. EXTEND PAST PAVING 6" TRENCHES ARE TO BE OF SUFFICIENT DEPTH TO PROVIDE 18" OF COVER OVER MAINLINE LATERAL LINES PRIOR TO THE INSTALLATION OF IRRIGATION HEADS. MAINLINE TO BE VISUALLY INSPECTED FOR LEAKS UNDER FULL OPERATING PRESSURE PRIOR TO BACKFILLING. MAINLINE UNDER STREETS TO BE 24" DEEP, MINIMUM.
- FLUSH MAINLINES PRIOR TO THE INSTALLATION OF REMOTE CONTROL VALVES. FLUSH LATERAL LINES PRIOR TO THE INSTALLATION OF IRRIGATION HEADS. MAINLINE TO BE VISUALLY INSPECTED FOR LEAKS UNDER FULL OPERATING PRESSURE PRIOR TO BACKFILLING.
- IRRIGATION CONTROL WIRE SHALL BE #14 U.L. APPROVED FOR DIRECT BURIAL. COMMON WIRE SHALL BE #14 U.L. APPROVED FOR DIRECT BURIAL, WHITE IN COLOR. WIRES TO BE MULTI-STRAND #18-9 REMOTE CONTROL VALVES SHALL BE A COLOR OTHER THAN WHITE. ALL SPLICES SHALL BE MADE WITHIN REMOTE CONTROL VALVE BOXES. LEAVE 24" EXCESS WIRE COIL AT REMOTE CONTROL LOCATIONS.
- REMOTE CONTROL VALVE BOXES SHALL BE INSTALLED FLUSH WITH FINISH GRADE (NOT NECESSARILY PLUMB). ALIGN VALVE BOXES WITH ADJACENT PAVEMENT EDGES OR STRUCTURES. VALVE BOXES SHALL BE PLASTIC WITH BOLT DOWN LIDS AND WITH WHITE NUMBERED VALVE STATIONS IN STENCILS.
- ALL EXCAVATIONS SHALL BE BACKFILLED TO 90% COMPACTION (MIN.). CONTRACTOR TO REPAIR SETTLED TRENCHES FOR ONE YEAR AFTER COMPLETION OF WORK.
- CONTRACTOR TO MAKE MINOR ADJUSTMENTS IN HEAD LOCATIONS AND ADJUST HEADS FOR RADIUS (ARC IF APPLICABLE), TO OPTIMUM COVERAGE, AND TO ELIMINATE SPRAYING ONTO PAVEMENT, BUILDINGS, AND WALLS. ADD HEADS AS NECESSARY FOR HEAD TO HEAD COVERAGE. INSTALL FLAT HEADS NEAR BLDGS.
- CONTRACTOR TO MAINTAIN A SET OF "AS-BUILT" DRAWINGS THROUGHOUT THE COURSE OF CONSTRUCTION AND DELIVER THESE DRAWINGS TO THE OWNER / HOA UPON THE COMPLETION OF WORK. THE DRAWINGS SHALL BE IN REPRODUCIBLE FORM.
- CONTRACTOR SHALL GUARANTEE THE SYSTEM AND MATERIALS TO BE FREE FROM DEFECTS FOR A PERIOD OF ONE YEAR STARTING WITH ACCEPTANCE AT THE FINAL SITE REVIEW.
- ALL HEADS WHICH MAY EXPERIENCE LOW HEAD DRAINAGE SHOULD HAVE IN-LINE OR IN-HEAD CHECK VALVES INSTALLED.
- THE IRRIGATION CONTRACTOR SHOULD ARRANGE WITH THE LAND ARCH. & CITY REP. FOR A SITE REVIEW OF THE SYSTEM. CALL WITH TWO DAYS PRIOR NOTICE TO ARRANGE REVIEW DATES. REVIEWS WILL BE SCHEDULED TO REVIEW:
  - PRESSURE TEST TO MAIN LINE PRIOR TO BACKFILLING TRENCHES.
  - COVER TEST OF SPRINKLER SYSTEM PRIOR TO PLANTING.
  - FINAL WALK-THROUGH OF ALL ASPECTS OF THE IRRIGATION SYSTEM.
- WATER JET ALL IRRIGATION TRENCHES, TYPICAL.
- ALL CONTROLLERS SHALL HAVE A MAP OR IRRIGATION ZONE DESCRIPTION PLACED IN THE CONTROLLER CABINET.
- DETECTABLE WARNING TAPE SHALL BE INSTALLED DIRECTLY OVER ALL IRRIGATION MAIN LINES. THE TAPE SHALL BE SIX INCHES (6") WIDE, 5-MIL AND HAVE ALUMINUM BACKING TO MAKE IT EASY TO FIND UNDERGROUND USING A NON-FERROUS LOCATOR. TAPE SHALL HAVE "CAUTION BURIED WATER LINE BELOW" PRINTED IN BLACK LETTERING ON A BLUE BACKGROUND.




**POP-UP SPRAY HEAD**

NOT TO SCALE




**POST MOUNT CONTROLLER**

NOT TO SCALE




**ISOLATION GATE VALVE**

NOT TO SCALE




**REDUCED PRESSURE BACKFLOW**

NOT TO SCALE



**POP-UP BUBBLER HEAD AT TREES**

NOT TO SCALE



**REMOTE CONTROL VALVE**

NOT TO SCALE

**ROBERT MOWAT ASSOCIATES**  
 LANDSCAPE ARCHITECTURE + LAND PLANNING  
 1501 N. Broadway Suite 400 Walnut Creek, CA 94596  
 Phone 925.705.7424 Fax 925.954.1390  
 www.rmlandscape.com

**BEL AIRE HEIGHTS SUBDIVISION**  
 1700 S. EL CAMINO REAL, #100  
 SAN MATEO, CA 94402

**IRRIGATION PLANS, NOTES & LEGENDS & DETAILS**

DATE 10-13-21  
 REVISIONS  
 1. PLANT & IRR. SITE PLAN REV. 5-4-23  
 2. CAL WATER COMMENTS 6-5-23

SHEET

**L-2**

OF 3

BEL AIRE HEIGHTS, SAN MATEO, CA © COPYRIGHT 2021 Robert Mowat Associates. No portion of this drawing may be reproduced, duplicated, or copied in any way without the express written consent of Robert Mowat Associates. This drawing is prepared for this particular site and may not be utilized for another site location.

# PLANTING LEGEND

SYMBOL	SIZE	BOTANICAL NAME	COMMON NAME	WATER USE	QUANTITY
	24" BOX	QUERCUS AGRIFOLIA	COAST LIVE OAK	LOW	13
	15 GAL	HETEROMELESE ARBUTIFOLIA	TOYON	LOW	5
	5 GAL	ARCTOSTAPHYLOS 'HOWARD MCMINN'	MANZANITA	LOW	17
	5 GAL	PRUNUS LAURACERASUS	ENGLISH LAUREL	LOW	8
	1 GAL	VERBENA LILACINA 'DE LA MINA'	DE LA MINA VERBENA	LOW	37
	1 GAL	COTONEASTER DAMMERI 'LOWFAST'	BEARBERRY COTONEASTER	LOW	3'-6" O.C.
	1 GAL	CAREX DIVULSA (TUMULICOLA)	BERKELEY SEDGE	LOW	2'-0" O.C.

## PLANTING NOTES

- ALL WORK SHALL BE PERFORMED BY A LICENSED LANDSCAPE CONTRACTOR AND PERSONNEL FAMILIAR WITH THE WORK AND UNDER THE SUPERVISION OF A QUALIFIED PLANTING FOREMAN.
- PLANT MATERIAL LOCATIONS ARE DIAGRAMMATIC AND SUBJECT TO CHANGE IN THE FIELD AS DIRECTED BY THE LANDSCAPE ARCHITECT. LOCATE PLANT MATERIALS TO SCREEN UTILITIES, IRRIGATION DEVICES, ETC. AS MUCH AS POSSIBLE YET ALLOW ACCESS TO THEM.
- ALL TREES SHALL BE STAKED AS SHOWN IN THE DETAILS.
- THE OWNER RESERVES THE RIGHT TO MAKE SUBSTITUTIONS, ADDITIONS AND DELETIONS IN THE PLANTING SCHEME AS NECESSARY WHILE WORK IS IN PROGRESS. SUCH CASES ARE TO BE ACCOMPANIED BY EQUITABLE ADJUSTMENTS IN THE CONTRACT PRICE IF WHEN NECESSARY.
- THE PLANT COUNT IS FOR THE CONTRACTOR'S CONVENIENCE. IN CASE OF A DISCREPANCY, THE PLAN SHALL GOVERN.
- LOOSEN THE TOP 10" OF TOPSOIL AND BLEND THE TOP 6" LAYER OF SOIL W/ FOLLOWING AMOUNTS / 1000 SQUARE FEET:


  - 6.0 CU. YDS. NITROGEN STABILIZED ORGANIC AMENDMENT\*
  - 50.0 LBS. GYPSUM
  - 25.0 LBS. NITROFORM (38-0-0)
  - 50.0 LBS. TREBLE SUPERPHOSPHATE (0-45-0)
  - 25.0 LBS. POTASSIUM SULFATE (0-0-50)
  - 15.0 LBS. FERROUS SULFATE (10% FE)

THE TOP 12" OF PLANT BACKFILL AROUND THE SIDES OF THE ROOTBALL OF TREES AND SHRUBS SHALL CONSIST OF THE ABOVE AMENDED SOIL PREPARED AS FOLLOWS:


  - 3 PARTS PULVERIZED SITE SOIL
  - 1 PART NITROGEN STABILIZED ORGANIC AMENDMENT\*
  - 1.0 LBS. IRON SULFATE

UNIFORMLY BLENDED WITH: (AMOUNT / CUBIC YARD BACKFILL MIX)


  - 3/4 POUND 6-20-20 COMPLETE FERTILIZER
  - 1/4 POUND POTASSIUM SULFATE (0-0-50)
- THE LANDSCAPE CONTRACTOR SHALL GUARANTEE ALL TREES FOR A PERIOD OF ONE YEAR AND ALL SHRUBS AND GROUND COVERS FOR A PERIOD OF 90 DAYS.
- ANY REQUIREMENTS IN THE PLANS SHALL BE CONSIDERED BINDING. IN CASE OF DISCREPANCIES THE OWNER AND LAND ARCH. SHALL BE IMMEDIATELY NOTIFIED FOR A DECISION BEFORE PROCEEDING WITH THE WORK.
- THERE SHALL BE REGULAR SITE VISITS BY THE LANDSCAPE ARCHITECT AND THE OWNER THROUGHOUT CONSTRUCTION AND A FINAL SITE REVIEW.
  - TO INSPECT PLANTS ON ARRIVAL FROM NURSERY
  - AT TIME OF PLANTING
  - A FINAL SITE REVIEW
- ALL PLANT MATERIAL NOT APPROVED BY LANDSCAPE ARCHITECT MAY BE SUBJECT TO REJECTION.
- ALL WORK SHALL BE INSTALLED IN CONFORMANCE WITH ALL LOCAL CODES AND ORDINANCES. THE LANDSCAPE CONTRACTOR SHALL OBTAIN ALL REQUIRED PERMITS. PROTECT EXISTING TREES AS NECESSARY. FENCE AS NECESSARY. LOCATE ALL UTILITIES BEFORE PROCEEDING WITH THE WORK. COORDINATE ALL DIGGING AND TRENCHING PRIOR TO BEGINNING WORK WITH THE PROJECT SUPERVISOR FIRST.
- THE DESIGN INTENT OF THE PLANTING PLAN IS TO ESTABLISH AND IMMEDIATE, ATTRACTIVE AND MATURE LANDSCAPE APPEARANCE. FUTURE PLANT GROWTH WILL NECESSITATE TRIMMING, SHAPING, PRUNING AND IN MOST CASES, REMOVAL OF TREES AND SHRUBS AS PART OF AN ON-GOING MAINTENANCE PROGRAM.
- ALL PLANT PITS SHALL BE FREE FROM ROCKS AND DEBRIS GREATER THAN 2" IN DIAMETER. APPLY "RONSTAR" OR "ELANCO XL" PRE-EMERGENT HERBICIDE TO ALL PLANTED SHRUB AREAS. APPLY HERBICIDE IN STRICT ACCORDANCE WITH MANUFACTURER'S SPECS.
- THE LANDSCAPE SHALL BE WEED FREE AT THE TIME OF THE FINAL WALK-THROUGH. CONTRACTOR TO PROVIDE MAINTENANCE DURING CONSTRUCTION AND FOR A PERIOD OF 60 DAYS FOLLOWING OWNER'S ACCEPTANCE OF THE COMPLETION OF THE FINAL PUNCH LIST AS PART OF THEIR BID. ALL PRUNING, SPRAYING, FERTILIZING, CLEAN-UP AND ASSOCIATED LANDSCAPE PRACTICES SHALL BE INCLUDED. THE 60 DAY MAINTENANCE PERIOD DOES NOT END UNTIL FINAL ACCEPTANCE BY THE OWNER IS GRANTED.
- CONTRACTOR TO SUBMIT UNIT PRICES FOR THE POSSIBLE ADDITION OF PLANTS TO THE PROJECT. SUBMIT UNIT PRICES FOR 15 GALLON TREES, 5 GALLON SHRUBS, 1 GALLON SHRUBS, GROUNDCOVER AT 50 FT. PRICES.
- 2" LAYER OF SHREDDED FIR BARK OVER ALL SHRUB/GROUNDCOVER AREAS.
- ON ALL SLOPES 2:1 OR GREATER, INSTALL JUTE MESH NETTING, LAP MIN. 12", STAPLE AT 24" O.C. TYP.
- ALL PLANT MATERIAL SHALL BE OF THE QUALITY AND SIZE IN ACCORDANCE WITH THE AMERICAN STANDARDS FOR NURSERY STOCK GUIDELINES, LATEST EDITION.
- THE CONTRACTOR IS RESPONSIBLE FOR THE REMOVAL FROM THE OWNER'S PROPERTY ALL WASTE MATERIAL GENERATED BY FROM THE PLANTING OPERATIONS.
- LANDSCAPE CONTRACTOR TO SHALL COORDINATE ALL WORK WITH RELATED SUB-CONTRACTORS AND WITH THE GENERAL CONSTRUCTION CONTRACTOR OF THE PROJECT.




426.25 PLANTING DETAIL



426.35 PLANTING DETAIL



426.24 PLANTING DETAIL



1 GOOD NEIGHBOR FENCE SCALE: 1/2" = 1' - 0" 180.01 GOOD NEIGHBOR FENCE

**ROBERT MOWAT ASSOCIATES**  
 LANDSCAPE ARCHITECTURE + LAND PLANNING  
 1501 N. Broadway Suite 400 Walnut Creek, CA 94596  
 Phone 925.705.7424 Fax 925.954.1390  
 www.rmatlandscape.com

**BEL AIRE HEIGHTS SUBDIVISION**  
 1700 S. EL CAMINO REAL, #100  
 SAN MATEO, CA 94402

**PLANTING NOTES, LEGENDS & DETAILS**

DATE 10-13-21  
 REVISIONS  
 PLANT & IRR. SITE PLAN REV. 5-4-23  
 CAL WATER COMMENTS 6-5-23

SHEET  
**L-3**  
 OF 3

© COPYRIGHT 2021 Robert Mowat Associates. No portion of this drawing may be reproduced, duplicated, or copied in any way without the express written consent of Robert Mowat Associates. This drawing is prepared for this particular site and may not be utilized for another site location.



**COUNTY OF SAN MATEO - PLANNING AND BUILDING DEPARTMENT**

**ATTACHMENT D**

# Ascension Heights Water Tank Project

## Addendum to the Ascension Heights Subdivision Final Environmental Impact Report

SCH No. 2013102009

JUNE 2023

PREPARED FOR

**County of San Mateo  
Planning and Building Department**

PREPARED BY

**SWCA Environmental Consultants**





**ASCENSION HEIGHTS WATER TANK PROJECT  
ADDENDUM TO THE  
ASCENSION HEIGHTS SUBDIVISION  
FINAL ENVIRONMENTAL IMPACT REPORT  
SCH NO. 2013102009**

Prepared for

**County of San Mateo  
Planning and Building Department**  
455 County Center, 2<sup>nd</sup> Floor  
Redwood City, CA 94063  
Attn: Camille Leung, Senior Planner

Prepared by

**SWCA Environmental Consultants**  
60 Stone Pine Road, Suite 100  
Half Moon Bay, CA 94019  
(650) 440-4160  
[www.swca.com](http://www.swca.com)

SWCA Project No. 70290

June 2023



## **CONTENTS**

<b>Chapter 1. Purpose of Addendum.....</b>	<b>1-1</b>
1.1 Introduction .....	1-1
1.2 Identification of Addendum as Appropriate CEQA Document .....	1-1
1.3 Summary of Conclusions .....	1-3
<b>Chapter 2. Background.....</b>	<b>2-1</b>
2.1 Summary Description of Approved Subdivision Project .....	2-1
2.2 Environmental Review Process .....	2-1
<b>Chapter 3. Modifications to the Implementation of the Approved Subdivision Project.....</b>	<b>3-1</b>
3.1 Background and Project Need .....	3-1
3.2 Surrounding Land Uses and Setting .....	3-1
3.3 Proposed Project Modifications .....	3-3
3.4 Project Construction .....	3-4
3.5 Project Operation.....	3-5
3.6 Agency Approvals.....	3-5
<b>Chapter 4. Environmental Impact Analysis.....</b>	<b>4-5</b>
4.1 Environmental Resources Topics Determined to Have No Impact In the 2016 EIR .....	4-6
4.2 Environmental Resources Topics Determined to have No Update in the Addendum.....	4-6
4.2.1 Air Quality and Greenhouse Gas Emissions .....	4-6
4.2.2 Geology and Soils.....	4-8
4.2.3 Hazards and Hazardous Materials .....	4-8
4.2.4 Land Use.....	4-9
4.2.5 Noise.....	4-9
4.2.6 Population and Housing.....	4-9
4.2.7 Public Services and Recreation .....	4-10
4.3 Environmental Resources Topics Determined to require an Update in the Addendum.....	4-10
4.3.1 Aesthetics .....	4-10
4.3.2 Biological Resources .....	4-15
4.3.3 Energy.....	4-20
4.3.4 Greenhouse Gas Emissions .....	4-21
4.3.5 Hydrology and Water Quality .....	4-23
4.3.6 Transportation.....	4-29
4.3.7 Tribal Cultural Resources.....	4-32
4.3.8 Utilities .....	4-33
4.3.9 Wildfire.....	4-36
4.4 Growth Inducement.....	4-38
4.5 Cumulative Impacts.....	4-38
<b>Chapter 5. Conclusion.....</b>	<b>5-1</b>

## **Appendices**

Appendix A. Site Plans

- Appendix B. Impervious Surface and Drainage Exhibit
- Appendix C. Drainage and Treatment Plan
- Appendix D. Tree Removal and Replacement Plans
- Appendix E. Revised Mitigation Monitoring and Reporting Program

## **Figures**

Figure 1. Project Location.....	2-2
Figure 2. Project Area.....	2-3
Figure 3. Proposed Site Plan.....	3-2
Figure 4. West Elevation View.....	3-4
Figure 5. Looking East from project site. ....	4-11
Figure 6. Existing Trees and Fencing, looking South.....	4-12
Figure 7. Looking South/Southwest from Parrot Drive.....	4-13

## **CHAPTER 1. PURPOSE OF ADDENDUM**

### **1.1 INTRODUCTION**

The County of San Mateo (County) Planning and Building Department, serving as the lead agency under the California Environmental Quality Act (CEQA), adopted the Final Environmental Impact Report (Final EIR) for the Ascension Heights Subdivision Project (Approved Subdivision Project; State Clearinghouse #2013102009) on February 9, 2016. The Final EIR is herein referred to as the 2016 EIR. The Approved Subdivision Project (County Case number PLN 2002-00517) included the subdivision of a 13.32-acre site into 21 legal parcels and construction of 19 single-family dwellings. California Water Service (Cal Water) Station 031-Baywood Tank property is a 0.517- acre parcel at 1452 Bel Aire Road, San Mateo, CA 94402 (Assessor's Parcel Number APN 041-111-020); Proposed Project parcel) that contains an existing 216,000-gallon water reservoir tank located at the top of a hill surrounded by the Approved Subdivision Project parcel. The Proposed Project parcel was not included as part of the Approved Subdivision Project, although the Approved Subdivision Project did include some driveway and access upgrades to the parcel.

The Ascension Heights Water Tank Project (Proposed Project) (County Case number PLN 2021-00275) would add an additional approximately 59,000-gallon water tank at the Station 031-Baywood Tank property to serve the Ascension Heights Subdivision Project. Improvements to the Proposed Project parcel were not evaluated as part of the Approved Subdivision Project. The Proposed Project would modify the geographic boundaries of the Approved Subdivision Project to incorporate the Cal Water site and the addition of the water tank necessary to serve the Approved Subdivision Project. This document analyzes the environmental impacts of the addition of the water tank to the Approved Subdivision Project and is an Addendum to the 2016 EIR.

### **1.2 IDENTIFICATION OF ADDENDUM AS APPROPRIATE CEQA DOCUMENT**

The purpose of this review is to evaluate potential environmental impacts associated with proposed changes to the previously Approved Subdivision Project, specifically, an additional water reservoir tank at the Cal Water Station 031-Baywood Tank property to serve the Approved Subdivision Project. Additional CEQA review beyond this addendum, in the form of a Supplemental EIR, would only be necessary if the proposed changes to the Approved Subdivision Project created new significant impacts or a substantial increase in the severity of significant impacts identified in the certified 2016 EIR.

State CEQA Guidelines Section 15164 states that the lead agency shall prepare an addendum to a previously certified EIR if the project sponsor needs to make some changes or additions to a project and if certain conditions are met. These conditions are based on State CEQA Guidelines Section 15162, which specifies the conditions that would require preparation of a Subsequent EIR. If *none* of the conditions described in Section 15162 calling for preparation of a Subsequent EIR have occurred, then an addendum to an EIR is the appropriate document to complete environmental review of changes to a project.

According to State CEQA Guidelines Section 15162:

- (a) When an EIR has been certified or a negative declaration adopted for a project, no subsequent EIR shall be prepared for that project unless the lead agency determines, on the basis of substantial evidence in the light of the whole record, one or more of the following:
  - (1) Substantial changes are proposed in the project which will require major revisions of the previous EIR or negative declaration due to the involvement of new significant environmental effects or a substantial increase in the severity of previously identified significant effects;
  - (2) Substantial changes occur with respect to the circumstances under which the project is undertaken which will require major revisions of the previous EIR or Negative Declaration due to the involvement of new significant environmental effects or a substantial increase in the severity of previously identified significant effects; or
  - (3) New information of substantial importance, which was not known and could not have been known with the exercise of reasonable diligence at the time the previous EIR was certified as complete or the Negative Declaration was adopted, shows any of the following:
    - (A) The project will have one or more significant effects not discussed in the previous EIR or negative declaration;
    - (B) Significant effects previously examined will be substantially more severe than shown in the previous EIR;
    - (C) Mitigation measures or alternatives previously found not to be feasible would in fact be feasible, and would substantially reduce one or more significant effects of the project, but the project proponents decline to adopt the mitigation measure or alternative; or
    - (D) Mitigation measures or alternatives which are considerably different from those analyzed in the previous EIR would substantially reduce one or more significant effects on the environment, but the project proponents decline to adopt the mitigation measure or alternative.

Additionally, State CEQA Guidelines Section 15164 provides the following guidance for preparation of an EIR addendum:

- (a) The lead agency or responsible agency shall prepare an addendum to a previously certified EIR if some changes or additions are necessary but none of the conditions described in Section 15162 calling for preparation of a subsequent EIR have occurred.

- (b) An addendum need not be circulated for public review but can be included in or attached to the final EIR or adopted negative declaration.
- (c) The decision making body shall consider the addendum with the final EIR or adopted negative declaration prior to making a decision on the project.
- (d) A brief explanation of the decision not to prepare a subsequent EIR pursuant to Section 15162 should be included in an addendum to an EIR, the lead agency's findings on the project, or elsewhere in the record. The explanation must be supported by substantial evidence.

This document is an Addendum to the 2016 EIR and has been prepared to evaluate the impacts of modifications to the Approved Subdivision Project identified in the 2016 EIR; those modifications are referred to herein as the "Proposed Project." The Addendum focuses on the environmental effects associated with specific additions to the water supply component of the Approved Subdivision Project. Proposed Project modifications would not result in new significant impacts or a substantial increase in the severity of a previously identified significant impact; therefore, preparation of a Supplemental or Subsequent EIR is not required.

### **1.3 SUMMARY OF CONCLUSIONS**

This Addendum to the 2016 EIR demonstrates that the environmental analysis, impacts, and mitigation requirements identified in the 2016 EIR remain substantively unchanged by the project modifications described herein and supports the finding that the Proposed Project does not raise any new significant impacts and does not exceed the levels of impact significance identified in the 2016 EIR. Accordingly, preparation of a Subsequent EIR is not necessary pursuant to State CEQA Guidelines Sections 15162 and 15164. This decision is based on substantial evidence, as set forth in the following discussion of the Proposed Project modifications and the environmental impacts of those modifications.

Circulation of this Addendum for public review is not required (State CEQA Guidelines Section 15164(c)); however, the Addendum will be considered by the decision-making body, along with the previously certified 2016 EIR, prior to taking action to approve or deny the Proposed Project (State CEQA Guidelines Section 15164(d)).

The Addendum will be posted on the San Mateo County website at:  
<https://www.smcgov.org/planning/project-ceqa-documents>



*This page intentionally left blank.*

## **CHAPTER 2. BACKGROUND**


### **2.1 SUMMARY DESCRIPTION OF APPROVED SUBDIVISION PROJECT**

The Approved Subdivision Project is on approximately 13.32 acres at the northeast corner of Bel Aire Road and Ascension Drive, east of Interstate (I-) 280 and northwest of State Route (SR-) 92, in the unincorporated community of San Mateo Highlands in San Mateo County, California (Figures 1 and 2). The Approved Subdivision Project subdivided six existing parcels into 21 legal lots and will result in the construction of 19 new single-family residences, and include a new access roadway and two common area parcels (approximately 7.6 acres total), which would be maintained as open space and include an undisturbed and protected area and common areas with foot trails.

The Approved Subdivision Project will also replace the existing access road to an existing water tank and cell transmitter on the Cal Water Station 031-Baywood Tank property, which is located at the top of the hill surrounded by the Approved Subdivision Project parcel. This Proposed Project site parcel was not included as part of the Approved Subdivision Project, although the Approved Subdivision Project did include some driveway and access upgrades to the parcel. The roadway is designed to accommodate maintenance vehicles that would require access to this parcel. The new roadway will terminate at the northwestern boundary of the Station 031 parcel. Additionally, as part of the Approved Subdivision Project, an approximately 18-foot wide, 120-foot-long connecting road will be constructed on the water tank parcel to connect the new access road with the structures on the parcel. The connecting road will be flanked by an approximately 3-foot-tall keystone block retaining wall on either side. Cal Water will maintain the access road within its dedicated parcel. In addition, 2,821 square feet of land east of the water tank/cell transmitter site is dedicated to Cal Water, the owner of the water tank. The cell transmitter is a Verizon antenna east of the CalWater site and will be replaced in summer 2023. A new fence surrounding the water tank will be provided as a project-sponsored improvement, as well as a new water main that will run through the property.

### **2.2 ENVIRONMENTAL REVIEW PROCESS**

The County Planning and Building Department, serving as the lead agency under CEQA, prepared the Final EIR for the Approved Subdivision Project, as well as the Findings and Mitigation Monitoring and Reporting Program (MMRP) in accordance with State CEQA Guidelines Sections 15091 (Findings) and 15097 (Mitigation Monitoring or Reporting), respectively. The Findings document identified impacts resulting from the Approved Subdivision Project, and the MMRP outlines mitigation measures to reduce significant impacts to less-than-significant levels.



**Figure 1. Project Location**



**Figure 2. Project Area**

*This page intentionally left blank.*

## **CHAPTER 3. MODIFICATIONS TO THE IMPLEMENTATION OF THE APPROVED SUBDIVISION PROJECT**

### **3.1 BACKGROUND AND PROJECT NEED**


The existing 216,000-gallon water storage tank, approximately 40 feet in diameter and 24 feet in height, used on the subject site at 1452 Bel Aire Road, San Mateo, CA 94402 (Assessor's Parcel Number APN 041-111-020) was installed in the late 1950s and has been in service to support the surrounding community. The proposed water storage tank would be located adjacent to the existing water storage tank. The Proposed Project includes installation of a new water tank and boosting facility<sup>1</sup> adjacent to the existing Cal Water Station 31-Baywood Tank on Cal Water property to augment the Approved Subdivision Project domestic and fire water supply (see Figures 1 and 2, Appendix A) to the 19 new residences, currently under construction. Improvements to the Proposed Project parcel (Cal Water site) were not evaluated as part of the Approved Subdivision Project. The Proposed Project would modify the geographic boundaries of the Approved Subdivision Project to incorporate the Cal Water site and the addition of the water tank necessary to serve the Approved Subdivision Project. The Proposed Project presents minor modifications to the Approved Subdivision Project addressed in the 2016 EIR.

### **3.2 SURROUNDING LAND USES AND SETTING**

The Proposed Project is zoned R-1/S-8 (One family residential district/Combining District S-8) and is in the Low-Density Residential land use designation in unincorporated San Mateo County within the San Mateo Highlands area. The Proposed Project parcel (Cal Water site) was not evaluated as part of the Approved Subdivision Project. The Proposed Project would modify the geographic boundaries of the Approved Subdivision Project to incorporate the Cal Water site and the addition of the water tank necessary to serve the Approved Subdivision Project. Surrounding uses are predominantly residential, with single-family residences on all four sides of the Approved Subdivision Project. Other land uses include the College of San Mateo, located approximately 0.13 mile to the northeast. The Proposed Project site is 0.55-mile northwest of SR-92- and 0.9-mile northeast of I-280.

---

<sup>1</sup> A boosting facility is a mechanism that draws water from the storage tank and pressurizes it for distribution to the service area.



**Figure 3. Proposed Site Plan.**

### **3.3 PROPOSED PROJECT MODIFICATIONS**

The Proposed Project proposes to install one 58,929-gallon bolted steel tank on a 0.06-acre (2,605-square-foot) portion of Cal Water Station 031-Baywood Tank (APN 041-111-020), adjacent to and northwest of the existing 216,000-gallon tank on the Cal Water property (see Figure 3, or Appendix A).


The elevation of the Proposed Project site is approximately 620 feet above mean sea level (MSL), and the topography is moderately-to-steeply sloping to the north, east, and west, with the existing tank south of the proposed site. The property is highly disturbed and supports minimal ruderal vegetation. There are several pine trees outside the fence line of the water tank site. Several of these trees have been removed due to storm damage and as part of site preparation for the Approved Subdivision Project. Cal Water has prepared an Erosion Control and Site Restoration Plan to restore the temporarily disturbed areas at the tank site. As part of the Approved Subdivision Project, screening trees will be planted to shield views of the tanks; the Proposed Project does not include planting of additional vegetation.

The Proposed Project includes the following modification to the Approved Subdivision Project:

- Construction of a new 58,929-gallon steel water tank approximately 21 feet 6.5 inches in diameter and 24 feet 2 inches in height and painted a tan color (CWS Grouse Tan). The new tank would be constructed approximately 12.2 feet northwest of the existing tank (Figure 3).
- Construction of new 4-foot-wide concrete apron with a 6-inch curb surrounding the new tank. Excess tank overflow would be captured and directed to a series of existing drainpipes and a concrete drainage channel and then directed to existing catch basins
- Construction of approximately 3,723 square feet of impervious surface area is proposed, resulting in a net increase of approximately 479 square feet of impervious surface over existing conditions.
- Construction of a 15-foot-wide paved access road that would extend from the driveway constructed on the eastern project boundary.
- Construction of new drainage facilities including the following:
  - A depression swale south of the proposed access road.
  - A bioretention pond in the site's the northwest corner. Stormwater would be captured onsite and directed to this bioretention pond.
- Installation of utility piping including a new 6-inch storm drain line which would connect the existing catch basin between the proposed tanks to a new bioretention pond located in the northwest corner of the parcel. A new 8-inch water line would be installed connecting the new tank with pump facilities just south of the proposed tank.



- Removal of existing fence and construction of a new eight-foot high wood fence on the north side and a new eight-foot gate and chain-link fence with inserted green slats along the south, east and west sides of the site.
- Removal of approximately 17 trees and replantation of approximately 40 trees on the west, east, and north sides of the subject property.
- Construction of a new PG&E transformer.



**Figure 4. West Elevation View.**

### **3.4 PROJECT CONSTRUCTION**

Proposed Project construction would result in approximately 0.13 acre (5,690 square feet) of total disturbance and require approximately 100 cubic yards (CY) of cut and 70 CY of fill. Approximately 70 CY of fill material would be imported to the Proposed Project site with haul trucks, and 30 CY of excavated soils would remain onsite. Excavated soils would be replaced with an aggregate base to meet compaction requirements. Approximately 70 CY of excavated soil that would not be reused onsite would be hauled offsite to a landfill for disposal. The Proposed Project grading would be in addition to the Approved Subdivision Project’s approximately 46,500 CY of cut and approximately 20,000 CY of engineered fill, for a Project total of 46,600 CY of cut and approximately 20,070 CY of fill.

The Proposed Project site would be accessed via the existing paved access road. A staging area would be located northeast of the new tank site at the subject property; during construction, there will be no vehicle parking on Bel Aire Road. CalWater has estimated that a crew of approximately four to five construction workers would be required.

Proposed Project construction is anticipated to begin in fall 2023 and last approximately 4 months. Cal Water customers would not experience any interruption of service during project implementation. The current tank is used for fire protection and is not the primary source for domestic water supply.

Construction of the tank would disturb approximately 0.13 acres, and result in a net increase of approximately 479 square feet of impervious surface over existing conditions. The project proponent would not be required to implement a Stormwater Pollution Prevention Plan (SWPPP) but would be required to implement a specific Erosion and Sediment Control Plan (ESCP).<sup>2</sup> The ESCP would include site-specific Best Management Practices (BMPs) that are designed to prevent runoff from construction areas to reduce potential impacts to surface water quality during Proposed Project construction, including temporary construction fencing, inlet protection, and fiber rolls.

### **3.5 PROJECT OPERATION**

Operation of the Proposed Project would not require additional personnel or generate additional trips above existing conditions. The schedule for maintenance activities for the new water tank would be the same or similar to the schedule for the existing tank.

### **3.6 AGENCY APPROVALS**

The County, as the CEQA Lead Agency, has primary discretionary approval authority over the Proposed Project. The Proposed Project would also be required to obtain, at a minimum, the following agency approvals:

- San Mateo County: Use Permit
- San Mateo County: Building Permit
- State Water Resources Control Board (SWRCB), Division of Drinking Water: Amended Water Supply Permit

## **CHAPTER 4. ENVIRONMENTAL IMPACT ANALYSIS**

The 2016 EIR for the Approved Subdivision Project evaluated the following environmental issues: aesthetic resources; air quality and greenhouse gas emissions; biological resources; geology and soils; hazards and hazardous materials; hydrology and water quality; land use; noise and vibration; population and housing; public services, utilities, and recreation; and transportation and circulation. In 2019, the CEQA checklist was revised to include sections for the analysis of energy, tribal cultural resources, and wildfire. All issue areas required to be evaluated under the 2019 CEQA revisions have been evaluated or reevaluated in this Addendum for the proposed construction of the water tank. This evaluation determines whether the Proposed Project would result in any new significant impacts or substantially more severe impacts than those identified in the 2016 EIR.

---

<sup>2</sup> San Francisco Regional Water Quality Control Board (RWQCB). 2015. *Municipal Regional Stormwater NPDES Permit*. California Regional Water Quality Control Board, San Francisco Bay Region. Order No. R2-2015-0049. NPDES Permit No. CAS612008. November 19. Available at: <https://www.smcgov.org/media/73431/download?inline=>. Accessed June 26, 2022.

## **4.1 ENVIRONMENTAL RESOURCE TOPICS DETERMINED TO HAVE NO IMPACT IN THE 2016 EIR**

The following topic areas were screened out of the 2016 EIR in accordance with State CEQA Guidelines Section 15063 (Initial Study). The Initial Study, in conjunction with comments received during scoping, were used to focus the EIR on effects determined to be potentially significant; as a result, the following resource areas were not included in the 2016 EIR.

- Agriculture and Forest Resources
- Cultural Resources
- Minerals

The proposed changes to the Approved Project would not modify the Initial Study analysis and conclusion, and further evaluation of impacts in these resource areas is not required.

## **4.2 ENVIRONMENTAL RESOURCE TOPICS DETERMINED TO REQUIRE NO UPDATE IN THE ADDENDUM**

The Proposed Project would have similar, less-than-significant impacts on the resource areas listed below as described in the 2016 EIR. The Proposed Project is consistent with the Approved Subdivision Project evaluated in the 2016 EIR because the proposed changes would neither increase the severity of any impacts associated with the Approved Subdivision Project nor result in new or substantially different environmental effects. Therefore, the Proposed Project would not change the analyses or conclusions reached in the Final EIR and the impacts on these environmental topic areas would remain less than significant. All mitigation measures in the 2016 EIR remain applicable and in this EIR Addendum, only measures needing minor edits or changes to accommodate the Proposed Project revisions are identified and summarized in the sections below.

### **4.2.1 Air Quality and Greenhouse Gas Emissions**

Air Quality and Greenhouse Gas Emissions impacts for the Approved Subdivision Project were analyzed in Section 4.2 of the 2016 EIR. Since certification of the Final EIR, and due to the timing of project implementation, diesel emission control technologies for off-road construction equipment fleets have improved and warrant modifications to Mitigation Measure 4.2-1b. Additionally, the construction years proposed for the project have been updated to 2023 and 2024 and equipment would be expected to meet EPA's Tier 4 standards. Implementing Tier 1 and Tier 2 mitigation for off-road equipment, as specified in the 2016 EIR mitigation measure, results in higher mitigated emissions than unmitigated emissions. Therefore, Mitigation Measure 4.2-1b, as detailed below, is revised, with outdated information shown in strikethrough. See the updated MMRP, included as Appendix D. New mitigation measures for off-road equipment are not needed to keep the project below thresholds of significance and therefore, the project would continue to have a less than significant impact without mitigation.

The Proposed Project is not expected to result in new significant effects or a substantial increase in the severity of previously identified environmental effects related to air quality. The Proposed Project has the potential to generate criteria pollutants and greenhouse gas (GHG) emissions during construction. The Proposed Project proposes additional minor excavation and grading activities, including approximately 70 CY of fill material to be imported to the Proposed Project site with haul trucks. Approximately 70 CY of excavated soil that would not be reused onsite would be hauled offsite to a landfill for disposal, which would result in a negligible increase in air quality and GHG emissions. The Proposed Project grading would be in addition to the Approved Subdivision Project's approximately 46,500 CY of cut and approximately 20,000 CY of engineered fill, for a Project total of 46,600 CY of cut and approximately 20,070 CY of fill. Given that the project proposes an additional 70 CY of fill to be hauled offsite, the Proposed Project would result in criteria air pollutant emission levels below these thresholds and would result in a negligible increase in air quality emissions beyond what was analyzed in the 2016 EIR. This increase does not result in a cumulatively considerable net increase in the level of nonattainment criteria air pollutants (ozone precursors or PM) given the additional grading and hauling activities.

Because there is no change to the proposed land uses, the project is expected to remain consistent with the applicable air quality plan. Since 2016 EIR certification increases in construction equipment efficiency, have lessened criteria air pollutant emissions. The Proposed Project would not contribute to a cumulatively considerable air quality impact.

The emission reduction credits required as part of Mitigation Measure 4.2-8 have been purchased, and Mitigation Measure 4.2-1b has been edited to include cleaner Tier 4 engines, resulting in a reduction of GHG emissions from the Proposed Project as compared to the Approved Subdivision Project. The construction and operation of a single water tank and any associated components would be subject to all mitigation measures identified in the 2016 EIR. Emissions from the proposed water tank would be offset by the reduction from the project's completed Mitigation Measure 4.2-8 and revised Mitigation Measure 4.2-1b. Furthermore, the newly updated BAAQMD GHG thresholds would continue to be met, consistent with the current CEQA checklist.

The Proposed Project would implement Mitigation Measures 4.2-1a and 4.2-1b as revised to ensure that adverse effects on air quality and greenhouse gases would be less than significant with mitigation and would not be cumulatively considerable.

*Mitigation Measures 4.2-1a, 4.2-1b and 4.2-8 apply. Mitigation 4.2-1b is edited below to include regulatory updates to air quality BMPs and applies to the Proposed Project.*

***Mitigation Measure 4.2-1b:*** *The project applicant shall ensure through contractual obligations with construction contractors that the following Best Management Practices (BMPs) shall be implemented during all stages of construction:*

- *All heavy duty construction equipment be equipped with diesel particulate matter filters.*
- *Only low ROG coatings shall be utilized.*

- ~~*The applicant shall use only Tier 2 or better heavy-duty construction equipment. The project applicant shall use Tier 4 Interim engines for all 75 horsepower or greater diesel-powered equipment, except where the project applicant establishes to the satisfaction of the County that Tier 4 Interim equipment is not available.*~~

**Conclusion:** Implementation of the Proposed Project would not result in new or more severe impacts to air quality and greenhouse gas than previously disclosed in the 2016 EIR. No new mitigation is necessary, and the impacts are not cumulatively considerable.

## 4.2.2 Geology and Soils

Geology and soils impacts for the Approved Subdivision Project were analyzed under Section 4.4, Geology and Soils, in the 2016 EIR. Project geologic conditions have not changed since certification of the 2016 EIR. The Proposed Project proposes additional minor grading activities that have the potential to result in structural damage and injury from seismic activity and related geologic hazards. Grading is proposed for the new water tank and 15-foot access road, an area totaling 0.13 acre (5,690 square feet) of disturbed area, in addition to the Approved Subdivision Project's 13.3 acres of disturbance. Approximately 70 CY of fill material would be imported to the Proposed Project site with haul trucks. Excavated soils would be replaced with an aggregate base to meet compaction requirements. Approximately 70 CY of excavated soil that would not be reused onsite would be hauled offsite to a landfill for disposal. The Proposed Project grading would be in addition to the Approved Subdivision Project's approximately 46,500 CY of cut and approximately 20,000 CY of engineered fill, for a Project total of 46,600 CY of cut and approximately 20,070 CY of fill. Construction activities have the potential to cause landslides and erosion. Implementation of BMPs and County's construction erosion control inspection program would ensure that development of the Proposed Project would result in less-than-significant impacts with mitigation and would not be cumulatively considerable with mitigation.

*Mitigation Measures 4.4-1a and 4.4-1b, Mitigation Measure 4.4-2a, 4.4-2b and 4.4-2c, and Mitigation Measure 4.4-3a and 4.4-3b applies to the Proposed Project.*

**Conclusion:** Implementation of the Proposed Project would not result in new or more severe impacts to geology and soils than previously disclosed in the 2016 EIR. No new mitigation is necessary, and the impacts are not cumulatively considerable.

## 4.2.3 Hazards and Hazardous Materials

Hazards and hazardous materials impacts for the Approved Subdivision Project were analyzed under Section 4.7, Hazards and Hazardous Materials, of the 2016 EIR. The Proposed Project's use and handling of hazardous materials would be similar to the Approved Subdivision Project. The Proposed Project has the potential to use and expose people to hazardous materials. The Proposed Project would result in impacts that are less than significant with mitigation and would not be cumulatively considerable with implementation of mitigation measures.

*Mitigation Measure 4.7-1, Mitigation Measure 4.7-3a and 4.7-3b applies to the Proposed Project.*

**Conclusion:** Implementation of the Proposed Project would not result in new or more severe impacts to hazards and hazardous materials than previously disclosed in the 2016 EIR. No new mitigation is necessary, and the impacts are not cumulatively considerable.

#### **4.2.4 Land Use**

Land Use impacts for the Approved Subdivision Project were analyzed in Section 4.5 of the 2016 EIR. While the Proposed Project represents an intensification of use on the site, the Proposed Project does not include any new roads or barriers and would be consistent with land use plans.

**Conclusion:** Implementation of the Proposed Project would not result in new or more severe impacts to land use than previously disclosed in the 2016 EIR. No new mitigation is necessary, and the impacts are not cumulatively considerable.

#### **4.2.5 Noise**

Noise and Vibration impacts for the Approved Subdivision Project were analyzed in Section 4.8 on the 2016 EIR. Noise conditions in the Project area have not changed since certification of the 2016 EIR. The Proposed Project's noise contribution would be similar to the Approved Subdivision Project and would expose residents to similar noise levels as analyzed for the Approved Subdivision Project. The Proposed Project has the potential to result in an increase in noise levels in the vicinity during construction and expose sensitive receptors to construction traffic noise. Development of the Proposed Project would result in impacts that are less than significant with mitigation and would not be cumulatively considerable with implementation of mitigation measures.

*Mitigation Measure 4.8-1 applies to the Proposed Project.*

**Conclusion:** Implementation of the Proposed Project would not result in new or more severe impacts to noise than previously disclosed in the 2016 EIR. No new mitigation is necessary, and the impacts are not cumulatively considerable.

#### **4.2.6 Population and Housing**

Population and Housing impacts for the Approved Subdivision Project were analyzed in Section 4.9 of the 2016 EIR. The Proposed Project would have a less-than-significant impact on population growth in the area. The Proposed Project is intended to provide drinking water and fire water supply to the 19 new residences in the Approved Subdivision Project. The project would be consistent with applicable County General Plan policies, including land use and zoning ordinances, and would support housing needs identified in the County General Plan. The Proposed Project would serve the residences of the Approved Subdivision Project and would not create or serve additional residential development. Impacts on Population and Housing would remain less than significant and would not be cumulatively considerable.

**Conclusion:** Implementation of the Proposed Project would not result in new or more severe impacts to population and housing than previously disclosed in the 2016 EIR. No new mitigation is necessary, and the impacts are not cumulatively considerable.

## **4.2.7 Public Services and Recreation**

Public Services and Recreation impacts for the Approved Subdivision Project were analyzed in Section 4.10 Public Services, Utilities and Recreation of the 2016 EIR. Implementation of the Proposed Project would not result in a change of service levels nor recreation access from those analyzed in the 2016 EIR. The Proposed Project would serve the residences of the Approved Subdivision Project and would not create or serve additional residential development. Development of the Proposed Project would result in impacts that are less than significant with mitigation and would not be cumulatively considerable with implementation of mitigation measures.

*Mitigation Measure 4.10-2a, 4.10-2b and 4.10-2c apply. Mitigation Measure 4.10-3, and Mitigation Measure 4.10-5 apply to the Proposed Project.*

**Conclusion:** Implementation of the Proposed Project would not result in new or more severe impacts to public services and recreation than previously disclosed in the 2016 EIR. No new mitigation is necessary, and the impacts are not cumulatively considerable.

## **4.3 ENVIRONMENTAL RESOURCE TOPICS DETERMINED TO REQUIRE AN UPDATE IN THE ADDENDUM**

The Proposed Project would have similar, less-than-significant impacts on the resource areas described below as in the 2016 EIR; however, alterations to the mitigation measures in the 2016 EIR would be required. The Proposed Project differs from the Approved Subdivision Project in that it covers a smaller area with less vegetation, and the responsibility for implementing the project and its mitigation measures lies with Cal Water. In all other aspects, the Proposed Project is consistent with the Approved Subdivision Project evaluated in the 2016 EIR because the proposed changes would neither increase the severity of any impacts associated with the Approved Subdivision Project or result in new or substantially different environmental effects. Applicable mitigation measures are listed below. Therefore, although the analyses for the Proposed Project are altered slightly, those analyses do not alter the conclusions reached in the Final EIR and the impacts on these resource areas would remain less than significant.

### **4.3.1 Aesthetics**

Aesthetic resources were discussed under Section 4.1, Aesthetics, in the 2016 EIR.

All impact conclusions remain the same from the 2016 EIR. Applicable mitigation measures are listed below.

### **4.3.1.1 Environmental Setting**

Section 4.1 of the 2016 EIR analyzed potential aesthetic impacts associated with the Ascension Heights Subdivision. The Proposed Project site is located within unincorporated San Mateo County, in a residential area of the San Mateo Highlands. The Proposed Project proposes construction of an approximately 59,000-gallon potable water reservoir on private property. The area is primarily characterized by single-family residences. The immediate surroundings are part of the Ascension Heights Subdivision, which is currently under construction. The Proposed Project site is located on a hilltop on Cal Water property and adjacent to an existing 216,000-gallon reservoir tank. The entire site is enclosed by fencing and surrounded by non-native grasses and shrubs and Monterey pine (*Pinus radiata*) trees located at the top of the knoll. Several knobcone pine (*P. attenuata*) trees fell during the winter storms of 2022-2023, reducing existing and proposed tank screening. See Figures 5 through 7 for views of the project site. The Proposed Project site is located approximately 630 feet southwest of the College of San Mateo.



**Figure 5. Looking East from project site.**





**Figure 6. Existing Trees and Fencing, looking South.**



**Figure 7. Looking South/Southwest from Parrot Drive.**

### **4.3.1.2 Impacts and Mitigation**

*a) Would the Project have a substantial adverse effect on a scenic vista?*

Based on the 2016 EIR, the primary views of the Proposed Project site are experienced by residents along Parrott Drive, Bel Aire Road, Ascension Drive, Los Altos Drive, Polhemus Road, and Bunker Hill Drive. In addition, the Proposed Project site is visible from the College of San Mateo and I-280 and is topographically prominent with some obstructing vegetation to the south and east. All viewers have an open view of the Proposed Project site (Figures 5 through 7). The failure of 6 screening trees due to poor tree health and damage from winter storms of 2022-2023 made the project site more visible from all public vantage points. For these trees, CalWater would provide tree replacement of 1:1 ratio. An additional 11 trees in the project site were removed due to construction of the Approved Subdivision Project; these trees will be replaced at a 3:1 ratio per Mitigation Measure 4.1-1b. The applicant proposes to replace the trees with over 40 trees, exceeding the minimum required 39 replacement trees. In general, new trees would be planted on the same side as where they were removed from, as further discussed below. See Tree Removal and Replacement Plans in APPENDIX D.

The 2016 EIR stated that the now Approved Subdivision Project would result in a visual change but would result in less than significant impacts with mitigation. The installation of an additional water tank, access road and drainage and pump infrastructure would result in an intensification of development on the site, but does not constitute a change in character or quality of the area given that the Proposed Project site already contains one existing water tank and associated water supply infrastructure, cell transmitter and access road. Replacement trees will be planted on all sides of the project parcel, particularly the west, east, and north sides (fewer trees were removed on the south side). However, on the north side of the subject site, fewer replacement trees will be planted than were removed due to space and equipment constraints (Cal Water proposes to minimize tree replacements within its fencing to limit potential hazard and future conflicts with equipment; the project parcel directly abuts Lot 11 to the north which will be separately landscaped). However, as proposed, the two replacement trees on the north side will be 25 feet or taller at maturity to screen the approximately 25-foot-tall tanks, a solid eight-foot-high wood fence will screen the tanks from Lot 11, and the tanks will be painted a tan color to match the existing tank, surrounding environment, and regional hillside landscape. As proposed, replacement trees would provide adequate screening of the new and old tanks. Mitigation Measures 4.1-1a and 4.1-1b would remain applicable to ensure that the adverse effects on a scenic vista remain *less than significant with mitigation*.

***Impact 4.1-1 (2016 EIR). Less than significant with implementation of Mitigation Measures 4.1-1a, 4.1-1b. See page 4.1-16 of the 2016 EIR.***

b) *Would the Project substantially damage scenic resources, including, but not limited to, trees, rock outcroppings, and historic buildings within a state scenic highway?*

As discussed in Table 4.1-1 of the 2016 EIR, I-280 is listed as a scenic highway. During construction, the Proposed Project site would have short-term visual impacts. Once construction and landscaping are in place, there would be no significant change in the visual quality of the corridor. The Approved Subdivision Project will plant trees obscuring views of the Proposed Project site in a three-to-one ratio for trees removed as part of the Approved Subdivision Project. In addition, the largest portion of open space remaining onsite would be visible from I-280. *No impact* would occur.

c) *Would the Project, in non-urbanized areas, substantially degrade the existing visual character or quality of public views of the site and its surroundings? (Public views are those that are experienced from publicly accessible vantage point). If the project is in an urbanized area, would the project conflict with applicable zoning and other regulations governing scenic quality?*

The Proposed Project is located on a hilltop on Cal Water property, adjacent to an existing 216,000-gallon reservoir tank. The Proposed Project would not change or degrade the existing visual character or quality of public views of the Proposed Project site and its surroundings. While there would be an increase in the amount of development on the parcel (see Figure 4), the type of development would not change. Views of the parcel would be partially shielded by trees planted as part of the Approved Subdivision Project. Similar to the discussion in Table 4.1-1 of the 2016 EIR, the Proposed Project would not conflict with

applicable zoning and other regulations governing scenic quality. Impacts would remain *less than significant*.

d) *Would the Project create a new source of substantial light or glare which would adversely affect day or nighttime views in the area?*

Emergency lights are proposed and would be located inside the pump motor control panels. These lights would turn on during maintenance activities conducted by CalWater to access electrical controls. The finish for the water tank would be of a non-glare substance. Therefore, the Proposed Project would not result in any permanent increase in light or glare. Similar to the Approved Subdivision Project, *no impact* would occur.

**Conclusion:** Implementation of the Proposed Project would not result in new or more severe impacts to visual and aesthetics resources than previously disclosed in the 2016 EIR. No new mitigation is necessary, and the impacts are not cumulatively considerable.

## **4.3.2 Biological Resources**

Potential impacts to biological resources associated with the Approved Subdivision Project were analyzed in Section 4.3 of the 2016 EIR. A Project-specific Biological Resources Survey Report (BRSR)<sup>3</sup> was prepared, and the results of the survey are incorporated by reference into the subsections below. Surveys were conducted within a defined biological study area (BSA), and nesting raptor surveys included tree groves on adjacent properties, including the Approved Subdivision Project site. The Proposed Project would be constructed on an existing developed Cal Water parcel with an existing water tank.

All impact conclusions remain the same from the 2016 EIR. Applicable mitigation measures are listed below.

### **4.3.2.1 Environmental Setting**

The Proposed Project site currently contains an existing water tank and cell transmitter equipment and is characterized by ruderal and developed land. It is located at the top of a hill, approximately 620 feet above MSL, and slopes downhill on all sides. According to the 2016 EIR, it is surrounded by knobcone pine forest to the northeast, northwest, and southwest and annual brome grasslands to the southeast. Several knobcone pine (*P. attenuata*) trees fell during the winter storms of 2022-2023. There are no waters or wetlands on the Proposed Project site.

Biological and botanical surveys for the 2016 EIR were conducted on July 25, 2013, and March 3 and 27, 2015. Botanical surveys concluded that the Approved Subdivision Project site had the potential to support 11 special-status plant species. Of these, the annual grassland habitat adjacent to the Proposed Project site had the potential to support the following five special-status plant species: bent-flowered fiddleneck

---

<sup>3</sup> Coast Ridge Ecology. 2015. *Results of 2015 Rare Plant Surveys and Update Mission Blue/Pardalis Blue Butterfly Habitat and Nesting Raptor Survey on the Ascension Heights Subdivision Project Site, San Mateo County, California*. April 11.

(*Amsinckia lunaris*; -/-/ 1B.2),<sup>4</sup> fragrant fritillary (*Fritillaria liliacea*; -/-/1B.2), Dudley's lousewort (*Pedicularis dudleyi*; -/ Rare/1B.2), white-rayed pentachaeta (*Pentachaeta bellidiflora*; E/E/1B.1),<sup>5</sup> and San Francisco campion (*Silene verecunda* ssp. *verecunda*; -/-/1B.2). The knobcone pine habitat adjacent to the Proposed Project site had the potential to support arcuate bush-mallow (*Malacothamnus arcuatus*; -/-/1B.2). In addition, the shaded portions of the access road had the potential to support suitable habitat for San Mateo wooly sunflower (*Eriophyllum latilobum*; -/-/1B.1). None of these species were observed during botanical surveys conducted during evident and identifiable blooming periods; therefore, it was concluded that the species were not present on the Approved Subdivision Project site.

According to the 2016 EIR, there was potential habitat for the Mission blue butterfly (*Plebejus icarioides*) on the Approved Subdivision Project site, but over the course of 24 biological surveys in 2005, 2008, and 2012, in addition to surveys in 2013 and 2015, no host plants (summer lupine [*Lupinus formosus*]) were found. Therefore, the 2016 EIR concluded there is no potential for the Mission blue butterfly to occur on the Approved Subdivision Project site.

According to the 2016 EIR, the annual grassland adjacent to the Proposed Project site provided suitable foraging and nesting habitat for burrowing owl (*Athene cunicularia*; -/SSC),<sup>6</sup> northern harrier (*Circus cyaneus*; -/SSC), and white-tailed kite (*Elanus leucurus*; -/FP).<sup>7</sup> However, the 2015 nesting raptor survey found no evidence of nesting raptors and concluded that it was “highly unlikely these species would nest on site due to a lack of suitable nesting habitat.”

The Proposed Project site was reviewed by a SWCA Environmental Consultants biologist on July 5, 2022. The Proposed Project site is developed with a small amount of ruderal vegetation and enclosed by a chain-link fence. Construction of the Approved Subdivision Project has cleared out the majority of the habitat on the north, northeast, and northwest sides of the parcel that were observed in the 2015 surveys, including the knobcone pine trees to the north of the Proposed Project site and closest to the new tank location. Tree clearing was conducted in accordance with the mitigation measures included in the 2016 EIR. Most of the habitat to the east, south, and west remains intact.

---

<sup>4</sup> The parenthesis include special-status plant federal/state/California Native Plant Society protected status, as follows: – = no protected status; 1B.2 = Rare or Endangered, Moderately threatened in California

<sup>5</sup> E = Endangered; 1B.1 = Rare or Threatened, Seriously threatened in California

<sup>6</sup> The parenthesis indicate special-status animal federal/state protection status, as follows: - = no protection status; SSC = State Species of Special Concern

<sup>7</sup> FP = State Fully Protected species

### 4.3.2.2 Impacts and Mitigation

- a) *Would the Project have a substantial adverse effect, either directly or through habitat modifications, on any species identified as a candidate, sensitive, or special status species in local or regional plans, policies, or regulations, or by the California Department of Fish and Game or U.S. Fish and Wildlife Service?*

Based on the 2016 EIR, 2015 biological survey, and 2022 site visit conducted by an SWCA Environmental Consultants biologist, the Proposed Project site does not contain suitable habitat for any candidate, sensitive, or special-status species. The Proposed Project site is disturbed and contains no potential habitat for special-status plants. Surveys conducted for the Approved Subdivision Project did not detect any special-status plants or summer lupine (*Lupinus formosus*), which is the host plant for Mission blue butterfly.

The adjacent knobcone pine and non-native grassland south of the tank site may provide marginal foraging and nesting habitat for raptors; however, the habitat is considered marginal due to wind exposure and lack of large supportive branches that could support raptor nests. Burrowing owl, northern harrier, and white-tailed kite are highly unlikely to nest adjacent to the Proposed Project site due to the lack of suitable nesting habitat such as ground squirrel burrows, dense vegetation, and suitable topography.<sup>8</sup>

The 2016 EIR identified potentially significant impacts to nesting or foraging habitat for burrowing owl, northern harrier, and white-tailed kite. Mitigation Measure 4.3-3a requires protocol-level preconstruction surveys for nesting raptors, and Mitigation Measure 4.3-3b provides instructions for if nesting raptors are found to be present, which would reduce this impact to a less than significant level. The Proposed Project site is disturbed and contains no potential habitat for special-status plants. The impact would be *less than significant*.

The entire site is enclosed by fencing and surrounded by non-native grasses and shrubs and Monterey pine (*Pinus radiata*) trees located at the top of the knoll (Figures 5 through 7). Much of the area surrounding the Proposed Project site is an ongoing construction zone. Although the majority of the adjacent knobcone pine trees have been removed as part of the Approved Subdivision Project, knobcone pine and non-native grassland still exist south of the Proposed Project site and may provide marginal foraging and nesting habitat for raptors. All tree planting associated with the approximately four trees that fell during the winter storms would be replanted outside of the fenced area along the north, east and west sides of the project at a 1:1 ratio. An additional 12 trees are proposed to be removed to make room for the second tank. Those trees would be replaced at a 3:1 ratio, totaling approximately 40 replanted trees as part of project activities. As discussed in Section 4.3.4 of the 2016 EIR, construction noise has the potential to disturb nesting raptors. Mitigation Measures 4.3-3a and 4.3-3b would reduce this potentially significant impact to a less-than-significant level. Therefore, impacts would be *less than significant with mitigation*.

---

<sup>8</sup> Coast Ridge Ecology. 2015. *Results of 2015 Rare Plant Surveys and Update Mission Blue/Pardalis Blue Butterfly Habitat and Nesting Raptor Survey on the Ascension Heights Subdivision Project Site, San Mateo County, California*. April 11.

**Impact 4.3-3 (2016 EIR).** *Less than significant with implementation of Mitigation Measures 4.3-3a and 4.3-3b. See page 4.3-23 of the 2016 EIR.*

- b) *Would the Project have a substantial adverse effect on any riparian habitat or other sensitive natural community identified in local or regional plans, policies, regulations or by the California Department of Fish and Game or US Fish and Wildlife Service?*

Per the 2016 EIR, there is no riparian habitat or other sensitive natural community on the Proposed Project site. *No impact* would occur.

- c) *Would the Project have a substantial adverse effect on federally protected wetlands as defined by Section 404 of the Clean Water Act (including, but not limited to, marsh, vernal pool, coastal, etc.) through direct removal, filling, hydrological interruption, or other means?*

The Proposed Project is located on a hilltop. There are no wetlands or waters on or adjacent to the Proposed Project site. *No impact* would occur.

- d) *Would the Project interfere substantially with the movement of any native resident or migratory fish or wildlife species or with established native resident or migratory wildlife corridors, or impede the use of native wildlife nursery sites?*

The Proposed Project is located on a hilltop. There are no migratory wildlife corridors on the Proposed Project site. There are no wetlands or waters on or adjacent to the Proposed Project site. *No impact* would occur.

The 2016 EIR identified the potential for nesting birds in the annual grassland in the vicinity of the Proposed Project. Potential disruption of nesting migratory birds and other birds of prey during construction could result in nest abandonment or mortality. Likewise, increased human activity and traffic, elevated noise levels, and operation of machinery could also impact birds if their nests are located within the vicinity of development areas. Mitigation Measure 4.3-4a requires preconstruction surveys for nesting birds if construction occurs during the nesting season. Mitigation Measure 4.3-4b sets requirements in case an active nest is found. Mitigation Measure 4.3-4c requires tree removal be conducted outside of nesting bird season. Much of the area surrounding the Proposed Project site is an ongoing construction zone. Although the majority of the adjacent knobcone pine trees have been removed as part of the Approved Subdivision Project, knobcone pine and non-native grassland still exist south of the Proposed Project site and may provide habitat for nesting birds. Construction noise has the potential to disturb nesting birds. Mitigation Measures 4.3-4a 4.3-4b and 4.4-4c would reduce this potentially significant impact to a less-than-significant level. Therefore, this impact would be *less than significant with mitigation*.

**Impact 4.3-4 (2016 EIR).** *Less than significant with implementation of Mitigation Measures 4.3-4a 4.3-4b and 4.3-3c. See page 4.3-25 of the 2016 EIR.*

- e) *Would the Project conflict with any local policies or ordinances protecting biological resources, such as a tree preservation policy or ordinance?*

As identified in the 2016 EIR, the County tree ordinance protects “significant” trees, being identified as any live tree which has a circumference measuring at or greater than 38 inches at a height of 4.5 feet above the ground or immediately below the lowest branch, whichever is lower. “Community of Trees” refers to an aesthetic grouping of trees, the removal of which would cause significant ecological, aesthetic, or environmental impact in the immediate area. An “Indigenous Tree” is one known to be native to the County including any native willow, box elder, buckeye, madrone, oak, or laurel tree.

Tree removal is proposed as part of project activities. All tree planting associated with the approximately four trees that fell during the winter storms would be replanted outside of the fenced area along the north, east and west sides at a 1:1 ratio. An additional 12 trees are proposed to be removed to make room for the second tank. Those trees would be replaced at a 3:1 ratio, totaling approximately 40 replanted trees as part of project activities. Any potential impacts to protected trees would be addressed with Mitigation Measures 4.3-6. This impact would be *less than significant with mitigation*.

***Impact 4.3-6 (2016 EIR). Less than significant with implementation of Mitigation Measures 4.3-6. See page 4.3-26 of the 2016 EIR.***

- f) *Would the Project conflict with the provisions of an adopted Habitat Conservation Plan, Natural Community Conservation Plan, or other approved local, regional, or state habitat conservation plan?*

There are no adopted Habitat Conservation Plan, Natural Community Conservation Plan, or other approved local, regional, or state habitat conservation plans in the project area. *No impact* would occur.

As discussed in the 2016 EIR, cumulative projects in the vicinity of the project site, including growth resulting from build-out of the County General Plan, are anticipated to permanently remove plant and wildlife resources. However, the Proposed Project would be implemented on a developed site with no existing vegetation or nesting or foraging habitat for wildlife. The County would implement mitigation measures designed to avoid, reduce, or mitigate potential impacts to special-status species. With incorporation of mitigation measures, the contribution of the Proposed Project to regional impacts to biological resources would not be cumulatively considerable.

***Impact 4.3-7 (2016 EIR): Less than significant with implementation of Mitigation Measures 4.3-7. See page 4.3-27.***

**Conclusion:** Implementation of the Proposed Project would not result in new or more severe impacts to biological resources than previously disclosed in the 2016 EIR. No new mitigation is necessary, and with incorporation of mitigation measures, the contribution of the Proposed Project to regional impacts to biological resources would not be cumulatively considerable.



### **4.3.3 Energy**

Energy resources were not discussed in the 2016 EIR. Since certification of the Final EIR in February 2016, legislative changes at the state level include comprehensive amendments to the State CEQA Guidelines. On December 28, 2018, California adopted the revised guidelines, which incorporate a new subdivision on energy impacts (Section 15126.2(b)), which clarifies that CEQA requires consideration of whether a project will result in significant environmental effects due to “wasteful, inefficient, or unnecessary consumption of energy” and states that agencies “shall mitigate” any wasteful energy use giving rise to significant impacts.

All impact conclusions remain the same from the 2016 EIR. Applicable mitigation measures are listed below.

#### **4.3.3.1 Environmental Setting**

The Proposed Project site is located within unincorporated San Mateo County, in a residential area of the San Mateo Highlands. The Proposed Project proposes construction of an approximately 59,000-gallon potable water reservoir on private property.

Electricity and natural gas are provided to the County and project site by the Pacific Gas and Electric Company (PG&E). There are existing overhead electrical utility lines adjacent to the Proposed Project site along Bel Aire Road and Ascension Drive. Comcast Corporation provides telecommunications services in the area.

Natural gas is measured in British thermal units (Btu), and electricity is measured in kilowatt hours (kWh). In 2020 total natural gas consumption in San Mateo County was 200 million Btu, which was down from the 2019 consumption of 214 million Btu.<sup>9</sup> In 2020 total energy electricity consumption in San Mateo County was 4,167 million kWh, which was down from the 2019 consumption of 4,342 million kWh.<sup>10</sup>

#### **4.3.3.2 Impacts and Mitigation**

- a) *Would the Project result in potentially significant environmental impact due to wasteful, inefficient, or unnecessary consumption of energy resources, during project construction or operation?*

The Proposed Project would construct an additional water tank and boosting facility that could utilize existing water supplies. Construction of the Proposed Project would result in indirect energy consumption from construction traffic and the use of construction materials. The primary energy demand during construction would occur from use of gasoline- and diesel-powered mobile construction equipment and

---

<sup>9</sup> California Energy Commission (CEC). 2019. *Gas Consumption by County*. Available at: <https://ecdms.energy.ca.gov/gasbycounty.aspx>. Accessed July 6, 2022.

<sup>10</sup> California Energy Commission (CEC). 2019. *Electricity Consumption by County*. Available at: <http://www.ecdms.energy.ca.gov/elecbycounty.aspx>. Accessed July 6, 2022.

vehicles to transport workers and materials to and from the construction site. Electricity would also be used for construction lighting, field services, and electrically driven construction devices such as air compressors, pumps, and other equipment.

The Proposed Project would result in very little indirect energy consumption as a result of post-construction traffic (i.e., operational traffic), such as vehicle trips associated with standard maintenance procedures. Although the Proposed Project would result in increased indirect energy consumption, the amount of transportation fuel and potential electricity use required for Proposed Project operation is not considered an inefficient or wasteful use of energy.

Implementation of the Proposed Project would result in energy use for the proposed water pumps. While the Proposed Project would result in slightly more energy use, the Proposed Project would have a more efficient water pumping system. Emergency lights are proposed and would be located inside the pump motor control panels. These lights would turn on during maintenance activities conducted by CalWater to access electrical controls. Therefore, the Proposed Project would not represent a substantial increase in energy consumption or a wasteful, inefficient, or unnecessary use of energy, and impacts would be *less than significant*.

*b) Would the Project conflict with or obstruct a state or local plan for renewable energy or energy efficiency?*

San Mateo County's General Plan Climate Change Element and Community Climate Action Plans (CCAP) are designed to reduce emissions to meet or exceed State goals. The Proposed Project includes development to serve housing that is currently under construction as part of the Approved Subdivision Project. The Proposed Project is compliant with the Water and Wastewater strategies outlined in the 2022 CCAP.<sup>11</sup> The Proposed Project is consistent with the following policies for GHG reduction:

- WW 1: Water efficiency retrofits for existing buildings
- WW 3: Water efficiency in new construction.

The Proposed Project would not conflict with or obstruct a local plan for renewable energy. Therefore, *no impact* would occur.

**Conclusion:** Implementation of the Proposed Project would not result in new or more severe impacts to energy than previously disclosed in the 2016 EIR. No new mitigation is necessary, and the impact is not cumulatively considerable.

#### **4.3.4 Greenhouse Gas Emissions**

Greenhouse Gas Emissions were discussed under Section 4.2, Air Quality and Greenhouse Gas Emissions, in the 2016 EIR.

---

<sup>11</sup> County of San Mateo. 2022. *Community Climate Action Plan*. Available at: <https://www.smcsustainability.org/wp-content/uploads/SMC-CCAP.pdf> Accessed March 1, 2023.

All impact conclusions remain the same from the 2016 EIR. Applicable mitigation measures are listed below.

#### **4.3.4.1 Environmental Setting**

As discussed in the 2016 EIR, the County's EECAP set a goal to achieve a 17% reduction below 2005 baseline emissions by 2020—exceeding the reduction goal of AB 32. The County met that goal early, achieving a 33% reduction in emissions over 1990 levels in 2017.

Today, the County has a goal of 45% emissions reduction by 2030 and carbon neutrality by 2040. To meet that goal, the County will implement various GHG reduction policies, programs, and activities. The CCAP<sup>12</sup> outlines the County's strategies, and actions are structured around four focus areas including:

**Building Efficiency:** Buildings are the second largest contributor to GHG emissions in unincorporated areas of the county, accounting for 32% of all emissions.

**Transportation:** In 2017 emissions in the transportation sector from vehicle miles traveled (VMT) represented 40% of the county's emissions inventory and was the largest GHG emissions contributor when compared to other sectors.

**Waste:** Waste represents a 26% share of overall county emissions. County goals include measures to prevent materials from entering landfills through source reduction and waste diversion actions.

**Working Lands:** County priorities include active management of working lands to increase carbon sequestration rates in soils and vegetation.

The CCAP includes a list of 16 strategies and policies, with supportive actions and sub-policies intended to reduce communitywide GHG emissions.

#### **4.3.4.2 Impacts and Mitigation**

Since certification of the 2016 EIR, and in response to AB 32, which requires the reduction of GHG emissions to 1990 below levels by 2030, the BAAQMD has updated their CEQA checklist questions. All other impacts and mitigation measures identified in the 2016 EIR remain applicable to the Proposed Project. According to the newly updated BAAQMD GHG thresholds, land-use building project plans must meet one of two requirements:

- a) *Projects must feature an all-electric project design, with no natural gas appliances or plumbing, and not result in any wasteful, inefficient, or unnecessary energy usage. Projects must also achieve a reduction in project-generated vehicle miles traveled (VMT) below the regional average or meet a locally adopted target and achieve compliance with CALGreen Tier 2 off-street electric vehicle requirements. Or,*

---

<sup>12</sup> County of San Mateo County. 2022. *Community Climate Action Plan*. Available at: <https://www.smcsustainability.org/wp-content/uploads/SMC-CCAP.pdf>. Accessed March 1, 2023.

b) *Projects must be consistent with a local GHG reduction strategy that meets the criteria under state CEQA guidelines Section 15183.5(b).*

The Proposed Project does not contain any natural gas appliances or plumbing and would not result in any wasteful, inefficient, or unnecessary energy usage (as stated in Section 4.3.3, Energy, above). The project is compliant with the 2020 San Mateo County Reach Code,<sup>13</sup> which requires that no gas or propane plumbing is installed in new buildings, and that electricity be used as the energy source for water, space heating, cooking, and clothes drying appliances.

The Proposed Project is compliant with the Water and Wastewater strategies outlined in the 2022 CCAP.<sup>14</sup> The Proposed Project is consistent with the following policies for GHG reduction:

- WW 1: Water efficiency retrofits for existing buildings
- WW 3: Water efficiency in new construction.

**Impact 4.2-8 (2016 EIR).** *Less than significant with implementation of Mitigation Measure 4.2-8. See page 4.2-29 of the 2016 EIR.*

**Conclusion:** Implementation of the Proposed Project would not result in new or more severe impacts to greenhouse gas emissions than previously disclosed in the 2016 EIR. No new mitigation is necessary, and the impact is not cumulatively considerable.

## 4.3.5 Hydrology and Water Quality

Hydrology and water quality were discussed under Section 4.6, Hydrology and Water Quality, in the 2016 EIR.

All impact conclusions remain the same from the 2016 EIR. Applicable mitigation measures are listed below.

### 4.3.5.1 Environmental Setting

The Proposed Project site is located approximately 9 miles east of the Pacific Ocean and approximately 7 miles west of the San Francisco Bay within the 1,200-square-mile San Francisco Subbasin (18050004) of the San Francisco Subregion, which includes a 4,470-square-mile area that drains to South San Francisco Bay. The project site is not located within the 100- and 500- year floodplain. The soils onsite

---

<sup>13</sup> County of San Mateo. 2022. *Community Climate Action Plan*. Available at: <https://www.smcsustainability.org/wp-content/uploads/SMC-CCAP.pdf> Accessed March 1, 2023.

<sup>14</sup> County of San Mateo. 2022. *Community Climate Action Plan*. Available at: <https://www.smcsustainability.org/wp-content/uploads/SMC-CCAP.pdf> Accessed March 1, 2023.

are well-drained but have a slow infiltration rate and therefore, high runoff potential when thoroughly wet.<sup>15</sup>

According to the 2016 EIR, the Approved Subdivision Project site does not contain any water features that are waters of the United States or state. Water flow on the site generally drains in a south or westerly direction towards Polhemus Creek. Historically, there was widespread soil erosion onsite. Currently, the site is being graded for the Approved Subdivision Project and has erosion control measures in place. A temporary construction access road has been developed along Bel Aire Road. The project site is fenced with both chain link construction fencing and silt fencing along the fence base. A bioretention basin has been developed in the northwest corner to capture stormwater runoff from the Approved Subdivision Project site.

#### **4.3.5.2 Impacts and Mitigation**

a) *Would the Project violate any water quality standards or waste discharge requirements or otherwise substantially degrade surface or ground water quality?*

Construction of the Proposed Project would involve grading, clearing, and landscaping activities associated with the development of one water tank and pumping system. Construction would result in the temporary disturbance of soil and expose disturbed areas to potential storm events, which could generate accelerated runoff, localized erosion, and sedimentation of local waterways. The Proposed Project would disturb an area of approximately 0.13 acre (5,690 square feet) (See Appendix C, Drainage and Treatment Plan). Disturbed areas and stockpiled soils exposed to winter rainfall could lead to sediment discharge into surface waters, resulting in a degradation of water quality. In addition, construction equipment and materials have the potential to leak, thereby discharging additional pollutants into local waterways. Pollutants potentially include particulate matter, sediment, oils and greases, and construction supplies such as concrete, paints, and adhesives. Changes to drainage patterns resulting from construction activities could result in discharge of these pollutants into surface waterways causing an exceedance of water quality objectives, which could adversely impact beneficial uses of downstream water resources.

The SMCWPPP<sup>16</sup> is a partnership of the City/County Association of Governments (C/CAG), the County, and each incorporated city and town in the county who share a common NPDES permit, also referred to as the Municipal Regional Stormwater Permit (MRP). Similar to the Approved Subdivision Project, construction of the Proposed Project is required to comply with the most recent version of the California NPDES General Permit for Storm Water Discharges Associated with Construction and Land Disturbance Activities (Order No. 2009-0009-DWQ). Since the Proposed Project would disturb approximately 0.13 acre of land, it would not be required to implement a Stormwater Pollution Prevention Plan (SWPPP) but would be required to implement a specific Erosion and Sediment Control Plan (ESCP), which would

---

<sup>15</sup> NRCS, 2019. Custom Soil Survey Report for San Mateo County, California: Ascension Heights Subdivision Project. WebSoil Survey available online at: <http://websoilsurvey.nrcs.usda.gov/app/HomePage.htm>. Accessed March 3, 2023.

<sup>16</sup> County of San Mateo. 2020. *San Mateo Countywide Water Pollution Prevention Program. Construction Webpage*. Available at: <https://www.flowstobay.org/construction>. Accessed June 26, 2022.

include BMPs designed to prevent surface runoff from construction from contaminating adjacent waterbodies.

The MRP, adopted by the SWRCB in November 2015, includes requirements for incorporating Low Impact Development (LID) measures into new development and redevelopment projects. These requirements are known as Provision C.3 requirements. Effective December 1, 2012, specific sizes of small projects must meet site design requirements in Provision C.3.i of the MRP, but not the stormwater treatment or hydromodification measures.<sup>17</sup> This applies to projects that create and/or replace at least 2,500 but less than 10,000 square feet of impervious surface. The Proposed Project would create approximately 479 square feet of additional impervious surface; therefore, Provision C.3 would not be applicable.

The Proposed Project would add approximately 479 square feet of impervious surface area to the existing Cal Water site. In addition, a bioretention area totaling 4,138 square feet would be added. The site design with the bioretention basin would result in a net decrease from existing conditions in the stormwater runoff volume from 0.43 cubic feet per second (cfs) to 0.34 cfs from a 10-year storm event.<sup>18</sup> Since the project design would decrease surface runoff from project operation, no operational impacts would occur.

In the case of emergency pressure changes, the new tank would be equipped with an overflow water system, which would discharge into the onsite storm drain to the bio-retention basin and then offsite to the catch basin to the northwest. The overflow volume would be approximately 3.34 cfs.<sup>19</sup>

Mitigation Measure 4.4-1b requires that an ESCP shall be prepared in accordance with regulatory requirements. As discussed above, implementation of the Proposed Project requires obtaining a San Mateo County Grading Permit, which includes the development of a site-specific ESCP. These regulations would reduce non-point source pollutants from construction through the implementation of BMPs and other control measures that minimize or eliminate pollutants from urban runoff, thereby protecting downstream water sources. BMPs implemented to address commercial pollutant sources generally involve maintenance of storm drain facilities, parking lots, vegetated areas, and dissemination of educational materials. Mitigation Measure 4.4-1b would be implemented and the impact would remain *less than significant with mitigation*.

***Impact 4.4-1b (2016 EIR). Less than significant with implementation of Mitigation Measure 4.4-1b of the 2016 EIR.***

---

<sup>17</sup> San Mateo Countywide Water Pollution Prevention Program. 2020. *C.3 Regulated Projects Guide Version 1.0*. Available at: [C.3 Regulated Projects Guide \(flowstobay.org\)](http://flowstobay.org). Accessed March 13, 2023.

<sup>18</sup> A 10-year storm is a storm event which would be likely to happen once every ten years. It is defined as a storm of 10-minute duration and 2.10 inches per hour rainfall intensity.

<sup>19</sup> Personal email from Julie Huynh (CalWater) to Diana Shu (San Mateo County). RE: PLN2021-00275: New Water Tank - Ascension Heights EIR Addendum Template, dated March 16, 2023.

Since the project design would include a bioretention basin and decrease surface runoff from project operation, operational runoff would not result in an increase in urban runoff. Therefore, with implementation of Mitigation Measure 4.6-2, the impact is reduced to *less than significant*.

***Impact 4.6-2 (2016 EIR). Less than significant with implementation of Mitigation Measures 4.6-2a, 4.6-2b, 4.6-2c. See page 4.6-13 of the 2016 EIR.***

b) *Would the Project substantially decrease groundwater supplies or interfere substantially with groundwater recharge such that the project may impede sustainable groundwater management of the basin?*

As stated in the 2016 EIR, the Proposed Project site does not contain a high groundwater table, evidenced by site surveys and test borings conducted on the Proposed Project site by Michelucci in 2013. The soils on the Proposed Project site are well-drained with a high runoff potential, which reduces the ability of the Proposed Project site to contribute to groundwater recharge of the underlying basin.<sup>20</sup> There are no aquifers below the site or in the vicinity of the Proposed Project site. No pumping activities or drilling of groundwater wells are proposed as part of the Proposed Project. Potable water demands created by the Proposed Project would be served by Cal Water, which is supplied by the Hetch Hetchy Reservoir.

Implementation of the Proposed Project would result in an increase of approximately 479 square feet of impervious surface. The Proposed Project would remove a portion of an existing concrete pad and construct a new adjacent water tank northwest of the existing tank. Although the Proposed Project would increase impervious surface onsite, the proposed installation of catchment areas would allow for treatment and percolation of water into the underlying soils, which would, in turn, contribute to groundwater recharge. Because the Proposed Project does not involve an increase in groundwater extraction, the Proposed Project would not substantially interfere with groundwater recharge such that there would be a net deficit in aquifer volume or lowering of the local groundwater table. The impact would be *less than significant*.

c) *Would the Project substantially alter the existing drainage pattern of the site or area, including through the alteration of the course of a stream or river or through the addition of impervious surfaces, in a manner which:*

i) *Would result in a substantial erosion or siltation on- or off-site?*

As stated in response 4.3.5.2.a, the Proposed Project is required to comply with the most recent version of the California NPDES General Permit for Storm Water Discharges Associated with Construction and Land Disturbance Activities (Order No. 2009-0009-DWQ), which mandates the development and implementation of a site-specific ESCP. Mitigation Measure 4.4-1b outlines the BMPs that shall be incorporated, at a minimum, into the ESCP prepared in accordance with regulatory requirements.

---

<sup>20</sup> NRCS, 2019. Custom Soil Survey Report for San Mateo County, California: Ascension Heights Subdivision Project. WebSoil Survey available online at: <http://websoilsurvey.nrcs.usda.gov/app/HomePage.htm>. March 3, 2023.

Operational runoff from all proposed impervious surfaces would be directed to the onsite facilities where water quality treatment would begin. Bioretention areas remove pollutants by filtering runoff slowly through an active layer of soil. As shown in the updated Impervious Surface and Drainage Exhibit prepared by Lea and Braze Engineering, Inc.,<sup>21</sup> the containment and treatment of stormwater is proposed via the bioretention basin in the northwest corner of the Proposed Project site and a swale in the western portion of the Proposed Project site.

The Proposed Project would result in an additional 479 square feet of impervious surface and includes a bioretention basin. The existing tank overflow drain is currently connected to an existing 6-inch storm drain line on the project parcel. This storm drain line extends to the northeast side of the parcel along a 20-foot-wide easement that ends between 1526 and 1538 Parrot Drive and feeds to a main storm drain line. The Proposed Project's tank overflow line will drain to the bioretention basin in the northwest corner of the Proposed Project area to capture the overflow. The proposed catch basin connects to the onsite 6-inch storm drain that flows to Parrot Drive. Around both tanks are concrete berms with slopes of 1% and 3% to direct runoff to the onsite bioretention basin, as shown on the Tank Foundation and Berm Details figure provided by Cal Water.<sup>22</sup>

Mitigation Measure 4.6-3a is included to require regular maintenance to ensure proper performance of stormwater retention facilities. To ensure off-site drainage associated with the Proposed Project would not exceed the capacity of existing stormwater drainage systems, Mitigation Measure 4.6-3b is included from the Approved Subdivision Project. Therefore, the impact determination for Impact 4.6-3 is *less than significant with mitigation*.

***Impact 4.6-3 (2016 EIR). Less than significant with implementation of Mitigation Measures 4.6-3a and 4.6-3b. See page 4.6-16 of the 2016 EIR.***

- ii) *Would substantially increase the rate or amount of surface runoff in a manner which would result in flooding on- or offsite?*

The Proposed Project incorporates strategies to reduce and manage runoff. Temporary pollution prevention and permanent stormwater BMPs have been designed to minimize the introduction of pollutants into streambeds and drainages. During construction, the contractor would be required to use filter fabric, gravel bags, straw wattles, or similar measures to collect sediment and filter water before allowing its discharge to downstream facilities. This would also require that disturbed areas be seeded to help stabilize un-vegetated areas.

Permanent BMPs include construction of a bioretention basin to capture post-development stormwater runoff during rain events. Additionally, the bioretention basin in the northwest corner of the Proposed Project site would be equipped with overflow drains to minimize inundation on paved surfaces during

---

<sup>21</sup> Lea & Braze Engineering, Inc. 2023. *Impervious Surface and Drainage Exhibit*. February 6. (Appendix B)

<sup>22</sup> California Water Service (Cal Water). 2021. *Site Plans: Foundation Details and Accessories*, Drawing MPS-5643 R3 Detail E on Sheet 2 of 7. April 20. (Appendix A)



larger storm events. With these design measures and implementation of BMPs, impacts would be *less than significant*.

- iii) *Would create or contribute runoff water which would exceed the capacity of existing or planned stormwater drainage systems or provide substantial additional sources of polluted runoff?*

During storm events, rainwater collects atmospheric pollutants and, upon surface impact, gathers roadway contaminant deposits, including oxygen-consuming constituents, suspended solids/particulates, nutrients, heavy metals, trace organics, and microorganisms.

A peak year summary outlined by Lea and Braze Engineering notes that mitigated post-construction peak flows would result in a reduction of 0.09 cfs over existing conditions.<sup>23</sup> Discharge generated from project development would be managed and treated with the construction BMPs through project construction and operation, and construction of the bioretention basin and a swale in the western portion of the Proposed Project site. The Proposed Project has adequate capacity to treat stormwater runoff.

Provisions of the NPDES permit incorporate various prescribed measures into the project design. The Proposed Project would add approximately 479 square feet of impervious surface and is not required to meet the County's C.3 Provisions. Potentially significant effects to water quality resulting from urban runoff would be reduced to less than significant through Proposed Project design features (as required by the NPDES permit and the County's Drainage Manual) and through implementation of the BMPs included in Mitigation Measure 4.6-1 for construction; therefore, *impacts would be less than significant with mitigation*.

- iv) *Would impede or redirect flood flows?*

Refer to responses 4.3.5.2.c.ii and 4.3.5.2.c.iii above for discussion of hydrological impacts. Impacts on flood flows would be *less than significant*.

- d) *Would the Project in flood hazard, tsunami, or seiche zones, risk release of pollutants due to project inundation?*

As discussed in the 2016 EIR, the Proposed Project site is in an area designated Zone X on the Federal Emergency Management Act (FEMA) Flood Map Service Center. Zone X is defined as "(a)reas determined to be outside the 0.2 percent annual chance of a flood plain."<sup>24</sup> Additionally, there are no waterbodies or unstable soil types within or adjacent to the Proposed Project site that could lead to inundation by seiche, tsunami, or mudflow. *No impact* would occur.

---

<sup>23</sup> Lea & Braze Engineering, Inc. 2023. *Impervious Surface and Drainage Exhibit*. February 6. (Appendix B)

<sup>24</sup> FEMA, 2023. Flood Map Service Center. Available at: <https://msc.fema.gov/portal/home>. Accessed March 1, 2023.

e) *Would the Project conflict with or obstruct implementation of a water quality control plan or sustainable groundwater management plan?*

During Proposed Project construction and operation, temporary and permanent BMPs and erosion control measures would be put in place to reduce construction and post-construction erosion and siltation. For more information on BMPs, see responses 4.3.5.2.ci through 4.3.5.2.ciii. The Proposed Project would not conflict with a groundwater management plan or water quality control plan, and impacts would be *less than significant*.

**Conclusion:** Implementation of the Proposed Project would not result in new or more severe impacts to hydrology and water quality than previously disclosed in the 2016 EIR. No new mitigation is necessary, and the impact is not cumulatively considerable.

## 4.3.6 Transportation

Transportation resources were discussed under Section 4.11, Transportation and Circulation, in the 2016 EIR.

### 4.3.6.1 Environmental Setting

The Proposed Project site is located within the unincorporated community of San Mateo Highlands in San Mateo County, at the northeast corner of Bel Aire Road and Ascension Drive, east of I-280 and west of SR-92. Neighboring cities and communities include the city of San Mateo to the northeast, Foster City to the east, and the unincorporated community of Highlands – Baywood Park to the west. Access to the Proposed Project site is primarily provided by Bel Aire Road, Ascension Drive, and Polhemus Road. These roads would provide direct access to the Proposed Project site, temporary construction easements, and staging areas. The Proposed Project area is governed by the CCAG, Countywide Transportation Plan,<sup>25</sup> and Transportation Element of the San Mateo County General Plan.<sup>26</sup>

Roadways that provide circulation to and from the Proposed Project area include:

- Polhemus Road is classified in the County General Plan as a two-lane north/south-oriented arterial highway roadway. Polhemus Road terminates at Crystal Springs Road north of the Proposed Project site and terminates at Ralston Avenue south of the Proposed Project site.
- Ascension Drive, Bel Aire Road, and Laurie Lane are two-lane residential streets that serve the Ascension Heights residential neighborhood. Parking on these streets is generally allowed on either side of the street.

---

<sup>25</sup> City/County Association of Governments of San Mateo County (CCAG). *2040 Countywide Transportation Plan*. Available at: <https://ccag.ca.gov/programs/countywide-transportation-plan/>. Accessed July 8, 2022.

<sup>26</sup> County of San Mateo. 1986. *1986 General Plan. Chapter 12, Circulation*. Available at: <https://www.smcgov.org/media/101521/download?inline=>. Accessed July 8, 2022.

- Parrott Drive is a two-lane north/south arterial roadway that originates at De Anza Boulevard and terminates at Columbia Drive north of the Proposed Project site. Parking along Parrott Drive is generally allowed on either side of the street.
- CSM Drive is a two-lane north/south minor collector that connects Parrott Drive on the west to West Hillsdale Boulevard on the east at the College of San Mateo.

The transportation conditions have not changed since the certification of the 2016 EIR, and all impact conclusions remain the same from the 2016 EIR. Applicable mitigation measures are listed below.

#### **4.3.6.2 Impacts and Mitigation**

Since certification of the 2016 EIR, the 2019 update to the CEQA checklist has added one question and altered some language in the remaining CEQA Transportation section questions. All other impacts and mitigations identified in the 2016 EIR remain applicable to the Proposed Project.

The change in the State CEQA Guidelines resulting from implementation of SB 743, adding Section 15064.3, became effective in 2019. It requires the analysis of VMT instead of a vehicle level of service (LOS) analysis. VMT per capita is calculated as the total annual miles of vehicle travel divided by the total population in an urbanized area. LOS measures vehicular delay, or the additional driving time encountered by drivers during the most congested times of travel (the a.m. and p.m. peak periods). SB 743 prohibits the use of LOS to measure impacts under CEQA and requires agencies to adopt alternative measures of such impacts. Prior to implementation of SB 743, the County used LOS analysis to determine transportation-related environmental impacts under CEQA. The method now being used by the County to measure development-related environmental impacts under CEQA is to assess VMT, using modified California Office of Planning and Research (OPR) recommendations.<sup>27</sup>

a) *Would the Project conflict with a program, plan, ordinance or policy addressing the circulation system, including transit, roadway, bicycle and pedestrian facilities?*

The Proposed Project is consistent with applicable local and regional transportation plans, including the County General Plan Transportation Element and Countywide Transportation Plan.<sup>28,29</sup> Construction-related traffic impacts would be temporary and localized, occurring over the 4-month construction period. The Proposed Project would not result in any road closures or obstruction of alternative transportation infrastructure such as pedestrian walkways, bike paths, or transit stops. Therefore, impacts associated with conflict with local transportation or circulation plans would be *less than significant*.

---

<sup>27</sup> County of San Mateo. 2020. *Change to Vehicle Miles Traveled as Metric to Determine Transportation Impacts under CEQA Analysis, Attachment A*. County of San Mateo, Inter-Departmental Correspondence, Department of Public Works to Board of Supervisors. September 23. Available at: <https://www.smcgov.org/media/46081/download?inline=>. Accessed March 14, 2022.

<sup>28</sup> County of San Mateo. 2013. *San Mateo County General Plan Policies. Chapter 12. Transportation Element.*, Available at: <https://www.smcgov.org/planning/general-plan-policies>. Accessed March 14, 2023.

<sup>29</sup> City/County Association of Governments of San Mateo County (CCAG). *2040 Countywide Transportation Plan*. Available at: <https://ccag.ca.gov/programs/countywide-transportation-plan/>. Accessed July 8, 2022.

The Proposed Project would not significantly change operations and maintenance activities at Cal Water Station 31, Baywood Tank, and would not result in an operational increase in traffic on local roadways. The impact would be *less than significant*.

Construction worker commuter trips would generate the most traffic during the construction period. The Proposed Project would have an average of less than 10 construction workers per day. Construction workers would park onsite during construction in the staging areas, workers would not park on neighborhood roads. Approximately 70 CY of fill material would be imported to the project site with haul trucks. Approximately 70 CY of excavated soil that would not be reused onsite would be hauled offsite to a landfill for disposal. Assuming the trucks are 10 CY capacity, the total Proposed Project haul trips for grading would be 14 trips. Soil importation would be completed at once, and over the course of two days, where the Proposed Project would generate an estimated total of approximately seven round-trip haul truck trips. As stated in the 2016 EIR, the Approved Subdivision Project is not anticipated to result in an unsafe condition for pedestrians and bicyclists, as the implementation of Mitigation Measure 4.11-3 which requires the Approved Subdivision Project to install street lighting. The impact of the Proposed Project would be *less than significant with mitigation*.

***Impact 4.11-3 (2016 EIR). Less than significant with implementation of Mitigation Measure 4.11-3. See page 4.11-10 of the 2016 EIR.***

b) *Would the Project conflict or be inconsistent with CEQA Guidelines § 15064.3, subdivision (b)?*

State CEQA Guidelines Section 15064.3(b) contains criteria for analyzing transportation impacts. Projects that may have a significant impact include land use projects that result in an increase in VMT that exceed an applicable threshold of significance and transportation projects that increase VMT. The Proposed Project does not increase the capacity of Bel Aire Road or Ascension Drive Road and is not anticipated to increase operational-related VMT, considering the Proposed Project is an autonomous facility and would require occasional maintenance trips. The County has not adopted VMT thresholds and relies on the California OPR December 2018 Technical Advisory, which recommends a screening threshold of 110 trips per day. The estimated project trip generation during construction and operation is well below the 110 trips per day screening threshold.

As discussed above, the Proposed Project would generate approximately seven hauling roundtrip trips total. This is well below the 110 vehicle trips per day screening threshold for significance. With additional construction phase trips, the impact would be less than significant. A temporary minor increase in VMT would occur during project construction resulting from worker trips to the Proposed Project site, materials delivery, and material hauling. The completed project would not increase VMT permanently, and given the low trip generation rate, impacts would be *less than significant*.

c) *Would the Project substantially increase hazards due to a geometric design feature (e.g., sharp curves or dangerous intersections) or incompatible uses (e.g., farm equipment)?*

The Proposed Project does not include new streets or introduce incompatible uses, but the Approved Subdivision Project does. Proposed Project staging and construction would occur on an existing, private Cal Water parcel, and the Approved Subdivision Project would require implementation of Mitigation Measure 4.11-4 to ensure impacts are *less than significant with mitigation*.

**Impact 4.11-4 (2016 EIR).** *Less than significant with implementation of Mitigation Measure 4.11-4. See page 4.11-10 of the 2016 EIR.*

d) *Would the Project result in inadequate emergency access?*

Construction and staging of the Proposed Project would occur on a private parcel and would not impede emergency access. The impact is considered *less than significant*.

In the 2016 EIR, the analysis of transportation focused on the year 2030 conditions. Construction of the Proposed Project would be completed before 2030, and operations and maintenance would not change from existing conditions. Therefore, the Proposed Project would not cause impacts to traffic, bikeway and pedestrian facilities, or mass transit in the year 2030, and the impact would be *less than significant*.

**Conclusion:** Implementation of the Proposed Project would not result in new or more severe impacts to transportation than previously disclosed in the 2016 EIR. No new mitigation is necessary, and the impact is not cumulatively considerable.

## **4.3.7 Tribal Cultural Resources**

Tribal Cultural Resources were not discussed in the 2016 EIR.

### **4.3.7.1 Environmental Setting**

AB 52, passed in 2014, required an update to the State CEQA Guidelines to include questions related to tribal cultural resources. Changes to the State CEQA Guidelines were approved as part of the 2018 CEQA Update. Cultural Resources were screened out of the 2016 EIR, and although AB 52 does not require consultation for an addendum, on March 7, 2023, the County sent letters to the following tribe:

- Tamien Nation of Greater Santa Clara County.

The letter notified the tribe of the Proposed Project and requested comments or questions on the Proposed Project. No responses were received.

### **4.3.7.2 Impacts and Mitigation**

a) *Would the Project cause a substantial adverse change in the significance of a tribal cultural resource, defined in Public Resources Code section 21074 as either a site, feature, place, cultural landscape that is geographically defined in terms of the size and scope of the landscape, sacred place, or object with cultural value to a California Native American tribe, and that is:*

i) *Listed or eligible for listing in the California Register of Historical Resources, or in a local register of historical resources as defined in Public Resources Code section 5020.1(k)?*

No tribal cultural resources are known to exist on the Proposed Project site, and no consultation requests were received from the identified local tribe. *No impact* would occur.

i) *A resource determined by the lead agency, in its discretion and supported by substantial evidence, to be significant pursuant to criteria set forth in subdivision (c) of Public Resources Code Section 5024.1. In applying the criteria set forth in subdivision (c) of Public Resource Code Section 5024.1, the lead agency shall consider the significance of the resource to a California Native American tribe?*

No tribal cultural resources are known to exist on the Proposed Project site, and no consultation requests were received from the identified local tribe. *No impact* would occur.

**Conclusion:** Implementation of the Proposed Project would not result in impacts to tribal cultural resources. No mitigation is necessary, and the impact is not cumulatively considerable.

### **4.3.8 Utilities**

Utilities resources were discussed under Section 4.10, Public Services, Utilities, and Recreation, in the 2016 EIR.

All impact conclusions remain the same from the 2016 EIR. Applicable mitigation measures are listed below.

#### **4.3.8.1 Environmental Setting**

The Cal Water Bayshore District (BSD) (also known as Mid-Peninsula District) provides potable water supply to the Proposed Project site and surrounding areas. It is estimated that the BSD's service area population was 137,486 in 2020. Cal Water has an annual purchased water supply from the City and County of San Francisco's Regional Water System, operated by the San Francisco Public Utilities

Commission (SFPUC), of approximately 13 million gallons per day (mgd) (14,563-acre feet per year [AFY]) in normal hydrologic years.<sup>30</sup>

The Proposed Project site is not connected to sewer facilities. Electricity and natural gas are provided by PG&E to the County and project site. There are existing overhead electrical utility lines adjacent to the Proposed Project site along Bel Aire Road and Ascension Drive. Per Condition 5, all utilities serving the subdivision are required to be installed underground, where utility construction is currently underway.

All impact conclusions remain the same from the 2016 EIR. Applicable mitigation measures are listed below.

#### **4.3.8.2 Impacts and Mitigation**

- a) *Would the Project require or result in the relocation or construction of new or expanded water, wastewater treatment or storm water drainage, electric power, natural gas, or telecommunications facilities, the construction or relocation of which could cause significant environmental effects?*

The Proposed Project includes development of a water tank and boosting facility pump. The Proposed Project would connect to and utilize local wastewater services, including the sewer systems owned and operated by Cal Water and the Town of Hillsborough and the wastewater treatment plant (WWTP) owned and operated by the City of San Mateo. There would be no service disruption during project construction.

The Proposed Project would connect the existing and new tank site into the stormwater system. As discussed in Section 4.3.5 of this EIR Addendum, the project would add approximately 479 square feet of impervious surface area but would also add approximately 4,138 square feet of a bioretention basin (See Appendix B, Impervious Surface and Drainage Exhibit). As a net result, the Proposed Project would decrease existing runoff rate from the Proposed Project site by 0.9 cfs.

The Proposed Project would supply water but would not use water; the Approved Subdivision Project requires construction of new water facilities. Mitigation Measure 4.10-2a includes compliance with water shortage contingency plan. Mitigation Measure 4.10-2b from the 2016 EIR includes the installation of pumping facilities at the Proposed Project site. Mitigation Measure 4.10-2c includes relocation of two water mains to allow for Cal Water Easements along Parrot Drive and Bel Aire Drive. Mitigations outlined in the 2016 EIR would still apply, and the impact of the Proposed Project would be considered *less than significant with mitigation*.

*Impact 4.10-2 (2016 EIR). Less than significant with implementation of Mitigation Measure 4.10-2a, 4.10-2b and 4.10-2c. See page 4.10-26 in the 2016 EIR.*

As discussed above, the Proposed Project would decrease existing runoff rate from the Proposed Project site by 0.9 cfs. The Approved Subdivision Project has installed bioretention basin and swale facilities,

---

<sup>30</sup> California Water Service, 2021. 2020 Urban Water Management Plan, Mid-Peninsula District. Available online at: [https://www.calwater.com/docs/uwmp2020/MPS\\_2020\\_UWMP\\_FINAL.pdf](https://www.calwater.com/docs/uwmp2020/MPS_2020_UWMP_FINAL.pdf). Accessed July 8, 2022.

which has been completed. Mitigation Measure 4.10-3 has been completed and does not apply to the Proposed Project. Impacts would remain *less than significant with mitigation*.

**Impact 4.10-3 (2016 EIR).** *Less than significant with implementation of Mitigation Measures 4.10-3. See page 4.10-27 of the 2016 EIR.*

As discussed above, the Proposed Project would decrease existing runoff rate from the site by 0.9 cfs. Mitigation Measure 4.6-3a is included to require regular maintenance to ensure proper performance of stormwater retention facilities. To ensure off-site drainage associated with the Proposed Project would not exceed the capacity of existing stormwater drainage systems, Mitigation Measure 4.6-3b is included from the Approved Subdivision Project. Therefore, the impact determination for Impact 4.10-4 is *less than significant with mitigation*.

**Impact 4.10-4 (2016 EIR).** *Less than significant with implementation of Mitigation Measures 4.6-3a and 4.6-3b and 4.10-4. See pages 4.6-16 and 4.10-27 of the 2016 EIR.*

b) *Would the Project have sufficient water supplies available to serve the project and reasonably foreseeable future development during normal, dry and multiple dry years?*

The Proposed Project site is currently connected to municipal water, and operation of the Proposed Project would result in increased water supply. The Proposed Project would use negligible water during construction and would not use water during project operation. The potable water would be used for the new residential development associated with the Approved Subdivision Project. Therefore, impacts would be *less than significant*.

c) *Would the Project result in a determination by the wastewater treatment provider, which serves or may serve the project that it has adequate capacity to serve the project's projected demand in addition to the provider's existing commitments?*

The Proposed Project would not generate wastewater. There are no wastewater connections proposed as part of the project. The impact of the Proposed Project would be *less than significant*.

d) *Would the Project generate solid waste in excess of state or local standards, or in excess of the capacity of local infrastructure, or otherwise impair the attainment of solid waste reduction goals?*

All waste produced in unincorporated communities is sent to Corinda Los Trancos Landfill (Ox Mountain), operated by Browning Ferris Industries. According to the California Department of Resources Recycling and Recovery (CalRecycle) Facilities Search, the Corinda Los Trancos Landfill has a cease operation date of January 1, 2034; therefore, the landfill has capacity to accept the Proposed Project waste.<sup>31</sup>

---

<sup>31</sup> California Department of Resources Recycling and Recovery (CalRecycle). 2019. SWIS Facility Detail: Corinda Los Trancos Landfill. Available at: <https://www2.calrecycle.ca.gov/SolidWaste/SiteActivity/Details/1561?siteID=3223>. Accessed March 2, 2023.



Construction of the Proposed Project would require the disposal of up to 70 CY of fill. Clean materials could be deposited at various locations available to Cal Water; materials may be reused onsite, used for fill at another location, or sold. If determined to be hazardous (e.g., pesticide residuals, heavy metals), the material may require disposal at an approved facility.

Operation and maintenance of the Proposed Project would include periodic maintenance by Cal Water employees, which would generate a minimal amount of solid waste. The Proposed Project would not require new or expanded solid waste facilities. *No impact* would occur.

e) *Would the Project comply with federal, state, and local management and reduction statutes and regulations related to solid waste?*

The primary state legislation regarding solid waste is AB 939, the California Integrated Waste Management Act, adopted in 1989. AB 939 required local jurisdictions to achieve a minimum 50% solid waste diversion rate by 2000. The Proposed Project would include construction and materials disposal and recycling. The Proposed Project would comply San Mateo County Code Chapter 4.04, which describes the responsibilities and requirements for owners, occupants, and service providers regarding solid waste collection, storage, recycling, and disposal. All waste produced in unincorporated communities is sent to Corinda Los Trancos Landfill (Ox Mountain), operated by Browning Ferris Industries. The Proposed Project would not conflict with state or local laws governing construction or operational solid waste diversion and would comply with local implementation requirements. Therefore, impacts would be *less than significant*.

**Conclusion:** Implementation of the Proposed Project would not result in new or more severe impacts to utilities than previously disclosed in the 2016 EIR. No new mitigation is necessary, and the impact is not cumulatively considerable.

### **4.3.9 Wildfire**

Wildfire was discussed under Section 4.7, Hazards and Hazardous Materials, in the 2016 EIR.

Since certification of the Final EIR in February 2016, legislative changes at the state level have altered the CEQA checklist for evaluating wildfire. Changes to the State CEQA Guidelines approved as part of the 2018 State CEQA Guidelines Update identifies wildfire as a separate environmental resource area, breaking it out so it is no longer a subset of hazards and hazardous materials.

#### **4.3.9.1 Environmental Setting**

The Proposed Project site is located within the County Local Responsibility Area (LRA) produced by the California Department of Forestry and Fire Protection (CAL FIRE). CAL FIRE maps designate the project site in a Very High Fire Hazard Severity Zone (VHFHSZ).<sup>32</sup> This designation is based on data and

---

<sup>32</sup>California Department of Forestry and Fire Protection (CalFIRE). 2022. FHSZ Viewer. Available: <https://egis.fire.ca.gov/FHSZ> .Accessed December 20, 2022.

models of potential fuels over a 30-to 50-year time horizon and their associated and expected fire behavior and expected burn probabilities to quantify the likelihood and nature of vegetation fire exposure (including firebrands) to buildings. The County designates the project site and surrounding areas as a Community at Risk Zone. Housing developments, a community college, and other urban residential development surround the project site. This area east of I-280 contains more than 95% of the urbanized land in the county and is developed with a mix of principal urban land uses, including industrial, commercial, and residential.<sup>33</sup> The existing 216,000-gallon tank on the Proposed Project site is used for fire protection and is not the primary source for domestic usages.

#### **4.3.9.2 Impacts and Mitigation**

*If located in or near state responsibility areas or lands classified as very high fire hazard severity zones,*

a) *Would the Project substantially impair an adopted emergency response plan or emergency evacuation plan?*

The Proposed Project area is located in a County LRA that is a VHFHSZ. The Proposed Project would change the private road alignment through construction of a new driveway on the Proposed Project site's western border. This driveway would be developed in accordance with County standards and would connect to Bel Aire Road. Construction activities could occur within County roadways; however, the Proposed Project site is at the terminus of a dead end road. Given the location of construction and the duration of the construction period, construction activities would not impair evacuation procedures in the event of an emergency, and there would be *no impact*. Operation and maintenance would include periodic visits by one or two employees and would not impact emergency response plans. The project would improve the water supply for fighting fires.

b) *Would the Project due to slope, prevailing winds, and other factors, exacerbate wildfire risks, and thereby expose project occupants to, pollutant concentrations from a wildfire or the uncontrolled spread of a wildfire?*

The Proposed Project is located in a County LRA that is a VHFHSZ. The Proposed Project activities would require construction and maintenance crews in the area during construction and operation. There is a potential that a fire could expose workers to risk of injury or death involving wildland fires. Implementation of Mitigation Measures 4.7-3a and 4.7-3b would ensure that impacts are considered *less than significant with mitigation*.

***Impact 4.7-3 (2016 EIR). Less than significant with implementation of Mitigation Measure 4.7-3a and 4.7-3b. See page 4.7-11 of the 2016 EIR.***

---

<sup>33</sup> County of San Mateo. 1986. *1986 General Plan. Chapter 12, Circulation*. Available at: <https://www.smcgov.org/media/101521/download?inline=>. Accessed July 8, 2022.

- c) *Would the Project require the installation or maintenance of associated infrastructure (such as roads, fuel breaks, emergency water sources, power lines or other utilities) that may exacerbate fire risk or that may result in temporary or ongoing impacts to the environment?*

The construction and operation of the Proposed Project would require connections to existing utility infrastructure, which are proposed to be undergrounded, posing no risk to fire combustion. The Proposed Project proposes a new 15-foot access road on the western side of the Proposed Project site and new water supply infrastructure. The existing water tank on the Proposed Project site is used for fire protection and is not the primary source for domestic usage. Therefore, impacts would be *less than significant*.

- d) *Would the Project expose people or structures to significant risks, including downslope or downstream flooding or landslides, as a result of runoff, post-fire slope instability, or drainage changes?*

The Proposed Project area is located in a County LRA that is a VHFHSZ. Because geologic conditions have not changed since the 2016 EIR, findings made in the site-specific 2013 Geotechnical Investigation conducted by Michelucci & Associates would still apply.

Mitigation Measures 4.4-2a, 4.4-2b, and 4.4-2c would ensure that development of the water tank would not increase downslope flooding or landslide potential. Therefore, impacts would be *less than significant with mitigation*.

***Mitigation Measure 4.4-2a, 4.4-2b, and 4.4-2c. See Page 4.4-14 of the 2016 EIR.***

**Conclusion:** Implementation of the Proposed Project would not result in new or more severe impacts to wildfire than previously disclosed in the 2016 EIR. No new mitigation is necessary, and the impact is not cumulatively considerable.

## **4.4 GROWTH INDUCEMENT**

Completion of the project as presently proposed with modifications for development of the water tank and supporting infrastructure would not affect the project's potential for growth inducement, beyond what was analyzed in the 2016 EIR. As the proposed water tank and associated infrastructure would only serve the residences of the Approved Subdivision Project, the total amount of development and population associated with the approved project remains unchanged.

## **4.5 CUMULATIVE IMPACTS**

The cumulative analysis in Chapter 5.2 of the 2016 EIR evaluated cumulative impacts using a combined approach of a list of reasonably foreseeable projects along with the specifications of the adopted General Plan. The list of reasonably foreseeable projects is shown in EIR Table 5-1, Foreseeable Development Projects (see pp. 5-1 of the January 2016 Final EIR). Where impact analysis is based on more general principles, the specifications of the County of San Mateo General Plan were used to determine cumulative

impacts. A review of the list of reasonably foreseeable projects identified in the EIR for the cumulative analysis indicates that the list, including the Ascension Heights Subdivision Project, has not changed, although certain projects have already been implemented.

The Ascension Heights Subdivision Project has not been fully implemented, and the Proposed Project is not expected to increase the severity of previously analyzed cumulative impacts. This is due in part to the fact that the proposed size and amount of development on the project site would remain the same as originally analyzed, and because geologic impacts of the project are site-specific and would not combine with any resulting from other nearby development projects to result in any cumulative impacts.

By definition, regional air pollution is largely a cumulative impact in that no single project is sufficient in size to, by itself, result in non-attainment of air quality standards. Instead, a project's individual emissions are considered to contribute to the existing, cumulative air quality conditions. If a project's contribution to cumulative air quality conditions is considerable, then the project's impact on air quality would be considered significant.<sup>34</sup> Given this, the updated impact analysis confirms that the project, as modified, would result in criteria air pollutant emission levels below these thresholds and would not result in a cumulatively considerable net increase in the level of nonattainment criteria air pollutants (ozone precursors or PM).

While temporary construction traffic would increase both in number of truck trips and in duration, the increases would not result in long-term traffic noise, traffic effects, or permanent increases in VMT that could combine with other development in the vicinity to cause new significant noise or transportation impacts. Thus, cumulative impacts under each environmental resource identified above would not be significantly increased as a result of the project modifications necessary to develop the additional water tank.

---

<sup>34</sup> BAAQMD, CEQA Air Quality Guidelines, May 2017, [http://www.baaqmd.gov/~media/files/planning-and-research/ceqa/ceqa\\_guidelines\\_may2017-pdf.pdf?la=en](http://www.baaqmd.gov/~media/files/planning-and-research/ceqa/ceqa_guidelines_may2017-pdf.pdf?la=en), accessed March 1, 2021.

## **CHAPTER 5. CONCLUSION**

On the basis of the discussion and analysis presented above, the information presented in the Ascension Heights Subdivision Project EIR certified by the Board on February 9, 2016, remains valid and requires only minor modifications, and all conclusions in the Final EIR are applicable to the approved project.

Minor changes to Mitigation Measure 4.2-1b are recommended to maintain the original intent and effect of the mitigation measure. Since certification of the Final EIR and approval of the project, and due to the timing of project implementation, diesel emission control technologies for off-road construction equipment fleets have improved and thus warrant modifications to the approved construction air quality mitigation measure.

As demonstrated by the updated analysis, the original project and the project as modified would not exceed significance thresholds after implementation of mitigation measures. Therefore, there are no changed circumstances relevant to the undertaking of the project, as modified for completion, that would cause new significant environmental impacts or cause a substantial increase in the severity of previously identified significant effects. No new information has become available that would substantially affect the analysis or conclusions in the Final EIR. Therefore, no major revision of the EIR is required and no additional environmental review is required beyond this EIR addendum.

*This page intentionally left blank.*

## **APPENDIX A**


### **Site Plan**

# MPS - SAN MATEO STATION 031 - ASCENSION DR & BEL AIRE RD INSTALL TANK AND BOOSTER PUMP

**STATION ADDRESS**  
OFF OF BEL AIRE ROAD, SAN MATEO, CA  
94551 ALAMEDA COUNTY  
APN# 098-034802000

**LANDSCAPE LEGEND:**  
 PROPOSED TREES  
 PROPOSED SHRUBS  
 EXISTING TREES

**LEGEND:**  
 TEE  
 ELBOW, 45°  
 ELBOW, 90°  
 BLOWOFF (PROPOSED)  
 BLOWOFF (EXISTING)  
 GATE VALVE (PROPOSED)  
 GATE VALVE (EXISTING)  
 REDUCER (PROPOSED)  
 REDUCER (EXISTING)  
 SOLID PLUG  
 PROPOSED WATER MAIN  
 EXISTING WATER MAIN  
 WALL  
 SANITARY SEWER  
 STORM DRAIN  
 FIRE HYDRANT (PROPOSED)  
 FIRE HYDRANT (EXISTING)  
 BUTTERFLY VALVE  
 CHECK VALVE  
 FLEX CPLG.  
 ALTITUDE VALVE




**CONTACT INFO:**  
 PROJECT ENGINEER: JULIE HUYNH  
 CALIFORNIA WATER SERVICE COMPANY  
 1720 N. FIRST ST.  
 SAN JOSE, CA 95112  
 PH: 408-367-8394  
 EMAIL: JHUYNH@CALWATER.COM  
 LEIGHTON LOW  
 BAYSHORE SUPERINTENDENT  
 341 DELAWARE STREET  
 SAN MATEO, CA 94401  
 (650) 642-4557  
 EMAIL: LLOW@CALWATER.COM  
 GEOTECHNICAL ENGINEER-OF-RECORDS:  
 JOSEPH MICHELUCCI  
 MICHELUCCI & ASSOCIATES, INC.  
 GEOTECHNICAL CONSULTANTS  
 1801 MURCHISON DRIVE, SUITE 210  
 BURLINGAME, CALIFORNIA, 94010  
 joe@michelucci.com  
 (650) 692-0163

**PROPOSED FACILITIES:**  
 • 50,000 GALLON STEEL TANK BOLTED TANK 20'-0" DIAMETER, 24 FT HEIGHT (COLOR GROUSE TAN)  
 • IMPERVIOUS SURFACE: 3,000 SF (ON PROPERTY), 500 SF (PRIVATE DRIVEWAY)  
 • BOOSTER PUMPS/ACOUSTIC SHELTER (COLOR GROUSE TAN)  
 • TANK LEVEL TRANSDUCER AND ENCLOSURE  
 • BOOSTER PUMP CONTROL PANEL (MCC) (COLOR GROUSE TAN) & A  
 • FLOWMETER AND ALTITUDE VALVE IN VAULTS

**SEISMIC DESIGN PARAMETERS:**

1. USE GROUP	=	I
2. IMPORTANCE FACTOR	=	1.0
3. SITE SOIL CLASS	=	B
4. 0.2-SECOND MAPPED SPECTRA ACCELERATION	=	2.313g
5. 1-SECOND MAPPED SPECTRA ACCELERATION	=	0.967g
6. SHORT PERIOD SITE COEFFICIENT	=	0.8
7. LONG PERIOD SITE COEFFICIENT	=	0.8
8. IMPULSIVE DESIGN ACCELERATION	=	1.388g
9. CONVECTIVE DESIGN ACCELERATION	=	0.516g
10. VERTICAL DESIGN ACCELERATION	=	0.300g




**GENERAL NOTES:**

- PROPERTY BOUNDARY SHOWN HEREON IS APPROXIMATE FOR REFERENCE ONLY. ELEVATION DATA IS BASED ON AN ASSUMED DATUM AND IS NOT BASED ON AN ESTABLISHED CITY OR STATE ELEVATION DATUM.
- TANK, EXTERIOR APPURTENANCES AND ABOVE GROUND PIPING SHALL BE PAINTED CWS "GROUSE TAN".
- EXTERIOR FINISH COLOR SHALL BE SHERWIN WILLIAMS CWS (COLOR GROUSE TAN) OR APPROVED EQUIVALENT.
- SEE DRAWING NO. MPS-5642 FOR EROSION CONTROL REQUIREMENTS.
- CONTRACTOR SHALL PROVIDE AS-BUILT DRAWINGS, CLEARLY MARKED TO SHOW ALL CHANGES FROM THE CONSTRUCTION DRAWINGS. PROJECT ALL SITE ELEMENTS WHICH ARE NOT INDICATED FOR REMOVAL, INCLUDING BUT NOT LIMITED TO PAVING, STRUCTURES, SIGNS, TREES AND VEGETATION.
- ALL MATERIALS GENERATED BY DEMOLITION ACTIVITIES, WHICH ARE NOT INDICATED FOR SALVAGE FOR RE-USE, SHALL BE LEGALLY DISPOSED OF OFF THE COMPANY'S PROPERTY.
- EXTREME CARE SHALL BE TAKEN TO PROTECT THE ROOT SYSTEMS OF EXISTING TREES THAT ARE WITHIN 6' OF THE CONSTRUCTION ZONE.

**DRAWING INDEX:**

PLOT PLAN AND ELEVATION (3 SHEETS)	MPS-5629 R5
GRADING PLAN	MPS-5641 R4
EROSION CONTROL PLAN (3 SHEETS)	MPS-5642 R3
PIPING PLAN (3 SHEETS)	MPS-5630 R4
STEEL BOLTED TANK AND DETAILS (7 SHEETS)	MPS-5643 R3
CALIFORNIA WATER SERVICE STANDARD DETAILS (2 SHEETS)	CWDGWS
C.W.S.CO MATERIALS, INSTALLATION & DISINFECTION SPECIFICATION	CW-863 R6
BOOSTER PUMP FOUNDATION PLAN AND DETAILS	MPS-5644
PANELBOARD, HYDRAULIC ENCLOSURE & GENERATOR TAP BOX FOUNDATION PLAN & DETAILS	MPS-5657
SITE PLAN AND SINGLE LINE DIAGRAM	MPS-5476 R2
CONDUIT LAYOUTS AND DETAILS (3 SHEETS)	MPS-5597 R2
RTU TERMINAL DRAWING	MPS-5596
ELECTRICAL SCHEMATIC (2 SHEETS)	MPS-5595
PANELBOARD LAYOUT (2 SHEETS)	MPS-5598
HYDRAULIC ENCLOSURE	MPS-5599



**ENGINEERING**  
  
**DEPARTMENT**  
 REVISIONS:  
 R1-(7/19/21) UPDATED DRAWING INDEX  
 R2-(9/9/21) PER COUNTY REVIEW COMMENTS  
 R3-(9/24/21) PER COUNTY REVIEW COMMENTS  
 R4-(6/27/2022) ADD NEW TRANSFORMER & MCC PADS DUE TO NO 50' LINE & 60'-RETENTION 2/17/23

**DISTRIBUTION** DATE: DTG:  
 FILE:   
 PRINT:   
 SYSTEM:   
 STATION:   
 SCHEMATIC:

**PLAT SHEET NO.:**  
SM-31-22

**SCALE:**  
AS SHOWN

**DRAWN BY:**  
D. HEARN

**DESIGNED BY:**  
J. HUYNH

**TECH REVIEW:** DATE:

**CHECKED BY:** DATE: 5/31/2023

**APPROVED BY:** DATE: 6/1/2023

**TITLE:**  
MPS - SAN MATEO STA 031  
INSTALL TANK AND BOOSTER PUMP  
PLOT PLAN & ELEVATION

**DISTRICT:**  
116-MPS

**SAN MATEO**

**DATE:**  
4/7/2021

**PROJECT ID:**  
00118772


**DRAWING NO.:**  
MPS-5629 R5

**SHT 1 OF 3**


USERNAME: jhuynh\_5/31/2023 3:52 PM  
 FILENAME: G:\Capital\_Projects\116\_Mid\_Peninsula\00118772\_Sta\_31\_ASCENSION HEIGHTS BAYWOOD TANK\2 - DESIGN\500 - Drawings\working drawings\MPS5629\_Plot\_Plan\_& Elevation\_4-24-2023.dwg



USERNAME: D:\Users\4/24/2023 7:46 AM  
 FILENAME: G:\Capitol\_Projects\116\_Mid\_Peninsula\00118772\_Station\_31\_ASCENSION HEIGHTS BAYWOOD TANK\2 - DESIGN\500 - Drawings\working drawings\MPS5629 - Plot\_Plan\_& Elevation\_4-24-2023.dwg



**WEST ELEVATION VIEW**  
N.T.S.



**TYPICAL WOOD FENCE**

SCALE: 1/2" = 1' - 0"

ENGINEERING



DEPARTMENT

REVISIONS:  
 R1-(7/19/21) UPDATED  
 DRAWING INDEX  
 R2-(9/9/21) PPR COUNTY  
 REVIEW COMMENTS  
 R3-(9/24/21) PER COUNTY  
 REVIEW COMMENTS  
 R4-(6/24/2022) ADD NEW  
 TRANSFORMER & MCC PANS DET  
 15'-HIG. ST. LANE & 80'-EXTENSION  
 7/17/23

DISTRIBUTION MAP  DATE: DWT:  
 PLAN SHEET   
 SYSTEM SCHEMATIC   
 STATION SCHEMATIC

PLAT SHEET NO.:

SM-31-22

SCALE:

AS SHOWN

DRAWN BY:

D. HEARN

DESIGNED BY:

J. HUYNH

TECH REVIEW: DATE:

5/18/2023

CHECKED BY: DATE:

APPROVED BY: DATE:

6/1/2023



MPS - SAN MATEO STA 031  
 INSTALL TANK AND BOOSTER PUMP  
 PLOT PLAN & ELEVATION

TITLE:

DISTRICT:

116-MPS

SAN MATEO

DATE:

4/7/2021

PROJECT ID:




00118772

DRAWING NO.:

MPS-5629 R5




SHT 2 OF 3

USERNAME: D:\24\2023\7-47 AM  
 FILENAME: G:\Capitol\Projects\116\_Mid\_Peninsula\00118772\_Station\_31\_ASCENSION HEIGHTS BAYWOOD TANK V2 - DESIGN\500 - Drawings\working drawings\MPS5629 - Plot\_Plan\_& Elevation\_4-24-2023.dwg




**FENCE ASSEMBLY (TYPE 1 AND TYPE 3)**  
 1. ALL PIPE SIZES ARE OUTSIDE DIAMETER  
 2. ALL BOLTS ARE 3/8"x1-1/4" CARRIAGE BOLTS

**FENCE ASSY TYPE 2**



**FENCE TYPE: (CHECK ONE)**  
 TYPE 1  TYPE 2  TYPE 3

- NOTES:**
- BARBED WIRE SHOULD BE EVENLY SPACED, POLYMER COATED 12 GAUGE STEEL WIRE WITH 4-POINT ROUND STEEL BARBS. CONCERTINA WIRES TO BE ADDED IN CONJUNCTION WITH BARBED WIRE AS NEEDED.
  - PULL POSTS ARE REQUIRED AT ALL ABRUPT CHANGES OF GROUND SLOPE AND AT A MAXIMUM OF 300' SPACING ON STRAIGHT RUNS OR UNIFORM SLOPES.
  - GATE HINGES ARE TO BE HEAVY, STRONG, MALLEABLE IRON WITH WELDED PIN OR HEX BOLT DESIGN.
  - ALL GATES ARE TO BE EQUIPPED WITH CATCH POSTS AND GATE STOPS TO HOLD GATE IN OPEN POSITION.
  - EXTENSION ARMS SHALL BE MALLEABLE IRON OR 14GA. MIN. THICKNESS PRESSED STEEL.
  - END, CORNER, ANGLE AND LINE POSTS TO BE 2-7/8" O.D., SCH. 40 AND 2" ARM EXTENSIONS TO BE POINTED AWAY FROM PROPERTY.
  - DOUBLE DRIVE GATES ARE TO HAVE PLUNGER TYPE LATCH AND PADLOCK ATTACHMENT. FLUSH PLATE AND ANCHOR TO RECEIVE PLUNGER BAR TO BE SET IN CONCRETE.
  - DIAGONAL BRACE OF 3/8" TRUSS ROD WITH TURN BUCKLE TO BE INSTALLED AT END, GATE, CORNER, ANGLE AND PULL POSTS.
  - FABRIC SHOULD ALSO BE TIED TO RAILS AND LINE POSTS WITHIN FOUR (4) INCHES OF THE TOP AND BOTTOM OF THE FABRIC WITH 9-GAUGE HOG RINGS.
  - BOTTOM OF FENCE FABRIC SHOULD BE SECURED TO BOTTOM RAIL AND SECURED AT MIDPOINT BETWEEN THE FENCE POSTS ALONG THE FENCE LINE. BOTTOM RAIL SHOULD BE SECURE IN-BETWEEN POLES USING GALVANIZED ALUMINUM EYEBOLT EMBEDDED IN CONCRETE. PLEASE SEE FENCING FOOTING SCHEDULE FOR CONCRETE DEPTH.
  - THESE STANDARDS ARE INTENDED TO ESTABLISH A MINIMUM QUALITY REQUIREMENT. SUITABLE EQUIVALENTS MAY BE ACCEPTED BY THE ENGINEER.



**FENCE FOOTING SCHEDULE**

HEIGHT	GATE OPENING/ POST SPACING	DEPTH "D"	WIDTH "W"
6'-0"	3'-0"	3'-0"	12"
6'-0"	10'-0"	3'-0"	12"
6'-0"	16'-0"	3'-0"	12"
8'-0"	3'-0"	3'-0"	12"
8'-0"	10'-0"	3'-0"	12"
8'-0"	16'-0"	3'-0"	16"

**NOTES:**

- CONCRETE USED FOR FOOTING SHALL BE A MINIMUM 2500 PSI AT 28 DAYS OF AGE.
- WITH HARD GROUND OR PAVEMENT, FENCE MUST REACH WITHIN 2 INCHES OF SURFACE. IF SOFT GROUND, FENCING MUST REACH BELOW THE SURFACE DEEP ENOUGH TO COMPENSATE FOR SHIFTING SOIL AND SAND AND TO DETER ENTRY BY EASILY DIGGING BELOW THE FENCE.

**ENGINEERING**

**DEPARTMENT**

REVISIONS:  
 R1-(7/19/21) UPDATED DRAWING INDEX  
 R2-(9/9/21) PER COUNTY REVIEW COMMENTS  
 R3-(9/24/21) PER COUNTY REVIEW COMMENTS  
 R4-(5/22/22) ADD NEW TRANSFORMER & MCC PANS DET 15-100 50 AMP R & 80-150-100 27/17/23

DISTRICTION MAP  DATE:   
 PLAN SHEET   
 SYSTEM SCHEMATIC   
 STATION SCHEMATIC

DATE:

PLAT SHEET NO.: **SM-31-22**

SCALE: **AS SHOWN**

DRAWN BY: **D. HEARN**

DESIGNED BY: **J. HUYNH**

TECH REVIEW:  DATE: **5/18/2023**

CHECKED BY:  DATE:

APPROVED BY:  DATE: **6/1/2023**

**MPS - SAN MATEO STA 031**  
**INSTALL TANK AND BOOSTER PUMP**  
**PLOT PLAN & ELEVATION**

TITLE:

DISTRICT: **116-MPS**

**SAN MATEO**


DATE: **4/7/2021**

PROJECT ID: **00118772**


DRAWING NO.: **MPS-5629 R5**

SHT 3 OF 3

USERNAME: jhuynh\_5/31/2023 3:55 PM  
 FILENAME: G:\Capitol\_Projects\116\_Mid\_Penninsula\00118772\_Sta\_31\_ASCENSION HEIGHTS BAYWOOD TANK\2 - DESIGN\500 - Drawings\working drawings\MPS5641\_Grading Plan 4-24-2023.dwg




**SITE PLAN**  
 SCALE: 1" = 15'




**REMOVABLE BOLLARD**  
 N.T.S.

**NOTE:**


- THE STEEL PIPE ABOVE GROUND SHALL BE PAINTED A MIN. OF 2 COATS OF ZINC CHROMATE PRIMER (YELLOW).
- DISTRICT PERSONNEL WILL FIELD LOCATE BOLLARDS.







**SECTION A-A**  
 N.T.S.



**MAINTENANCE AREA GRADING DETAIL**  
 N.T.S.



**ASPHALT PAVING DETAIL**  
 N.T.S.



**VICINITY MAP**  
 Not to Scale

**DEMOLITION & GRADING NOTES:**

- THE LIST OF MATERIALS FOR THIS PROJECT IS FOR REFERENCE PURPOSES ONLY, AND IS NOT INTENDED AS A FULL TAKE-OFF OF ALL MATERIALS REQUIRED TO COMPLETE THE PROJECT AS PER CWS CO. STANDARD SPECIFICATIONS.
- ALL SITE WORK SHALL BE COMPLETED IN ACCORDANCE WITH REQUIREMENTS OUTLINED IN THE GEOTECHNICAL REPORT.
- CONTRACTOR SHALL PREPARE SITE BY STRIPPING AND REMOVING ALL LOOSE MATERIAL, VEGETATION, CONCRETE, GRAVEL FROM ACCESS ROAD, DEBRIS, DELETERIOUS MATERIAL AND TREES DESIGNATED FOR REMOVAL FROM THE AREAS TO BE OCCUPIED BY THE NEW TANK.
- SPOILS SHALL NOT REMAIN ON-SITE, DISPOSAL OF ALL PROJECT GENERATED SPOILS SHALL BE AT A FACILITY LICENSED AND CLASSIFIED TO ACCEPT THE MATERIALS. CONTRACTOR TO PROVIDE OWNER WITH FORMAL RECEIPT FROM THE ACCEPTING FACILITY.
- TEMPORARY CUT SLOPES STEEPER THAN 1 (H): 1 (V) MAY NOT STAND DUE TO THE LOCALIZED CONSISTENCY OF THE NATURAL SOILS. IN AREAS TO BE FILLED, THE EXPOSED SURFACE SHOULD BE SCARIFIED TO AT LEAST AN 8-INCH DEPTH, MOISTURE CONDITIONED TO AT LEAST OPTIMUM MOISTURE CONTENT AND COMPACTED TO AT LEAST 90 PERCENT RELATIVE COMPACTION BASED ON ASTM D-1557-07.
- THE TANK PAD AREA SHALL BE OVER EXCAVATED A MINIMUM RADIAL DISTANCE OF 5 FEET BEYOND TO OUTSIDE EDGE OF PLANNED RINGWALL FOUNDATION. IN ADDITION, THE CONCRETE RINGWALL SHALL BE CONSTRUCTED ON A MINIMUM OF 1-FOOT OF ENGINEERED FILL. IN AREAS TO BE FILLED, THE EXPOSED SURFACE SHALL BE SCARIFIED TO AT LEAST AN 8-INCH DEPTH, MOISTURE CONDITIONED TO AT LEAST OPTIMUM MOISTURE CONTENT AND COMPACTED TO AT LEAST 95% RELATIVE COMPACTION BASED ON ASTM D-1557-07.
- EXCAVATED ONSITE MATERIAL MAY BE REUSED AS COMPACTED FILL PROVIDED IT MEETS THE REQUIREMENTS FOR IMPORTED FILL. STORAGE OF SUITABLE COMPACTED FILL MAY BE ALLOWED ONSITE, QUANTITY AND LOCATION SHALL BE DETERMINED BY AND COORDINATED WITH DISTRICT STAFF.
- IMPORTED FILL SHALL BE FREE OF ORGANIC MATTER, MATERIAL LARGER THAN 4-INCHES IN DIAMETER AND SHALL HAVE A PLASTICITY INDEX (P.I.) OF LESS THAN 16.
- COMPACTED FILL SHALL BE PLACED IN HORIZONTAL LIFTS NOT EXCEEDING 8-INCHES IN LOOSE THICKNESS, MOISTURE CONDITIONED TO AT LEAST OPTIMUM MOISTURE CONTENT AND COMPACTED TO AT LEAST 95-PERCENT RELATIVE COMPACTION BENEATH STRUCTURES, SLABS AND WITHIN 18-INCHES OF THE AGGREGATE BASE ROCK FOR PAVEMENTS, AND 90-PERCENT RELATIVE COMPACTION ELSEWHERE.
- PAVEMENT SECTIONS SHALL CONSIST OF A MINIMUM OF 3-INCHES ASPHALT CONCRETE (AC) OVER A MINIMUM OF 9-INCHES OF AGGREGATE BASE ROCK (AB). AC SHALL BE PLACED AND COMPACTED IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION 39 OF THE CALTRANS STANDARD SPECIFICATIONS; AB SHALL CONFORM TO THE PROVISION OF SECTION 26 (CALTRANS) FOR 3/4-INCH MAXIMUM CLASS 2 AB AND SHALL BE COMPACTED TO AT LEAST 95-PERCENT RELATIVE COMPACTION BASED ON ASTM D-1557-07 RATHER THAN CALTRANS METHOD 216.
- AFTER GENERAL COMPACTION AND COMPACTION OF UTILITY TRENCH BACKFILLS, THE PROPOSED PAVEMENT AREAS AND TANK ACCESS SUBGRADE SURFACE SHALL BE CHECKED FOR YIELDING AREAS BY PROOF-ROLLING WITH A LOADED WATER TRUCK OR EQUIVALENT. ANY YIELDING AREAS SHALL BE EXCAVATED AND REPLACED WITH COMPACTED FILL. THE UPPER 12-INCHES SHALL BE MOISTURE CONDITIONED TO AT LEAST OPTIMUM MOISTURE CONTENT AND COMPACTED TO AT LEAST 95-PERCENT RELATIVE COMPACTION.
- MAINTENANCE AREA SHALL BE GRADED TO 4-INCH BELOW PROPOSED FINAL ELEVATIONS AND THEN SCARIFIED, WATERED AND COMPACTED TO 85% RELATIVE COMPACTION PER ASTM D1557, PLACE 4-INCH OF CLASS 2 A.B. COMPACTED TO 90% RELATIVE COMPACTION. THE ENTIRE SITE, EXCEPT STEEP SLOPES AND EQUIPMENT AREAS, IS TO BE CONSIDERED MAINTENANCE AREA.
- CONTRACTOR SHALL PROVIDE A MINIMUM OF 48 HOURS NOTICE TO CWS ENGINEER PRIOR TO FILLING WITH COMPACTED FILL OR POURING OF CONCRETE FOUNDATIONS AT ALL EXCAVATION, COMPACTION AND GRADING ACTIVITIES TO ALLOW FOR COORDINATION OF INSPECTION BY A GEOTECHNICAL ENGINEER OR THEIR REPRESENTATIVE.

**GENERAL NOTES:**

- THE OWNER IS REQUIRED TO OBTAIN THE PLANNING PERMIT AND BUILDING PERMIT FROM THE CITY OF SAN MATEO. THE CONTRACTOR IS RESPONSIBLE TO OBTAIN ALL OTHER PERMITS FROM OTHER AGENCIES NECESSARY FOR THE CONSTRUCTION OF THE PROJECT.
- CONTRACTOR SHALL BE RESPONSIBLE FOR ADHERING TO AND COMPLYING WITH LOCAL GOVERNING AGENCY PERMIT RESTRICTIONS, WHICH MAY AFFECT ALLOWABLE WORKING HOURS AND NOISE LEVELS. WORKING HOURS SHALL BE RESTRICTED TO THE HOURS OF 8:00 A.M. TO 5:00 P.M., MONDAY THROUGH FRIDAY.
- SUBJECT PROPERTY IS OWNED BY: CALIFORNIA WATER SERVICE CO. (CWS CO.) 1720 N. FIRST ST. SAN JOSE, CA. 95112  
 THIS PLAN HAS BEEN PREPARED BY CALIFORNIA WATER SERVICE CO. ENGINEERING DEPARTMENT, JULIE HUYNH, P.E. (PROJECT COORDINATOR/EFFECTIVE CONTROL OF WORK) (408) 367-8394 AN EMPLOYEE THEREIN.
- FACILITY IS A WATER UTILITY SUPPLY AND STORAGE INSTALLATION, NOT A PLACE OF EMPLOYMENT, PUBLIC ACCOMMODATION OR COMMERCIAL FACILITY. THEREFORE, THIS PROJECT IS NOT SUBJECT TO THE A.D.A. PROVISIONS OF TITLE 24 IN THE CALIFORNIA BUILDING CODE.
- SANITARY SEWER CONNECTION WILL NOT BE MADE. NO SEPTIC SYSTEM WILL BE INSTALLED. NO SEWAGE, TRASH OR GARBAGE WILL BE GENERATED ON THIS SITE.
- CONTRACTOR SHALL BECOME FAMILIAR WITH PROJECT SURROUNDINGS, WORKING CONDITIONS, AND SITE LIMITATIONS AND INCLUDE ALLOWANCES IN THEIR BID TO COVER ANY PROJECT CONSTRAINTS. CONTRACTOR SHOULD BE AWARE THAT GROUND WATER MAY BE ENCOUNTERED DURING EXCAVATION ACTIVITIES THAT MAY REQUIRE DEWATERING.
- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH 2019 C.B.C., 2019 C.F.C., AND MOST CURRENT NFPA AND NEC ANWA 1101 & C600.
- CONTRACTOR SHALL COMPLY WITH ALL PERMIT REQUIREMENTS AND NOTIFY THE GOVERNING AGENCY AND OWNER FOR REQUIRED INSPECTIONS.
- ALL DESIGN AND CONSTRUCTION SHALL CONFORM TO THE CITY OF SAN MATEO'S DESIGN AND CONSTRUCTION STANDARDS, AS APPLICABLE.
- IF THERE IS ANY CONFLICT, CONTRACTOR MUST BRING TO OWNER'S ATTENTION AND OBTAIN OWNER'S APPROVAL FOR CHANGE.
- CONTRACTOR SHALL APPLY COUNTY OF SAN MATEO COUNTYWIDE CONSTRUCTION BEST MANAGEMENT PRACTICES (BMPs) AND CALTRANS BEST MANAGEMENT PRACTICES TO PREVENT WATER AND SEDIMENT FROM ENTERING NAVIGABLE WATERWAYS. THE CONTRACTOR IS RESPONSIBLE FOR IDENTIFYING AND INSTALLING THE APPLICABLE AND APPROPRIATE BMP'S IDENTIFIED IN THE CALTRANS CONSTRUCTION BEST MANAGEMENT PRACTICES (BMP) MANUAL (MAY 2017) SOME OF THE REQUIRED PRACTICES MAY OR MAY NOT BE SHOWN ON THIS SITE PLAN.
- CONSTRUCTION OPERATIONS DUST SHALL BE CONTROLLED. DUST CONTROL MUST BE MAINTAINED TO THE CITY OF LIVERMORE'S SATISFACTION.
- WASTEWATER GENERATED DURING CONSTRUCTION SHALL NOT BE DISCHARGED TO THE STORM DRAINAGE SYSTEM. THIS INCLUDES WASTE FROM PAINTING, SAW CUTTING, CONCRETE WORK ETC. THE CONTRACTOR SHALL MAKE ARRANGEMENTS TO ELIMINATE DISCHARGES TO THE STORM DRAINAGE SYSTEM. IF NECESSARY PROVIDE AN AREA FOR ON-SITE WASHING ACTIVITIES DURING CONSTRUCTION. MATERIALS THAT COULD CONTAMINATE STORM RUNOFF SHALL BE STORED IN AREAS WHICH ARE DESIGNATED TO PREVENT EXPOSURE TO RAINFALL AND TO NOT ALLOW STORM WATER TO RUN ONTO THE AREA.
- PAVEMENT CLEANING-FLUSHING OF STREETS/PARKING LOTS TO REMOVE DIRT AND CONSTRUCTION DEBRIS IS PROHIBITED UNLESS SEDIMENT CONTROLS ARE USED. PREFERABLY, AREAS REQUIRED CLEANING SHOULD BE SWEEPED.
- CONTRACTOR MUST KEEP THE SITE CLEAN AT ALL TIME, AND MINIMIZE NEGATIVE IMPACT TO THE SURROUNDING AREAS AND NEIGHBORS. MATERIAL, TOOLS AND EQUIPMENT MUST BE KEPT SAFE AND OUT OF PUBLIC DANGER AT ALL TIME DURING CONSTRUCTION. CONTRACTOR TO PROVIDE ADEQUATE DUST CONTROL MEASURES DURING CONSTRUCTION.
- IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE EXACT HORIZONTAL AND VERTICAL LOCATION OF ALL EXISTING UTILITIES WITHOUT ADDITIONAL COST TO OWNER. CONTRACTOR SHALL CONTACT "UNDERGROUND SERVICES ALERT" 48 HOURS PRIOR TO ANY EXCAVATION.
- THE LIST OF MATERIALS FOR THIS PROJECT IS FOR REFERENCE PURPOSES ONLY, AND IS NOT INTENDED AS A FULL TAKE-OFF OF ALL MATERIALS REQUIRED TO COMPLETE THE PROJECT AS PER CWS STANDARD SPECIFICATIONS.
- CONTRACTOR MUST SHARE THE SITE AND SITE ACCESS WITH OWNER AND OTHER CONTRACTORS.
- CONTRACTOR SHALL WORK CONTINUOUSLY WITHOUT ANY UNDUE DELAY.
- CONTRACTOR MAY NEED TO REMOVE SMALL TREES AND LIMBS TO ALLOW ACCESS FOR SOME EQUIPMENT. CARE SHALL BE TAKEN TO MINIMIZE ALL CUTTING ACTIVITY. ALL CUTS SHALL BE COORDINATED WITH THE OWNER'S CONSTRUCTION SUPERINTENDENT.
- ELEVATION DATA IS BASED ON ARBITRARY DATUM AND IS NOT BASED ON AN ESTABLISHED CITY OR STATE ELEVATION DATUM. THIS IS NOT A MAP OF A BOUNDARY SURVEY. NO PROPERTY CORNERS HAVE BEEN SET AS PART OF THIS WORK. SURVEY MONUMENTS FOUND IN THE COURSE OF THIS MAPPING ARE SET BY OTHERS, AND HAVE BEEN USED ONLY AS A REFERENCE FOR THE PURPOSE OF TOPOGRAPHIC MAPPING, WITHOUT OUR VERIFICATION OF THEIR AGREEMENT WITH APPLICABLE LEGAL DESCRIPTIONS AND SENIORITY OF DEEDS. RELATION OF TOPOGRAPHIC FEATURES (I.E., FENCES, WALLS, TREES, POWER POLES, ETC.) TO PROPERTY LINES AS SHOWN ON THIS MAP IS SUBJECT TO THE ADJUSTMENTS THAT A BOUNDARY SURVEY MAY REQUIRE.

**PIPING DEMOLITION / ABANDONMENT**

- UNDERGROUND PIPING WILL BE ABANDONED IN PLACE AT LEAST 24-INCHES BELOW GRADE.  
 1.1 PIPE THAT ENDS SHALL BE PLUGGED WITH PLUGGED FITTINGS ARE ALL APPROPRIATELY SIZED.
- ANY VAULT OR VALVE CAN WILL BE BACK-FILLED WITH IMPORT MATERIAL TO GRADE AND COMPACTED TO CITY STANDARDS.
- ANY WORK INVOLVING ASBESTOS CEMENT PIPE SHALL BE COMPLETED IN ACCORDANCE WITH ALL LATEST APPLICABLE FEDERAL, STATE AND LOCAL REQUIREMENTS AND REGULATION AS WELL AS APPLICABLE ANWA STANDARD.
- FERROUS PIPING WILL EITHER BE ABANDONED IN PLACE OR RECYCLED. NON-FERROUS PIPING WILL EITHER BE ABANDONED IN PLACE OR DISPOSED AT A LANDFILL.



**GRADING EARTHWORK QUANTITIES:**

CUT: 100 CY  
 FILL: 70 CY  
 SITE IMPORT: 70 CY

NOTE:  
 EARTHWORK QUANTITIES ARE APPROXIMATE FOR PERMITTING PURPOSES ONLY. NO SHRINK OR SWELL FACTORS HAVE BEEN APPLIED TO THESE VALUES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GRADING REQUIRED TO OBTAIN FINISH GRADES AS SHOWN.

**GEOTECHNICAL INVESTIGATION:**

ALL GRADING ACTIVITIES AND SITE PREPARATION SHALL COMPLY WITH THE GEOTECHNICAL INVESTIGATION PREPARED BY MICHELLOCCI & ASSOCIATES, INC., JOB NO. 01-3186 DATE DECEMBER 16, 2002, AND UPDATED SEISMIC CRITERIA LETTER DATED 9/7/2021



**DRAINAGE DEPRESSION SWALE DETAIL**  
 N.T.S.

NOTE:  
 DRAINAGE SWALE TO BE MINIMUM 1FT FROM EDGE OF FOUNDATION



DEPARTMENT

REVISIONS:  
 01-09/2021 PER COUNTY REVIEW COMMENTS  
 02-03-27-2021 CHANGE WATER TYPING  
 02-06/24/2022 ADD NEW TRANSFORMER & M.C. PADS  
 04-ADD SD LINE & BID-RETENTION 2/17/23

DATE: \_\_\_\_\_  
 DATE: \_\_\_\_\_  
 DATE: \_\_\_\_\_  
 DATE: \_\_\_\_\_

PLAT SHEET NO.: **SM-31-22**

SCALE: **AS SHOWN**

DRAWN BY: **D. HEARN**

DESIGNED BY: **J. HUYNH**

TECH REVIEW: \_\_\_\_\_ DATE: \_\_\_\_\_

CHECKED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

APPROVED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

DATE: 5/31/2023

DATE: 6/1/2023



TITLE: **MPS - SAN MATEO STA 031 STANDARD BOLTED STEEL STORAGE TANK GRADING PLAN**

DISTRICT: \_\_\_\_\_

PROJECT ID: **116-MPS**


DATE: \_\_\_\_\_

DATE: **2/3/2021**

DRAWING NO.: **00118772**

DRAWING NO.: **MPS-5641 R4**

SHT 1 OF 1




**EROSION CONTROL PLAN**  
SCALE: 1" = 15'

**LEGEND**

	LAYDOWN / STAGING
	WADDLES/FIBER ROLLS
	INLET PROTECTION
	EXISTING FENCE
	TEMPORARY CONSTRUCTION FENCING

**STATION ADDRESS**  
OFF OF BEL AIRE ROAD, SAN MATEO, CA  
94551 ALAMEDA COUNTY  
APN# 095-034802000



**VICINITY MAP**  
Not to Scale

## Personal Protective Equipment

Required for Jobsite Entry

Additional PPE may be required depending on the job tasks being performed.

**HARD HAT**

**EYE PROTECTION**

**EAR PROTECTION**

**SLEEVES**

**HIGH VISIBILITY VEST**

**LONG PANTS**

**GLOVES**

**WORK BOOTS**

Quality. Service. Value.®

**EROSION CONTROL NOTES:**

- CONTRACTOR SHALL APPLY CALTRAN BEST MANAGEMENT PRACTICES TO PREVENT WATER AND SEDIMENT FROM ENTERING NAVIGABLE WATERWAYS. THE CONTRACTOR IS RESPONSIBLE FOR IDENTIFYING AND INSTALLING THE APPLICABLE AND APPROPRIATE BMP'S IDENTIFIED IN THE CASQA SMBMP HANDBOOK (JANUARY 2003) AVAILABLE ONLINE AT [HTTP://WWW.CABMPHANDBOOKS.COM](http://www.cabmphandbooks.com) SOME OF THE REQUIRED PRACTICES MAY OR MAY NOT BE SHOWN ON THIS SITE PLAN.
- FOLLOWING BMP'S FROM CASQA SMBMP HANDBOOK (JANUARY 2003) WILL BE IMPLEMENTED:
  - SE-5 TEMPORARY STRAW WATTLES
  - SE-10 STORM DRAIN INLET PROTECTION
  - SP STOCKPILE MANAGEMENT
  - WM-8 CONCRETE WASTE MANAGEMENT
  - TC-1 TEMPORARY CONSTRUCTION ENTRANCE AND EXIT
- CONSTRUCTION OPERATIONS - DUST SHALL BE CONTROLLED. WASTEWATER GENERATED DURING CONSTRUCTION SHALL NOT BE DISCHARGED TO THE STORM DRAIN SYSTEM. THIS INCLUDES WATER FROM PAINTING, SAW CUTTING, CONCRETE WORK ETC. THE CONTRACTOR SHALL MAKE ARRANGEMENTS TO ELIMINATE DISCHARGES TO THE STORM DRAIN SYSTEM AND THE EXISTING SUMP. IF NECESSARY PROVIDE AN AREA FOR ON-SITE WASHING ACTIVITIES DURING CONSTRUCTIONS. MATERIALS THAT COULD CONTAMINATE STORM RUNOFF SHALL BE STORED IN AREA WHICH IS DESIGNATED TO PREVENT EXPOSURE TO RAINFALL AND TO NOT ALLOW STORM WATER TO RUN ONTO THE AREA.
- AREAS REQUIRED CLEANING SHOULD BE SWEEP. THIS INCLUDES RESIDUES FROM SAW CUTTING, GRINDING AND PAVING.
- CONTRACTOR MUST KEEP THE SITE CLEAN AT ALL TIME, AND MINIMIZE NEGATIVE IMPACT TO THE SURROUNDING AREAS AND NEIGHBORS. MATERIALS, TOOLS AND EQUIPMENT MUST BE KEPT SAFE AND OUT OF PUBLIC DANGER AT ALL TIME DURING CONSTRUCTION.
- EROSION CONTROL MEASURES ARE TEMPORARY AND TO BE USED ONLY DURING CONSTRUCTION.
- DUE TO LIMITED LAYDOWN AREA, CONTRACTOR SHALL PLACE CONCRETE WASHOUT, PORTABLE TOILETS, REFUSE PILES, DEBRIS BOXES AND STOCKPILES ONSITE AS NECESSARY. ALL POTENTIAL CONTAMINATES SHALL BE PROTECTED FROM RUNOFF AND LOCATED AWAY FROM SURFACE WATER LOCATIONS AND STORM DRAIN INLETS.
- PROVIDE INLET PROTECTION USING GRAVEL BAG WITH FILTER FABRIC IN PLACE FOR SECOND EXISTING CATCH BASIN LOCATED SOUTH EAST OF CATCH BASIN SHOWN ON PLAN VIEW.



ENGINEERING DEPARTMENT

REVISIONS:  
R1-(9/29/21) PER COUNTY REVIEW COMMENTS  
R2-(9/24/21) PER COUNTY REVIEW COMMENTS  
R3-(8/23/22) UPDATE PER STAMP

DISTRIBUTION MAP  DATE: \_\_\_\_\_  
 PLAN SHEET   
 SYSTEM SCHEMATIC   
 STATION SCHEMATIC

PLAT SHEET NO.: **SM-31-22**

SCALE: **AS SHOWN**

DRAWN BY: **D. HEARN**

DESIGNED BY: **J. HUYNH**

TECH REVIEW: \_\_\_\_\_ DATE: \_\_\_\_\_

CHECKED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

APPROVED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

9/7/2022



MPS - SAN MATEO STA 031  
 58,929 GALLON BOLTED STEEL TANK  
 EROSION CONTROL

TITLE: \_\_\_\_\_  
 DISTRICT: **116-MPS**  
 SAN MATEO  
 DATE: **1/8/2021**  
 PROJECT ID: **00118772**  
 DRAWING NO.: **MPS-5642 R3**  
 SHEET 1 OF 3




Know what's below.  
Call before you dig.

# Construction Best Management Practices (BMPs)

Construction projects are required to implement the stormwater best management practices (BMP) on this page, as they apply to your project, all year long.

## Materials & Waste Management



### Non-Hazardous Materials

- Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or if not actively being used within 14 days.
- Use (but don't overuse) reclaimed water for dust control.

### Hazardous Materials

- Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, county, state and federal regulations.
- Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecast.
- Follow manufacturer's application instructions for hazardous materials and be careful not to use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- Arrange for appropriate disposal of all hazardous wastes.

### Waste Management

- Cover waste disposal containers securely with tarps at the end of every work day and during wet weather.
- Check waste disposal containers frequently for leaks and to make sure they are not overfilled. Never hose down a dumpster on the construction site.
- Clean or replace portable toilets, and inspect them frequently for leaks and spills.
- Dispose of all wastes and debris properly. Recycle materials and wastes that can be recycled (such as asphalt, concrete, aggregate base materials, wood, gyp board, pipe, etc.)
- Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste.

### Construction Entrances and Perimeter

- Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.

## Equipment Management & Spill Control




### Maintenance and Parking

- Designate an area, fitted with appropriate BMPs, for vehicle and equipment parking and storage.
- Perform major maintenance, repair jobs, and vehicle and equipment washing off site.
- If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan or drop cloths big enough to collect fluids. Recycle or dispose of fluids as hazardous waste.
- If vehicle or equipment cleaning must be done onsite, clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or surface waters.
- Do not clean vehicle or equipment onsite using soaps, solvents, degreasers, or steam cleaning equipment.

### Spill Prevention and Control

- Keep spill cleanup materials (e.g., rags, absorbents and cat litter) available at the construction site at all times.
- Inspect vehicles and equipment frequently for and repair leaks promptly. Use drip pans to catch leaks until repairs are made.
- Clean up spills or leaks immediately and dispose of cleanup materials properly.
- Do not hose down surfaces where fluids have spilled. Use dry cleanup methods (absorbent materials, cat litter, and/or rags).
- Sweep up spilled dry materials immediately. Do not try to wash them away with water, or bury them.
- Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- Report significant spills immediately. You are required by law to report all significant releases of hazardous materials, including oil. To report a spill: 1) Dial 911 or your local emergency response number, 2) Call the Governor's Office of Emergency Services Warning Center, (800) 852-7550 (24 hours).

## Earthmoving



- Schedule grading and excavation work during dry weather.
- Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- Remove existing vegetation only when absolutely necessary, and seed or plant vegetation for erosion control on slopes or where construction is not immediately planned.
- Prevent sediment from migrating offsite and protect storm drain inlets, gutters, ditches, and drainage courses by installing and maintaining appropriate BMPs, such as fiber rolls, silt fences, sediment basins, gravel bags, berms, etc.
- Keep excavated soil on site and transfer it to dump trucks on site, not in the streets.

### Contaminated Soils

- If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:
  - Unusual soil conditions, discoloration, or odor.
  - Abandoned underground tanks.
  - Abandoned wells
  - Buried barrels, debris, or trash.

## Paving/Asphalt Work



- Avoid paving and seal coating in wet weather or when rain is forecast, to prevent materials that have not cured from contacting stormwater runoff.
- Cover storm drain inlets and manholes when applying seal coat, tack coat, slurry seal, fog seal, etc.
- Collect and recycle or appropriately dispose of excess abrasive gravel or sand. Do NOT sweep or wash it into gutters.
- Do not use water to wash down fresh asphalt concrete pavement.

### Sawcutting & Asphalt/Concrete Removal

- Protect nearby storm drain inlets when saw cutting. Use filter fabric, catch basin inlet filters, or gravel bags to keep slurry out of the storm drain system.
- Shovel, absorb, or vacuum saw-cut slurry and dispose of all waste as soon as you are finished in one location or at the end of each work day (whichever is sooner!).
- If sawcut slurry enters a catch basin, clean it up immediately.

## Concrete, Grout & Mortar Application




- Store concrete, grout, and mortar away from storm drains or waterways, and on pallets under cover to protect them from rain, runoff, and wind.
- Wash out concrete equipment/trucks offsite or in a designated washout area, where the water will flow into a temporary waste pit, and in a manner that will prevent leaching into the underlying soil or onto surrounding areas. Let concrete harden and dispose of as garbage.
- When washing exposed aggregate, prevent washwater from entering storm drains. Block any inlets and vacuum gutters, hose washwater onto dirt areas, or drain onto a bermed surface to be pumped and disposed of properly.

## Landscaping



- Protect stockpiled landscaping materials from wind and rain by storing them under tarps all year-round.
- Stack bagged material on pallets and under cover.
- Discontinue application of any erodible landscape material within 2 days before a forecast rain event or during wet weather.


## Painting & Paint Removal



### Painting Cleanup and Removal

- Never clean brushes or rinse paint containers into a street, gutter, storm drain, or stream.
- For water-based paints, paint out brushes to the extent possible, and rinse into a drain that goes to the sanitary sewer. Never pour paint down a storm drain.
- For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of excess liquids as hazardous waste.
- Paint chips and dust from non-hazardous dry stripping and sand blasting may be swept up or collected in plastic drop cloths and disposed of as trash.
- Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury, or tributyltin must be disposed of as hazardous waste. Lead based paint removal requires a state-certified contractor.

## Dewatering




- Discharges of groundwater or captured runoff from dewatering operations must be properly managed and disposed. When possible send dewatering discharge to landscaped area or sanitary sewer. If discharging to the sanitary sewer call your local wastewater treatment plant.
- Divert run-on water from offsite away from all disturbed areas.
- When dewatering, notify and obtain approval from the local municipality before discharging water to a street gutter or storm drain. Filtration or diversion through a basin, tank, or sediment trap may be required.
- In areas of known or suspected contamination, call your local agency to determine whether the ground water must be tested. Pumped groundwater may need to be collected and hauled off-site for treatment and proper disposal.


**Storm drain polluters may be liable for fines of up to \$10,000 per day!**




**Stockpile Management (SP)**




**Fiber Rolls SE-5**




**Storm Drain Inlet Protection SE-10**



**Concrete Waste Management WM-8**



**Stabilized Construction Entrance/Exit TC-1**



ENGINEERING



DEPARTMENT

REVISIONS:  
 R1-(9/2/11) PER COUNTY REVIEW COMMENTS  
 R2-(9/24/21) PER COUNTY REVIEW COMMENTS  
 R3-(8/23/22) UPDATE PER STAMP

DISTRICT: 116-MPS

DATE: 1/8/2021

PROJECT ID: 00118772

DRAWING NO.: MPS-5642 R3

SHEET 3 OF 3

AS SHOWN

DRAWN BY: D. HEARN

DESIGNED BY: J. HUYNH

TECH REVIEW: DATE:

CHECKED BY: DATE: 8/26/2022

APPROVED BY: DATE: 9/17/2022




TITLE:  
 DISTRICT:  
 116-MPS  
 SAN MATEO  
 DATE:  
 1/8/2021  
 PROJECT ID:  
 00118772  
 DRAWING NO.:  
 MPS-5642 R3  
 SHEET 3 OF 3

USER: D:\Capitol\_Projects\116\_Mid\_Penninsula\00118772\_Sta\_31\_ASCENSION HEIGHTS BAYWOOD TANK\2 - DESIGN\500 - Drawings\working drawings\MPS-5642\_erosion control\_8-24-2022.dwg

# MPS - SAN MATEO

## STATION 031 - ASCENSION DR & BEL AIRE RD

### INSTALL TANK AND BOOSTER PUMP




**PROPOSED SITE PLAN**  
SCALE: 1" = 15'

#### STATION ADDRESS

OFF OF BEL AIRE ROAD, SAN MATEO, CA  
94551 ALAMEDA COUNTY  
APN# 098-034802000

#### LEGEND:

- TEE
- ELBOW, 45°
- ELBOW, 90°
- BLOWOFF (PROPOSED)
- BLOWOFF (EXISTING)
- GATE VALVE (PROPOSED)
- GATE VALVE (EXISTING)
- REDUCER (PROPOSED)
- REDUCER (EXISTING)
- SOLID PLUG
- PROPOSED WATER MAIN
- EXISTING WATER MAIN
- WALL
- SANITARY SEWER
- STORM DRAIN
- FIRE HYDRANT (PROPOSED)
- FIRE HYDRANT (EXISTING)
- BUTTERFLY VALVE
- CHECK VALVE
- FLEX CPLG.
- ALTITUDE VALVE
- FLOOR DRAIN PLAN



**VICINITY MAP**  
Not to Scale

#### BILL OF MATERIALS

QTY	DESCRIPTION
±15 LF	8" DI PIPE w/RESTRAINT GASKETS
±130 LF	6" DI PIPE w/RESTRAINT GASKETS
1	8" GATE VALVE, PO w/RESTRAINT GASKETS
2	8" ELL, 90° FLG, 150#
1	8" ELL, 90° PO X FLG 150# w/RESTRAINT GASKETS
1	8" ELL, 90° PO w/RESTRAINT GASKETS
1	8" CL&C FOE-POE 150# (6'-0" LONG), CUT TO FIT
1	8" DI FOE-POE, 150# (6'-0" LONG), CUT TO FIT
1	8" BUTTERFLY VALVE FLG, 150#
2	8" SOW, FLG 150#
3	6" BUTTERFLY VALVE FLG, 150#
6	6" ELL, 90° FLG, 150#
5	6" ELL, 90° PO X FLG 150# w/RESTRAINT GASKETS
2	6" ELL, 90° PO w/RESTRAINT GASKETS
1	6" STEEL CML PIPE, FBE (6'-0" LONG), 150#
7	6" GATE VALVE, PO w/RESTRAINT GASKETS
2	6" CHECK VALVE, FLG, 150#
5	6" CL&C FOE-POE 150# (6'-0" LONG), CUT TO FIT
5	6" SOW, FLG 150#
4	6" STEEL CML PIPE, FOE-POE (1'-6" LONG), 150#
2	SET OF THE ROPS AND CLIPS
2	6" STEEL CML PIPE, FBE (1'-6" LONG), 150#
4	6" STEEL CML PIPE, FBE (1'-0" LONG), 150#
1	6" DI FOE-POE, 150# (6'-0" LONG), CUT TO FIT
3	6" TEE PO w/RESTRAINT GASKETS
1	6" CROSS PO w/RESTRAINT GASKETS
2	ACOUSTICAL SHELTERS (OWNER FURNISH)
2	2" WELDED THREAD-O-LET W/2" BALL VALVE AND PLUG
1	1/2" SENSING LINE TAP, CORP COCK AND ASSEMBLIES
1	8" FLEX-TEND EXPANSION JOINT (OWNER FURNISH)
1	6" FLEX-TEND EXPANSION JOINT (OWNER FURNISH)
1	6" MAGMETER (OWNER FURNISH)
1	8" CLA-VAL (OWNER FURNISH)
1	48" X 72" ARMORCAST VAULT
1	48" X 60" ARMORCAST VAULT
2	6" RESTRAINED FLANGE ADAPTER OR MEGA FLANGE
2	8" RESTRAINED FLANGE ADAPTER OR MEGA FLANGE
2	3"X6" WEDGEMOUNT AIR LOC HD
9	VALVE CASING COVER AND ASSEMBLY

#### FIRE HYDRANT CONNECTION

QTY	DESCRIPTION
2	INSTALL 6" CLOW 960 FIRE HYDRANT AND 6" GATE VALVE (SEE HYDRANT DETAILS ON DWG-CW-DWG)

#### MISCELLANEOUS

AS REQ'D	DESCRIPTION
AS REQ'D	THRUST BLOCKS REQUIRED ON ALL FITTINGS
AS REQ'D	TRACER WIRE #12 AWG STRANDED COPPER, THWN INSULATED
AS REQ'D	LINEGUARD TAPE
AS REQ'D	POLYWRAP TUBING
AS REQ'D	PVC TAPE
AS REQ'D	METAL GUARD #301
AS REQ'D	RES-BIT WRAP (100' ROLL)
AS REQ'D	2" BLOW OFF ASSEMBLIES FOR TESTING, DISINFECTION, AND FLUSHING
MISC.	MATERIALS INCLUDING CAPS FOR TESTING, DISINFECTION, AND FLUSHING

REFERENCE LIST ONLY - CONTRACTOR TO VERIFY AND OBTAIN ALL MATERIALS REQUIRED TO COMPLETE THE PROJECT.

#### STORM DRAIN

QTY	DESCRIPTION
95 LF ±	6" PVC SDR-26
110a	8" PVC SDR-26
1	2'X2' CONCRETE CATCH BASIN
4	12" Ø D PVC DRAIN BASIN w/ ROUND DUCTILE IRON GRATE
MISC.	COUPLINGS AND FITTINGS FOR TIE-IN

#### GENERAL NOTES:

- CONTRACTOR SHALL BECOME FAMILIAR WITH PROJECT SURROUNDINGS, WORKING CONDITIONS, AND SITE LIMITATIONS AND WILL INCLUDE ALLOWANCES IN THEIR BID TO COVER ANY PROJECT CONSTRAINTS.
- CONTRACTOR SHALL BE RESPONSIBLE FOR ADHERING TO AND COMPLYING WITH LOCAL GOVERNING AGENCY PERMIT RESTRICTIONS, WHICH MAY AFFECT ALLOWABLE WORKING HOURS AND NOISE LEVELS.
- CONTRACTOR SHALL PROVIDE TRAFFIC CONTROL AS REQUIRED BY APPLICABLE LOCAL GOVERNING AGENCY. CONTRACTOR SHALL SUBMIT A TRAFFIC CONTROL PLAN PER CALTRANS STANDARDS TO OWNER PRIOR TO CONSTRUCTION, IF REQUIRED. WORK REQUIRING TRAFFIC CONTROL SHALL BE CONDUCTED BETWEEN THE HOURS OF 9:00 A.M. AND 3:30 P.M., MONDAY THRU FRIDAY, OR AS OTHERWISE AUTHORIZED BY LOCAL GOVERNING AGENCY REPRESENTATIVE.
- CONTRACTOR SHALL APPLY CALTRANS BEST MANAGEMENT PRACTICES TO PREVENT WATER AND SEDIMENT FROM ENTERING NAVIGABLE WATERWAYS. THE CONTRACTOR IS RESPONSIBLE FOR IDENTIFYING AND INSTALLING THE APPLICABLE AND APPROPRIATE BMP'S IDENTIFIED IN THE CALTRANS CONSTRUCTION SITE BMP MANUAL (MAY 2017) AVAILABLE ONLINE AT [HTTP://WWW.DOT.CA.GOV/HQ/CONSTRUC/STORMWATER/MANUALS.HTM](http://www.dot.ca.gov/hq/CONSTRUC/STORMWATER/MANUALS.HTM). SOME OF THE REQUIRED PRACTICES MAY OR MAY NOT BE SHOWN ON THIS SITE PLAN.
- CONTRACTOR TO CONTACT "UNDERGROUND SERVICE ALERT" 48 HOURS PRIOR TO ANY EXCAVATION.
- IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE EXACT LOCATION AND DEPTH OF ALL EXISTING UTILITIES.
- TRENCH TO BE SHORED IN ACCORDANCE WITH CALIFORNIA OSHA REGULATIONS.
- PLACE A CONTINUOUS WIRE AND STRIP OF DETECTOR TAPE OVER ALL PIPES AND EXTEND UP INTO ALL VALVE BOXES. TRACER WIRE IS REQUIRED ON ALL PIPE. (SEE LATEST REVISION OF DRAWING CW-850).
- SEE LATEST REVISION OF DRAWING CW-435 FOR TYPICAL THRUST BLOCK INSTALLATION. IN ADDITION TO RESTRAINT GASKETS, ALL FITTINGS TO HAVE THRUST BLOCKS.
- FACILITIES SEPARATION:
  - WATER MAIN SHALL BE INSTALLED AT LEAST 10 FEET HORIZONTALLY FROM AND ONE FOOT VERTICALLY ABOVE ANY PARALLEL PIPELINE CONVEYING SEWAGE (UNTREATED, PRIMARY, OR SECONDARY), DISINFECTED SECONDARY RECYCLED WATER, OR HAZARDOUS FLUIDS.
  - WATER MAIN SHALL BE INSTALLED AT LEAST 4 FEET HORIZONTALLY FROM AND ONE FOOT VERTICALLY ABOVE ANY PIPELINE CONVEYING TERTIARY RECYCLED WATER OR STORM DRAINAGE.
  - AT CROSSINGS, WATER MAIN SHALL BE CONSTRUCTED NO LESS THAN 45-DEGREES TO AND AT LEAST ONE FOOT VERTICALLY ABOVE ANY PIPELINES INDICATED IN A AND B ABOVE.
  - NO CONNECTION JOINTS SHALL BE MADE IN THE WATER MAIN WITHIN EIGHT (8) HORIZONTAL FEET OF CROSSING ANY PIPELINES INDICATED IN A AND B ABOVE.
  - WATER MAIN SHALL NOT BE INSTALLED WITHIN 100 HORIZONTAL FEET OF ANY SANITARY LANDFILL, WASTEWATER DISPOSAL POND, OR HAZARDOUS WASTE DISPOSAL SITE.
  - WATER MAIN SHALL NOT BE INSTALLED WITHIN 25 HORIZONTAL FEET OF ANY CESSPOOL, SEPTIC TANK, SEWAGE LEACH FIELD, SEEPAGE PIT, UNDERGROUND HAZARDOUS MATERIAL STORAGE TANK, OR GROUNDWATER RECHARGE PROJECT SITE.
- WHEN ASSEMBLING A PVC C-900 PIPE TO AN IRON FITTING (PUSH-ON OR MECHANICAL JOINT), REMOVE ALL BUT 1/4 INCH OF THE FACTORY-MADE BEVEL FROM THE SPIGOT END OF THE PIPE PRIOR TO INSTALLATION.
- VALVE GANS AND COVERS SHALL BE PLACED OVER ALL VALVES. COVERS SHALL BE SET TO EXISTING FINISHED GRADE AND RESET IF NECESSARY ONCE THE STREET IS AT FINAL GRADE. (SEE LATEST REVISION OF DRAWINGS CW-14 AND CW-439).
- NO VALVE COVERS ARE TO LIE IN SIDEWALKS, CROSS GUTTER, CURB OR DRIVEWAYS. EACH SERVICE SHOULD ALSO BE LOCATED TO PROVIDE PROTECTION TO THE METER BOX FROM VEHICLE TRAFFIC AND PARKING.
- PROTECT UNDERGROUND FLEXIBLE COUPLINGS, BARE STEEL, MJ X MJ SLEEVES, AND ALL BOLTS (INCLUDING STAINLESS STEEL) AS FOLLOWS:
  - THE ENTIRE AREA OF THE FITTING MUST BE DRY AND FREE OF DUST, DIRT, AND OTHER FOREIGN MATTER. RUST OR OTHER FOREIGN MATTER MUST BE REMOVED BY SCRAPING OR WIRE BRUSHING. WIPING WITH A DRY CLEAN CLOTH MAY BE NECESSARY TO REMOVE THE PARTICLES FROM BRUSH CLEANING. ANY OIL OR GREASE, MUST BE REMOVED BY USING A LOW RESIDUE, VOLATILE PETROLEUM SOLVENT BEFORE APPLICATION OF GREASE AND WRAPPING.
  - THE EXPOSED AREA SHOULD BE COATED WITH A HEAVY COATING OF METALGUARD 301 GREASE BY THE GLOVE METHOD TO A THICKNESS OF AT LEAST 1/4".
  - FIRMLY WRAP THE ENTIRE GREASE AREA WITH ONE LAYER, HALF-LAPPED, OF A WOVEN GLASS FILAMENT MESH (RES OR BIT WRAP, 4" WIDE).
  - APPLY A SECOND LAYER OF METALGUARD 301 GREASE ON TOP OF THE GLASS FILAMENT BY THE GLOVE METHOD TO A THICKNESS OF AT LEAST 1/4".
  - FIRMLY WRAP THE ENTIRE GREASE AREA WITH A SECOND LAYER, HALF-LAPPED, OF THE WOVEN GLASS FILAMENT MESH.
  - COVER THE ENTIRE MESH WRAPPED AREA OF THE FITTING WITH A THIRD AND FINAL COATING AT LEAST 1/4" THICK OF METALGUARD 301 GREASE BY THE GLOVE METHOD.
  - FIRMLY APPLY 2 LAYERS OF POLYWRAP, HALF-LAPPED, OVER ALL AREAS OF THE COATED AND WRAPPED FITTING. BACKFILLING MAY FOLLOW IMMEDIATELY AFTER THIS WRAPPING.
- TRENCH BACKFILL AND PAVING SHALL CONFORM TO TRENCH SECTION DETAILS AND ALL GOVERNING AGENCY REQUIREMENTS.
- NEW PIPELINE SHALL BE INSTALLED WITH 4 FEET OF COVER, EXCEPT WHERE SPECIFIED.
- CONTRACTOR SHALL LIMIT DAILY TRENCHING OPERATIONS TO THE LENGTH OF PIPE THAT CAN BE INSTALLED AND BACKFILLED THAT DAY.
- CONTRACTOR SHALL INSTALL NEW MAIN AND ADJUST FROM NOMINAL LINE AND GRADE TO MATCH THE EXISTING FACILITIES AT ALL LOCATIONS. THE CONTRACTOR SHALL INSTALL A TEMPORARY CAP AND BLOW-OFF AT TIE-IN LOCATIONS FOR TESTING. (SEE LATEST REVISION OF DRAWINGS CW-122 & CW-638). CONTRACTOR WILL TIE THE NEW MAIN FROM THIS LOCATION.
- THE NEW PIPELINE SHALL BE TESTED AT 150 PSI FOR A PERIOD OF 4 HOURS. SEE SPECIFICATIONS TO DETERMINE EXACT TESTING REQUIREMENTS.
- TIE-INS TO BE MADE AT A TIME THAT IS CONVENIENT TO OWNER WHICH MAY BE AT NIGHTS OR WEEKENDS. THE ADDITIONAL COST DUE TO OVERTIME PAY SHALL BE AT OWNER'S EXPENSE.
- CONTRACTOR SHALL PROVIDE MISC. MATERIAL REQUIRED TO COMPLETE THE TIE-IN SUCH AS, BUT NOT LIMITED TO: PROTECTION COATING MATERIAL FOR PIPE AND FITTINGS, LINEGUARD TAPE, CONCRETE FOR THRUST BLOCKS, EMBEDMENT BACKFILL AROUND AND OVER THE PIPE, FINAL BACKFILL TO MEET COMPACTION REQUIREMENTS, AND PAVEMENT REPLACEMENT.
- CONTRACTOR SHALL BE RESPONSIBLE TO ABANDON ALL PIPE ENDS BY PLUGGING WITH BRICK AND MORTAR. ABANDON ALL GATE VALVES BY REMOVING COVER, CUT CASING DOWN TO SUBGRADE, AND BACKFILL VALVE CASING WITH CONCRETE SLURRY TO REMOVE VOIDS. REPLACE BASE ROCK AND PERMANENT PAVEMENT AS NECESSARY. WHEN REMOVING EXISTING FITTINGS, CONTRACTOR SHALL ALSO REMOVE EXISTING CONCRETE THRUST BLOCK.
- CONTRACTOR SHALL RESTORE LAWN, GUTTER, PAVEMENT, BERM, AND CURB TO MATCH EXISTING PER GOVERNING AGENCY'S STANDARDS.
- SPOILS SHALL NOT REMAIN ON-SITE. DISPOSAL OF ALL PROJECT-GENERATED SPOILS SHALL BE AT A FACILITY LICENSED AND CLASSIFIED TO ACCEPT THE MATERIALS. CONTRACTOR TO PROVIDE OWNER WITH A FORMAL RECEIPT FROM THE ACCEPTING FACILITY. ALL MATERIALS THAT WILL REQUIRE TESTING PRIOR TO DISPOSAL SHALL BE SAMPLED AND TESTED IN ACCORDANCE WITH THE REQUIREMENTS OF THE DISPOSAL FACILITY IN ADVANCE OF THE NEED FOR DISPOSAL.
- THE LIST OF MATERIALS FOR THIS PROJECT IS FOR CWS CO. ESTIMATING AND REFERENCE PURPOSES ONLY, AND IS NOT INTENDED AS A FULL TAKE-OFF OF ALL MATERIALS REQUIRED TO COMPLETE THE PROJECT PER CWS CO. STANDARD SPECIFICATIONS.
- AT TIE-INS, CONTRACTOR SHALL SPRAY OR SWAB ALL FITTINGS WITH CHLORINE SOLUTION FOR DISINFECTION PRIOR TO FINAL CONNECTIONS.
- CONTRACTOR TO ENSURE AIR IN THE PIPELINE IS REMOVED USING EXISTING OUTLETS SUCH AS FIRE HYDRANTS AND BLOW OFFS. CONTRACTOR IS RESPONSIBLE FOR INSTALLING AIR RELEASES IF EXISTING OUTLETS ARE INSUFFICIENT.
- ALL WORK SHALL COMPLY WITH CAL WATER SPECIFICATIONS FOR MATERIALS, INSTALLATION, DISINFECTION AND DECHLORINATION PER LATEST REVISION OF DRAWING CW-863.
- ALL SLIP-ON WELDING FLANGES SHALL BE RAISED-FACE SLIP-ON WELDING FLANGES.

ENGINEERING



DEPARTMENT

REVISIONS:  
R1 - (9/29/21) PER COUNTY REVIEW COMMENTS  
R2 - (9/27/21) CHANGED QUANTITY OF TANK  
R3 - (6/24/2022) ADD NEW TRANSFORMER & MISC. PADS  
R4 - ADD SD LINE & BIO-RETENTION  
3/17/23

DATE: \_\_\_\_\_  
DRAWN BY: \_\_\_\_\_  
DESIGNED BY: \_\_\_\_\_  
TECH REVIEW: \_\_\_\_\_

PLAT SHEET NO.: **SM-31-22**  
SCALE:

**AS SHOWN**


**D. HEARN**

**J. HUYNH**

DATE: 6/2/2023

DATE: 6/2/2023

DATE: 6/2/2023










**MPS - SAN MATEO STA 031**  
**INSTALL TANK AND BOOSTER PUMP**  
**PIPING PLAN**

TITLE: \_\_\_\_\_  
DISTRICT: \_\_\_\_\_  
**116-MPS**

**SAN MATEO**  
DATE: **4/6/2021**  
PROJECT ID: \_\_\_\_\_  
**00118772**

DRAWING NO.: **MPS-5630 R4**  
SHEET 1 OF 3

USERNAME: DLE\_6/1/2023\_2:27 PM  
 FILENAME: G:\Capital\_Projects\116\_Mid\_Penninsula\00118772\_Sta\_31\_Ascension\_Heights\_Baywood\_Tank\_V2 - DESIGN\500 - Drawings\working drawings\MPS5630\_Piping\_Plan 4-24-2023.dwg



**NOTES:**

- STEEL CYLINDER PER A.S.A. WITH ASTM A53 TEST PRESSURE AND ASTM A36 PHYSICAL PROPERTIES.
- COATING SHALL BE REINFORCED WITH 14 GAUGE WIRE MESH OR 14 GAUGE WIRE SPIRALLY WOUND IN CENTER OF COATING PER LATEST REVISION OF AWWA STANDARD C205.
- WELDING FITTINGS SHALL BE ASTM A234 GRADE B.

**PIECE MARKED "A & B"**  
N.T.S.

PIECE "MARKED"	QTY	STEEL CYL. (OD)	SCH.	CML	CMC
A	1	8.63"	20	3/8"	3/4"
B	5	6.63"	40	3/8"	3/4"

CEMENT MORTAR LINING, CML  
CEMENT MORTAR COATING, CMC

**DD CL&C FABRICATION DETAIL**  
1.1-6  
N.T.S.

**ENGINEERING**

**DEPARTMENT**

REVISIONS:  
 R1-(9/9/21) PER COUNTY REVIEW COMMENTS  
 R2-(9/27/21) CHANGED DIAMETER OF TANK  
 R3-(6/24/2022) ADD NEW TRANSFORMER & MCC PANS  
 R4-ADD SD LINE & BIO-RETENTION  
 2/17/23

DISTRICT: \_\_\_\_\_  
 DATE: \_\_\_\_\_

SCALE: **SM-31-22**

**AS SHOWN**

DRAWN BY: **D. HEARN**

DESIGNED BY: **J. HUYNH**

TECH REVIEW: \_\_\_\_\_ DATE: \_\_\_\_\_

CHECKED BY: \_\_\_\_\_ DATE: 6/2/2023




APPROVED BY: \_\_\_\_\_ DATE: 6/2/2023

**MPS - SAN MATEO STA 031**  
**INSTALL TANK AND BOOSTER PUMP**  
**PIPING PLAN**


TITLE: \_\_\_\_\_  
 DISTRICT: **116-MPS**  
 DATE: **4/6/2021**  
 PROJECT ID: **00118772**  
 DRAWING NO.: **MPS-5630 R4**  
 SHEET 2 OF 3




USERNAME: DLF\_5/31/2023 3:49 PM  
 FILENAME: C:\Capital\_Projects\116\_Mid\_Penninsula\00118772\_Site\1\_ASCENSION HEIGHTS BAYWOOD TANK\2 - DESIGN\500 - Drawings\working drawings\MPS5630\_Piping\_Plan 4-24-2023.dwg



**SPACING REQUIREMENTS FOR VALVES**



**MOUSE HOLE DETAIL**




**INSTALLATION PROCEDURE**

1. Compact and level the bottom of the excavation.
  2. Place 8 inch layer of tamped 3/4" crushed drain rocks.
  3. Place the vault so that the cover is at finished grade elevation.
  4. Temporarily brace the inside of the vault in at least three locations against the opposite sidewalls during the backfill operation. One brace should be against the center, and the other two placed equally 18 inches from the center brace.
  5. Backfill around the vault with sand cement slurry. (Minimum 1 Sack Mix)
  6. Backfill in evenly distributed 12" lifts and cover the full length and width of the entire fill area before the next layer of material is placed.
  7. Remove bracing after backfill operation is completed. Allow cement slurry to set before removing bracing.
  8. Installation procedure is applicable for vaults up to 50" in depth.
- In addition to the above, contractors shall follow the local agency's requirements for installation and all applicable Codes.

**NOTE:**

VAULT MUST BE LOCATED BEHIND THE CURB, OUTSIDE THE TRAVELED WAY. IF VAULT MUST BE LOCATED IN TRAVELED WAY, A CONCRETE UTILITY VAULT WITH MANHOLE COVER SHALL BE USED.





**CWT** POLYMER VAULT WITH TORSION ASSISTED COVER  
 953-R5

**STANDARD SIZES**

SPECIFY QUANTITY	A-WIDTH	B-LENGTH	C-DEPTH	LOAD RATING	SPECIFY
1	48"	60"	60"	10K	
1	48"	72"	60"	10K	

\* SPECIFY LOAD RATING REQUIRED  
 10K-PEDESTRIAN ONLY  
 20K-INCIDENTAL TRAFFIC

NOTE: CHECK ARMORCAST CATALOG FOR CUSTOM SIZES TO FIT TYPE 2 INSTALLATIONS.



INSTALLATION	DIAMETER OF ROD	NUMBER OF RODS	NUMBER OF HEAVY HEX NUTS (2 PER ROD)	"L"	"T"	NUMBER OF CLIPS
BOOSTER	3/4"	4	8	18"	8"	2

\* VERIFY FOE-POE LENGTH IN THE FIELD

- NOTE:**
- 1) LENGTH OF "L" SHALL EQUAL THE LENGTH OF FOE-POE.
  - 2) ROD DIAMETER SHALL BE THE SAME DIAMETER AS THE FLANGE BOLT.
  - 3) USE 1/2" THICK BAR STOCK FOR CLIPS.

**DD** STAY ROD AND CLIP DETAIL  
 1.1-5 N.T.S.



**REVISIONS:**

NO.	DATE	DESCRIPTION
R1	09/29/21	PER COUNTY REVIEW COMMENTS
R2	09/27/21	CHANGED DRAINAGE OF TANK
R3	16/24/2022	ADD NEW TRANSFORMER & MCL PANS
R4		ADD SD LINE & BQ-RETENTION

DISTRIBUTION MAP  DATE:   
 PLAT SHEET    
 SYSTEM SCHEMATIC    
 STATION SCHEMATIC

PLAT SHEET NO.:

SM-31-22

SCALE:

AS SHOWN

DRAWN BY:

D. HEARN

DESIGNED BY:

J. HUYNH

TECH REVIEW: DATE:

CHECKED BY: DATE:

6/2/2023

APPROVED BY: DATE:

6/2/2023



MPS - SAN MATEO STA 031  
 INSTALL TANK AND BOOSTER PUMP  
 PIPING PLAN

TITLE:

DISTRICT:

116-MPS

SAN MATEO

DATE:

4/6/2021

PROJECT ID:

00118772

DRAWING No.:

MPS-5630 R4

SHT 3 OF 3



REVISIONS:
SEISMIC CRITERIA
DATE: 9/7/2021
BY: J. HUYNH

PLAT SHEET NO.:
SM-31-22

AS SHOWN
DRAWN BY:
D. HEARN

DESIGNED BY:
J. HUYNH

TECH REVIEW:
DATE:
8/26/2022

CHECKED BY:
DATE:
9/7/2022

APPROVED BY:
DATE:
9/7/2022

TITLE:
MPS - SAN MATEO STA 031
STANDARD BOLTED STEEL STORAGE TANK
PLAN LAYOUT AND ELEVATION

DISTRICT:
116-MPS
SAN MATEO
DATE:
4/20/2021
PROJECT ID:
00118772
DRAWING NO.:
MPS-5643 R3
SHT 1 OF 7

STANDARD BOLTED STEEL STORAGE TANK
STATION 031, SAN MATEO, CA.

GENERAL NOTES:

- 1. THIS CONTRACT SHALL BE FOR THE DETAILED DESIGN, FABRICATION, AND CONSTRUCTION OF THE PROPOSED BOLTED STEEL STORAGE TANK INCLUDING FOUNDATION, CATHODIC PROTECTION SYSTEM, INTERIOR AND EXTERIOR COATING SYSTEMS, TESTING AND DISINFECTION ACCORDING TO THE LATEST VERSION OF AWWA D-103.
2. CAL WATER TO COORDINATE WORK BETWEEN TANK CONTRACTOR AND FUTURE PUMP BUILDING, SITE-WORK, AND PIPING CONTRACTORS, AS NEEDED.
3. EXTERIOR WATER PIPING WORK WILL BE PERFORMED BY OTHERS AT A LATER DATE.
4. CAL WATER WILL PROVIDE TANK CONTRACTOR WITH ELEVATION BENCHMARK FOR EXCAVATION AND FOUNDATION WORK, AND TANK CENTER POINT LAYOUT.
5. TANK WORK SHALL BE AS PER CAL WATER SPECIFICATIONS. SEE "CALIFORNIA WATER SERVICE SPECIFICATION FOR FABRICATION AND ERECTION OF BOLTED STEEL TANK" IN THE CONTRACT BID PACKAGE.
6. UPON COMPLETION, TANK SHALL BE CLEANED, TESTED, AND DISINFECTED PER CAL WATER STANDARDS BY THE TANK CONTRACTOR. CONTRACTOR MAY BE REQUIRED TO PROVIDE WATER FOR CLEANING IF NONE IS AVAILABLE AT THE SITE.
7. TANK CONTRACTOR TO PROVIDE ADEQUATE DUST CONTROL MEASURES DURING CONSTRUCTION.
8. TANK CONTRACTOR MAY SUBSTITUTE HIS OWN DESIGN FOR ANY OF THESE ACCESSORIES IF APPROVED IN ADVANCE BY THE CAL WATER PROJECT ENGINEER.
9. LOCATION, SIZE AND DESIGN OF ALL ACCESSORIES SHALL MEET OSHA REQUIREMENTS.
10. TANK CONTRACTOR SHALL PROVIDE A DETAILED SHOP-DRAWING PACKAGE OF TANK AND FOUNDATION DESIGN DETAILS TO THE CAL WATER PROJECT ENGINEER FOR REVIEW AND STAMPED APPROVAL PRIOR TO FABRICATION.
11. CATHODIC PROTECTION SYSTEM REQUIREMENTS SHALL BE AS PER THE SPECIFICATION UNDER APPENDIX 'A' IN THE CONTRACT BID PACKAGE.
12. ALL SHOP PAINTING SHALL BE IN ACCORDANCE WITH THE LATEST VERSION OF THE CALIFORNIA WATER SERVICE CO. SPECIFICATIONS FOR PAINTING STEEL WATER STORAGE TANKS AND FACILITIES.
13. THE UNDERSIDE OF TANK FLOOR PLATE STEEL SHALL REMAIN UNCOATED.
14. CAL WATER TO PROVIDE SITE GEOTECHNICAL REPORT AS PART OF THE CONTRACT BID PACKAGE.
15. ALL LOCK HASPS SHALL FIT A CAL WATER STANDARD LOCK, WHICH IS A MASTER PROSERIES 6727.

STATION ADDRESS
OFF OF BEL AIRE ROAD, SAN MATEO, CA
94551 ALAMEDA COUNTY
APN# 098-034802000

PROPOSED TANK DATA:



TANK CAPACITY: 58,929 GALLONS
TANK DIAMETER: 21'-6 1/2" FEET
TANK HEIGHT: 24'-2 3/8" FEET
HEIGHT TO OVERFLOW: 21'-3 3/8" FEET
FOUNDATION TYPE: CONCRETE RINGWALL
INTERIOR MATERIAL: ASPHALT OVER BASE ROCK
EXTERIOR COLOR: CWS "GROUSE TAN"

LIST OF ACCESSORIES

Table with columns: ACCESSORY, QUANTITY, SIZE, LOCATION. Lists items like INLET, OUTLET, 30" MANHOLE, EXTERIOR LADDER, INTERIOR LADDER, 6" DRAIN, OVERFLOW, FLUSH-TYPE CLEANOUT, THREADED OUTLET, SENSING LINE TAPS, SAMPLE TAP, TANK VENT (CENTER), LIQUID LEVEL INDICATOR.

SHEET INDEX:

- SHEET 1 GENERAL PROFILE, LAYOUT, AND ORIENTATION
SHEET 2 TANK FOUNDATION DETAILS AND NOTES
SHEET 3 TANK SHELL DETAILS AND ACCESSORIES
SHEET 4 LADDER DETAILS AND ACCESSORIES
SHEET 5 ROOF DETAILS AND ACCESSORIES
SHEET 6 MISCELLANEOUS DETAILS AND ACCESSORIES
SHEET 7 CATHODIC PROTECTION DETAILS AND ACCESSORIES



LEGEND


- TEE
ELBOW, 45°
ELBOW, 90°
BLOWOFF (PROPOSED)
BLOWOFF (EXISTING)
GATE VALVE (PROPOSED)
GATE VALVE (EXISTING)
REDUCER (PROPOSED)
REDUCER (EXISTING)
SOLID PLUG
PROPOSED WATER MAIN
EXISTING WATER MAIN
WALL
SANITARY SEWER
STORM DRAIN
FIRE HYDRANT (PROPOSED)
FIRE HYDRANT (EXISTING)
BUTTERFLY VALVE
CHECK VALVE
FLEX C.P.L.G.
BOOSTER PUMP
FLEX-TEND

SEISMIC DESIGN PARAMETERS:


- 1. USE GROUP FACTOR = 1
2. IMPORTANCE FACTOR = 1.0
3. SITE SOIL CLASS = B
4. 0.2-SECOND MAPPED SPECTRA ACCELERATION = 2.313g
5. 1-SECOND MAPPED SPECTRA ACCELERATION = 0.967g
6. SHORT PERIOD SITE COEFFICIENT = 0.9
7. LONG PERIOD SITE COEFFICIENT = 0.8
8. IMPULSIVE DESIGN ACCELERATION = 1.388g
9. CONVECTIVE DESIGN ACCELERATION = 0.516g
10. VERTICAL DESIGN ACCELERATION = 0.300g

GEOTECHNICAL INVESTIGATION:

SEISMIC DESIGN PARAMETERS PER GEOTECHNICAL INVESTIGATION PREPARED BY MICHELUCCI & ASSOCIATES, INC., JOB NO. 01-3186 DATED DECEMBER 16, 2020 AND UPDATED SEISMIC CRITERIA LETTER DATED 9/7/2021.




ELEVATION PROFILE N.T.S.



PLAN VIEW - TANK ACCESSORIES ORIENTATION N.T.S.


USERNAME: Dhearn\_8/24/2022 2:15 AM
FILENAME: G:\Capitol\_Projects\116\_Mid\_Penninsula\00118772\_Sta\_31\_Ascension\_Heights\BAYWOOD\_TANK\2 - DESIGN\500 - Drawings\working drawings\MPS5643\_Steel Bolted Tank and Details 8-16-2022.dwg

USERNAME: D:\Users\8/24/2022 7:15 AM  
 FILENAME: G:\Capitol\Projects\116\_Mid\_Penninsula\00118772\_Station\_31\_ASCENSION HEIGHTS BAYWOOD TANK.V2 - DESIGN\500 - Drawings\working drawings\MPS5643\_Steel Bolted Tank and Details 8-16-2022.dwg




- NOTES:**
- GRADE SOIL AS NECESSARY TO OBTAIN REQUIRED DRAINAGE. SLOPE BERM AWAY FROM TANK MIN. 5% AND GRADE BERM TYPES "b" & "c" AROUND TANK TO SLOPE MINIMUM 0.5% TO THE NEAREST CATCH BASIN OR ADEQUATE DRAINAGE.
  - START A.C. AT BASE OF TANK LIP AND KEY 1" UNDER TANK LIP. NO GAPS ALLOWED BETWEEN TANK LIP AND A.C. TO PREVENT WATER ENTRANCE UNDER TANK. CAULK GAP IF NECESSARY.
  - A.C. TO BE CALTRANS TYPE B ASPHALTIC CONCRETE WITH 3/8" MAXIMUM AGGREGATE SIZE.

**DETAIL A**  
TANK FOUNDATION CROSS SECTION  
N.T.S.




- NOTE:**
- TANK CONTRACTOR TO CALCULATE AND DESIGN ALL FOUNDATION DIMENSIONS AND REBAR REINFORCEMENT REQUIREMENTS. SEE TANK CONTRACTOR DESIGN DRAWING.


**DETAIL B**  
TANK RINGWALL FOUNDATION  
N.T.S.




**DETAIL C**  
FLUSH-TYPE CLEANOUT NOTCH  
N.T.S.



**DETAIL D**  
APRON/DRAIN BOX: TOP VIEW  
N.T.S.




**DETAIL E**  
TANK FOUNDATION & BERM  
N.T.S.



**SECTION F-F**

**DETAIL F**  
APRON/DRAIN BOX  
N.T.S.



**SECTION G-G**

**DETAIL G**  
FLUSH TYPE CLEANOUT DETAILS  
N.T.S.

- NOTES:**
- BUTTERFLY VALVE TO BE SUPPLIED BY TANK CONTRACTOR. VALVE TO BE DUCTILE IRON BODY AND SHALL COMPLY TO THE LATEST VERSION OF AWWA C504. VALVE SHALL BE MANUFACTURED BY MUELLER COMPANY, M&H VALVE & FITTING COMPANY, PRATT COMPANY OR KENNEDY VALVE CO.

**GENERAL NOTES:**

- TANK CONTRACTOR SHALL DESIGN THE FOUNDATION, AND PROVIDE "WET STAMPED" CALCULATIONS & SHOP-DRAWINGS TO THE OWNER.
- FOUNDATION SUB-CONTRACTOR SHALL BE A LICENSED GENERAL CONTRACTOR IN CALIFORNIA AND MUST HAVE EXPERIENCE IN TANK FOUNDATION CONSTRUCTION.
- ALL FOUNDATION DIMENSIONS AND REBAR REINFORCEMENT REQUIREMENTS SHALL BE PROVIDED BY THE TANK CONTRACTOR. (OR THE ENGINEERING CONSULTANT)

**EXCAVATION NOTES:**

- EXCAVATE EARTH MATERIAL WITHIN THE TANK FOOTPRINT LIMITS AS SPECIFIED IN THE GEOTECHNICAL REPORT. BACKFILL AS NECESSARY IN 8" LIFTS TO THE BOTTOM OF BASE ROCK ELEVATION. BACKFILL SHALL BE MOISTURE CONDITIONED AND COMPACTED TO 95% RELATIVE COMPACTION OR AS SPECIFIED IN THE GEOTECHNICAL REPORT.
- THE BOTTOM OF THE EXCAVATION SHALL BE REVIEWED BY THE GEOTECHNICAL ENGINEER OR HIS REPRESENTATIVE PRIOR TO ANY BACKFILL OPERATIONS. NATIVE MATERIALS EXPOSED AT THE BOTTOM OF THE EXCAVATION SHALL BE SCARIFIED, MOISTURE CONDITIONED, AND COMPACTED TO A MINIMUM OF 90% OF ASTM D-1557 OR AS SPECIFIED IN THE GEOTECHNICAL REPORT.

**FOUNDATION NOTES:**

- THE TOP OF THE CONCRETE RINGWALL FOUNDATION SHALL BE SMOOTH AND LEVEL WITHIN 1/8" IN 30' CIRCUMFERENTIAL LENGTH. THE REMAINDER OF THE TANK FOUNDATION PAD SURFACE SHALL BE SMOOTH AND FINISHED TO WITHIN 0.02' OF THE ESTABLISHED GRADE.
- THE BASE ROCK FOR THE FOUNDATION PAD SHALL BE CLASS 2 AGGREGATE MINIMUM SIZE 1/2". PROPELLED ROLLERS SHALL BE PERFORMED IN A MANNER IN WHICH BUMPS AND IRREGULARITIES ARE ELIMINATED AND THE FINISHED SURFACE SHALL BE TRUE TO THE REQUIRED GRADES AND BE COMPACTED TO 95% MAXIMUM DENSITY.
- THE PRIME COAT SHALL BE ASPHALT GRADE SS1H CONFORMING TO CAL-TRANS "STANDARD SPECIFICATIONS" AND APPLIED IN QUANTITIES BETWEEN 0.10 AND 0.25 GALLONS PER SQUARE YARD OF BASE COURSE.
- ASPHALT CONCRETE FOR THE TANK PAD SHALL BE "TYPE A" PER CALTRANS SECTION 39.
- JUST PRIOR TO PLACING THE FLOOR PLATES, APPLY PURE PORTLAND CEMENT TO THE ASPHALT SURFACE (6 SACKS TOTAL). WET AS NECESSARY TO PREVENT BLOWING.
- ANCHOR BOLTS TO BE A36 BOLT WITH HEAVY HEX HEAD, GALVANIZED; 5" MIN. THREAD LENGTH AT TOP. ALL ANCHOR BOLTS SHALL BE WITHIN 1/8" OF ESTABLISHED TANK RADIUS.
- THE OUTSIDE FACE OF THE RINGWALL SHALL BE FORMED TO PRODUCE A FINISHED SURFACE WITHIN 1/8" TOLERANCE OF THE DIMENSIONS SHOWN ON THE PLANS AND BE WITHOUT WAVES, RIDGES OR VOIDS. FORMS SHALL BE REMOVED NOT LESS THAN 5 DAYS AFTER CONCRETE HAS BEEN PLACED.
- FORMS, REINFORCING STEEL, AND SUBGRADE SHALL BE THOROUGHLY DAMPED BEFORE PLACING CONCRETE. CONCRETE SHALL BE THOROUGHLY CONSOLIDATED IN A MANNER APPROVED BY THE OWNER.
- ALL CONCRETE WORK SHALL CONFORM TO THE REQUIREMENTS OF ACI 301. THE MIXING AND PLACEMENT SHALL BE IN ACCORDANCE WITH ACI 318. THREE TEST CYLINDERS SHALL BE TAKEN FOR EACH 50 CUBIC YARDS OF CONCRETE PLACED WITH A MINIMUM OF THREE CYLINDERS FOR EACH DAY THAT THE CONCRETE IS PLACED. THE CONCRETE SHALL DEVELOP A MINIMUM (28 DAY) STRENGTH OF 3,000 PSI IN THE RINGWALL AND CENTER COLUMN FOOTING. ALL CONCRETE SHALL BE TESTED BY OWNER APPROVED TESTING AGENCY AND BE IN ACCORDANCE WITH ACI 318, SECT 4.7. ALL TEST RESULTS SHALL BE PROVIDED TO THE OWNER.
- REINFORCING STEEL SHALL BE GRADE 60 FOR RINGWALL AS DEFINED IN ASTM SPEC. A615. ANY REQUIREMENT OF THE CONCRETE REINFORCEMENT NOT COVERED IN THESE NOTES SHALL BE IN ACCORDANCE WITH THE "MANUAL OF THE STANDARD PRACTICES" AS PUBLISHED BY THE CONCRETE REINFORCING STEEL INSTITUTE.
- ALL CONCRETE SHALL BE CURED FOR A MINIMUM OF 7 DAYS AFTER PLACING.
- ALL CONCRETE SHALL CONTAIN A MINIMUM OF 6 SACKS OF CEMENT PER CUBIC YARD AND DEVELOP COMPRESSIVE STRENGTHS OF AT LEAST 3,000 PSI AT 28 DAYS. SLUMP TO BE 4" MAXIMUM. AGGREGATE TO BE 1" MAXIMUM. CONCRETE MUST BE PLACED WITHIN ONE HOUR AFTER MIXING HAS BEEN STARTED.
- CONTRACTOR SHALL TAKE ELEVATION READINGS OF FOUNDATION AS SOON AFTER CONCRETE PLACEMENT AS POSSIBLE. THE READINGS WILL BE TAKEN IN EVERY 10' OF SHELL CIRCUMFERENCE. THE RECORD OF READINGS AND THE MEASUREMENT OF THE MAXIMUM VARIATION IN ANY 30 FT. SHALL BE PROVIDED TO THE CAL WATER ENGINEER.

**ENGINEERING**



**DEPARTMENT**

**REVISIONS:**

NO.	DATE	DESCRIPTION
01	08/24/2022	ADD NEW TRANSFORMER & MCL PANS DET.
02	08/24/2022	ADD NEW TRANSFORMER & MCL PANS DET.
03	08/24/2022	ADD NEW TRANSFORMER & MCL PANS DET.
04	08/24/2022	ADD NEW TRANSFORMER & MCL PANS DET.
05	08/24/2022	ADD NEW TRANSFORMER & MCL PANS DET.

DISTRICT	DATE
PROJECT	
STATION	
SCALE	

PLAT SHEET NO.	
SM-31-22	
AS SHOWN	
DRAWN BY:	
D. HEARN	
DESIGNED BY:	
J. HUYNH	
TECH REVIEW:	

PLAT SHEET NO. SM-31-22

SCALE: AS SHOWN

DRAWN BY: D. HEARN

DESIGNED BY: J. HUYNH

TECH REVIEW: DATE:

CHECKED BY: DATE:

APPROVED BY: DATE:

DATE: 8/26/2022

DATE: 9/7/2022

MPS - SAN MATEO STA 031  
 STANDARD BOLTED STEEL STORAGE TANK  
 FOUNDATION DETAILS AND ACCESSORIES

TITLE:

DISTRICT:

116-MPS

SAN MATEO

DATE:

4/20/2021

PROJECT ID:


00118772

DRAWING NO.:

MPS-5643 R3

SHT 2 OF 7

USERNAME: Drcrm\_8/24/2022 7:16 AM  
FILENAME: G:\Capitol\_Projects\116\_Mid\_Peninsula\00118772\_Station\_31\_ASCENSION HEIGHTS BAYWOOD TANK\2 - DESIGN\500 - Drawings\working drawings\MPS5643\_Steel Bolted Tank and Details 8-16-2022.dwg



STANDARD LAYOUT DRAWINGS AND DETAILS FOR BOLTED-STEEL STORAGE TANK

ENGINEERING



DEPARTMENT

REVISIONS:  
01-09/2020-REVISED  
SEISMIC CRITERIA  
02-07/2021-CHANGED  
DRAINER OF TANK  
02-02/2022 ADD NEW  
TRANSFORMER & MCL PANS DET

DISTRIBUTION MAP   
PLAN SHEET   
SYSTEM SCHEMATIC   
STATION SCHEMATIC

PLAT SHEET NO.:

SM-31-22

SCALE:

AS SHOWN

DRAWN BY:

D. HEARN

DESIGNED BY:

J. HUYNH

TECH REVIEW: DATE:

CHECKED BY: DATE:

8/26/2022

APPROVED BY: DATE:

9/7/2022

MPS - SAN MATEO STA 031  
STANDARD BOLTED STEEL STORAGE TANK  
LADDER DETAILS AND ACCESSORIES

TITLE:

DISTRICT:

116-MPS

SAN MATEO

DATE:

4/20/2021

PROJECT ID:


00118772

DRAWING NO.:


MPS-5643 R3

SHT 3 OF 7


USERNAME: Drcrm\_8/24/2022 7:16 AM  
 FILENAME: G:\Capitol\_Projects\116\_Mid\_Peninsula\00118772\_Sta\_31\_ASCENSION HEIGHTS BAYWOOD TANK\2 - DESIGN\500 - Drawings\working drawings\MPS5643\_Steel Bolted Tank and Details 8-16-2022.dwg




**DETAIL P**  
 LADDER PROFILE  
 N.T.S.




**VIEW Z-Z**  
 ANTI-CLIMB DOOR INSTALLATION  
 N.T.S.




**FRONT VIEW**



**SIDE VIEW**




**DETAIL Z**  
 TYPICAL HINGE  
 N.T.S.




**DETAIL R**  
 ANTI-CLIMB DOOR  
 N.T.S.

**DOOR HASP COVER WELDING DETAIL**



**DETAIL AA**  
 HASPS FOR ANTI-CLIMB DOOR  
 N.T.S.



**ISOMETRIC VIEW OF ANTI-CLIMB DOOR**

ENGINEERING



DEPARTMENT

REVISIONS:  
 RL-09/2020-REPLATED  
 SEISMIC CRITERIA  
 RS-07/2021-CHANGED  
 DATE FOR THE TANK  
 RP-06/24/2020 ADD NEW  
 TRANSFORMER & MCL PANS. DI

DISTRIBUTION MAP   
 PLAN SHEET   
 SYSTEM SCHEMATIC   
 STATION SCHEMATIC

PLAT SHEET NO.:  
**SM-31-22**





SCALE:  
**AS SHOWN**  
 DRAWN BY:  
**D. HEARN**  
 DESIGNED BY:  
**J. HUYNH**  
 TECH REVIEW: DATE:

CHECKED BY: DATE:  
 8/26/2022  
 APPROVED BY: DATE:  
 9/17/2022

**MPS - SAN MATEO STA 031**  
**STANDARD BOLTED STEEL STORAGE TANK**  
**LADDER DETAILS AND ACCESSORIES**

TITLE:  
 DISTRICT:  
**116-MPS**  
**SAN MATEO**  
 DATE:  
**4/20/2021**  
 PROJECT ID:  
**00118772**  
 DRAWING NO.:  
**MPS-5643 R3**  
 SHEET 4 OF 7

USERNAME: D:\Users\8/24/2022 7:17 AM  
 FILENAME: G:\Capitol\_Projects\116\_Mid\_Peninsula\00118772\_Sta\_31\_ASCENSION HEIGHTS BAYWOOD TANK\2 - DESIGN\500 - Drawings\working drawings\MPS5643\_Steel Bolted Tank and Details 8-16-2022.dwg



**CUPOLA VENT SIZING CHART**

	A	B	C	F	F	G	H
24"	24	48	36	6	9 1/2	5 5/8	12 1/2

ALL NUMBERS ARE IN INCHES

- NOTES:**
1. VENT TO BE CONSTRUCTED OF A-36 STRUCTURAL STEEL AND COATED IN ACCORDANCE WITH CAL WATER ASPS-3B FOR THE INTERIOR AND CAL WATER ASPS-6A FOR THE EXTERIOR.
  2. 6x6 MESH MATERIAL SHALL BE STAINLESS STEEL.
  3. THROUGH HOLE FOR PADLOCK SHALL FIT A CAL WATER STANDARD LOCK.

**ENGINEERING**

**CALIFORNIA WATER SERVICE**

**DEPARTMENT**

REVISIONS:

NO.	DATE	DESCRIPTION
01	8/24/2022	ISSUED FOR PERMIT
02	8/24/2022	CHANGED
03	8/24/2022	ADD NEW
04	8/24/2022	ADD NEW

DISTRIBUTION:

DATE: 8/26/2022

SCALE: AS SHOWN

DESIGNED BY: D. HEARN

DESIGNED BY: J. HUYNH

TECH REVIEW: DATE: 9/7/2022

CHECKED BY: DATE: 8/26/2022

APPROVED BY: DATE: 9/7/2022

**PLAT SHEET NO. SM-31-22**

**MPS - SAN MATEO STA 031**

**STANDARD BOLTED STEEL STORAGE TANK**

**ROOF DETAILS AND ACCESSORIES**

TITLE: MPS - SAN MATEO STA 031  
 STANDARD BOLTED STEEL STORAGE TANK  
 ROOF DETAILS AND ACCESSORIES

DISTRICT: 116-MPS

SAN MATEO


DATE: 4/20/2021

PROJECT ID: 00118772


DRAWING NO.: MPS-5643 R3

SHT 5 OF 7


USERNAME: D:\Users\8/24/2022 7:17 AM  
 FILENAME: G:\Capitol\_Projects\116\_Mid\_Penninsula\00118772\_Station\_31\_ASCENSION HEIGHTS BAYWOOD TANK\2 - DESIGN\500 - Drawings\working drawings\MPS5643\_Steel Bolted Tank and Details 8-16-2022.dwg




**DETAIL FF**  
 8" INLET & 6" OUTLET  
 N.T.S.



**TOP**  
 N.T.S.




**FRONT**  
 N.T.S.



**SIDE**  
 N.T.S.

**DETAIL GG**  
 VORTEX PLATE DETAIL  
 N.T.S.



**SIDE**  
 N.T.S.

**DETAIL HH**  
 PIPE SUPPORT DETAIL  
 N.T.S.



REVISIONS:

01-09-2020	REVISED
03-07-2021	CHANGED
04-11-2021	TANK
02-04-2022	ADD NEW
	TRANSFORMER & MCL PANS DET

DISTRIBUTION MAP  DATE:   
 PLAN SHEET    
 SYSTEM SCHEMATIC    
 STATION SCHEMATIC

PLAT SHEET NO.: **SM-31-22**

SCALE: **AS SHOWN**

DRAWN BY: **D. HEARN**

DESIGNED BY: **J. HUYNH**

TECH REVIEW:   
 DATE:

CHECKED BY:   
 DATE: 8/26/2022

APPROVED BY:   
 DATE: 9/7/2022

MPS - SAN MATEO STA 031  
 STANDARD BOLTED STEEL STORAGE TANK  
 MISCELLANEOUS DETAILS AND ACCESSORIES

TITLE:   
 DISTRICT:

116-MPS



SAN MATEO

DATE: 4/20/2021


PROJECT ID: 00118772

DRAWING NO.: MPS-5643 R3


USERNAME: D:\Users\8/24/2022 7:18 AM  
 FILENAME: G:\Capitol\Projects\116\_Mid\_Peninsula\00118772\_Std\_31\_ASCENSION HEIGHTS BAYWOOD TANK\2 - DESIGN\500 - Drawings\working drawings\MPS5643\_Steel Bolted Tank and Details 8-16-2022.dwg




**DETAIL A**  
 CATHODIC PROTECTION SYSTEM LAYOUT  
 N.T.S.



**RECTIFIER MOUNTING BRACKET DETAIL**




**DETAIL B**  
 RECTIFIER MOUNTING DETAIL  
 N.T.S.



**TITANIUM ANODE CONNECTION DETAIL**


- KEY**
- ① #10 AWG HMWPE STRANDED COPPER WIRE.
  - ② ANODE TO CABLE CRIMP CONNECTION AND SILVER SOLDER AND 3-M RESIN SPLICE.
  - ③ MIXED METAL OXIDE ANODE WIRE, 0.062" DIA. ON TITANIUM WITH COPPER CORE.
  - ④ 1/2 LB. PORCELAIN WEIGHT

NOTE:  
 WEIGHT SIZE AND SHAPE MUST FIT THROUGH 5" DIA. ACCESS HOLE




**TYPICAL ANODE SUSPENSION SYSTEM DETAIL**


**DETAIL C**  
 CATHODIC PROTECTION ANODE ASSEMBLY  
 N.T.S.




**DETAIL D**  
 ANODE HANDHOLE  
 N.T.S.




**DETAIL E**  
 UNDER ROOF CABLE SUPPORT PORCELAIN INSULATOR DETAIL  
 N.T.S.



**DETAIL F**  
 ANODE SUSPENSION AND HANDHOLE DETAIL  
 N.T.S.



**DETAIL G**  
 WIRE AND CONDUIT TANK ENTRANCE DETAIL  
 N.T.S.



**DETAIL H**  
 TYPICAL SPLICE CONNECTION DETAIL

- NOTES:**
1. THE WIRING DIAGRAMS ON THIS DRAWING ARE GENERIC AND NOT SPECIFIC OF ANY SYSTEM. REFER TO THE INSTRUCTION BOOKLET AND SYSTEM WIRING DIAGRAMS INSIDE THE RECTIFIER CABINET DOOR FOR TESTING, ADJUSTMENTS AND TROUBLESHOOTING.
  2. WHEN REPLACING ANODES ALWAYS REPLACE THE ENTIRE HEADER CABLE, SEE DETAILS BB & CC. ALSO TEST THE RESISTANCE OF THE LEAD WIRES FROM THE RECTIFIER AND REPLACE THEM IF THEY ARE IN POOR CONDITION AND/OR THE WIRES ARE OTHER THAN NO. 10 AWG TYPE THWN, THHN OR HMWPE AS SHOWN ON THIS DRAWING.
  3. AFTER REPLACING ANODES (SEE DETAIL AA), INSTALLING SYSTEM COMPONENTS AND TROUBLESHOOTING THE SYSTEM, PERFORM A POLARITY TEST USING A D.C. VOLT METER. CONNECT THE COMMON TEST LEAD TO THE TANK STRUCTURE AND CONNECT THE POSITIVE LEAD TO THE ANODE WIRE SUPPLY. THE VOLTAGE READING MUST BE POSITIVE. THIS TEST MAY BE DONE AT THE RECTIFIER OUTPUT CONNECTIONS.
  4. CONTACT THE TANK MAINTENANCE DEPARTMENT FOR SYSTEM POWER REQUIREMENTS AND DESIRED SETTINGS. PERFORM A "POTENTIAL PROFILE TEST" OF THE SYSTEM USING A PORTABLE COPPER TO COPPER REFERENCE CELL. FILL OUT FORM NO. 74 AND SUBMIT TO THE ENGINEERING DEPARTMENT.



DEPARTMENT

REVISIONS:

NO.	DATE	DESCRIPTION
01	09/29/20	REVISED SEISMIC CRITERIA
02	07/27/21	CHANGED WATER TANK
03	06/24/2022	ADD NEW TRANSFORMER & MCL PANS DET.

PLAT SHEET NO.: **SM-31-22**

SCALE: **AS SHOWN**

DRAWN BY: **D. HEARN**

DESIGNED BY: **J. HUYNH**

TECH REVIEW: \_\_\_\_\_ DATE: \_\_\_\_\_

CHECKED BY: \_\_\_\_\_ DATE: **8/26/2022**

APPROVED BY: **D. Hearn** DATE: **9/12/2022**

TITLE: **MPS - SAN MATEO STA 031**  
**STANDARD BOLTED STEEL STORAGE TANK**  
**CATHODIC PROTECTION DETAILS & ACCESSORIES**

DISTRICT: **116-MPS**

PROJECT ID: **00118772**



DRAWING NO.: **MPS-5643 R3**

SHT 7 OF 7







Table with columns for DATE, DET., and rows for DISTRIBUTION, PLAN, SYSTEM, and PLAT SHEET NO.




CW VALVE COVER AND FRAME FABRICATION DETAILS FOR PAVED AND UNPAVED AREAS 14R6



STANDARD PAVED AREA INSTALLATION N.T.S.




EXISTING PAVED AREA PVC CASING AND SLIP SLEEVE EXTENSION N.T.S.



STANDARD UNPAVED AREA INSTALLATION N.T.S.




ALTERNATE UNPAVED AREA INSTALLATION N.T.S.




VALVE CASING FOOTING TOP VIEW N.T.S.


THRUST BLOCK SCHEDULE table with columns for PIPE SIZE, FITTING, SOFT CLAY, SAND, and ROCK, and rows for various fittings like PLUG, CAP, ELL, etc.




CW TYPICAL THRUST BLOCK INSTALLATION 435R4




PLAN VIEW




SPICE DETAIL FOR CUT WIRES







CW SAMPLING DEVICE FOR 2" BLOW-OFF 638R1




CW STANDARD INSTALLATION 850R4




CW STANDARD PRIVATE FIRE SERVICE CONNECTION 840R4




STANDARD INSTALLATION N.T.S.




CW TYPICAL FIRE HYDRANT INSTALLATION 380R16




CW SAMPLING DEVICE FOR 2" BLOW-OFF 638R1



CW STANDARD INSTALLATION 850R4



CW STANDARD PRIVATE FIRE SERVICE CONNECTION 840R4



MATERIAL FOR ITEM (A) (ETHER INSTALLATION)



Table with columns for REVISIONS, including date and description.

Approval and drawing information fields including DATE, DRAWN BY (M. FONG), DESIGNED BY, CHECKED BY, APPROVED BY, and SCALE (N.T.S.).

Table listing parts for 2" service connections, including part letters (A-T), part names, and manufacturer specifications (Mueller, Ford, A.Y. McDonald, Cambridge Brass, Smith-Blair, APAC).


- NOTES: 1. 2" SERVICE SHALL BE INSTALLED FOR ALL 1-1/2" METERS. 2. A SADDLE SHALL BE USED FOR ALL 2" SERVICES. 3. ALL PE PLASTIC PIPE REQUIRES TRACER WIRE TAPED TO PE PIPE AND EXTENDED INTO METER BOX PER LATEST REVISION OF DWG. CW-850 AND AS SPECIFIED IN CWS CO. MATERIAL SPECIFICATIONS DWG. CW-832.

- OPTIONS: THESE OPTIONS MAY BE REQUIRED BY CWS CO. 1. EXTEND CUSTOMER'S PIPING ±12" BEYOND METER BOX WITH TWO 12" NIPPLES & TWO 90° ELLS, BRASS (OR GALVANIZED IF PREFERRED BY CWS). SEE NOTE 5.


Table listing parts for 1" service connections, including part letters (A-J), part names, and manufacturer specifications (Mueller, Ford, A.Y. McDonald, Cambridge Brass, Smith-Blair, APAC).

- NOTES: 1. ALL PE PLASTIC PIPE REQUIRES TRACER WIRE TAPED TO PE PIPE AND EXTENDED INTO METER BOX PER LATEST REVISION OF DWG. CW-850 AND AS SPECIFIED IN CWS CO. MATERIAL SPECIFICATIONS DWG. CW-832.

- OPTIONS: THESE OPTIONS MAY BE REQUIRED BY CWS CO. 1. EXTEND CUSTOMER'S PIPING ±12" BEYOND METER BOX WITH TWO 12" NIPPLES & TWO 90° ELLS, BRASS (OR GALVANIZED IF PREFERRED BY CWS). SEE NOTE 5.



CW 555R15 STANDARD 1" SERVICE CONNECTION FOR 5/8" X 3/4" METER AND 1" METER




CW 436R9 STANDARD 2" SERVICE CONNECTION FOR 2" METER OR 1-1/2" METER [POLYETHYLENE INSTALLATION]


Table listing parts for 2" service connections, including part letters (A-T), part names, and manufacturer specifications (Mueller, Ford, A.Y. McDonald, Cambridge Brass, Smith-Blair, APAC).

- NOTES: 1. 2" SERVICE SHALL BE INSTALLED FOR ALL 1-1/2" METERS. 2. A SADDLE SHALL BE USED FOR ALL 2" SERVICES. 3. RESPONSIBILITY FOR SERVICE MAINTENANCE BY CWS CO. ENDS AT DOWNSTREAM METER COUPLING (OR LEFT TO DISTRICT'S DISCRETION).

- OPTIONS: THESE OPTIONS MAY BE REQUIRED BY CWS CO. 1. EXTEND CUSTOMER'S PIPING ±12" BEYOND METER BOX WITH TWO 12" NIPPLES & TWO 90° ELLS, BRASS (OR GALVANIZED IF PREFERRED BY CWS). SEE NOTE 3.



CW 1020 STANDARD 2" SERVICE CONNECTION FOR 2" OR 1-1/2" METER [COPPER INSTALLATION]



CW 122R5 STANDARD BLOW OFF ASSEMBLY FOR 12" TO 16" PIPE

CW 122R5 STANDARD BLOW OFF ASSEMBLY FOR 18" AND LARGER PIPE

TITLE: CALIFORNIA WATER SERVICE COMPANY STANDARD DRAWINGS

Drawing information fields including DISTRICT (ALL), DATE (5/12/2016), PROJECT ID, DRAWING NO. (CWDGWS), and SHEET 2 OF 2.



DEPARTMENT

REVISIONS: R6 Update Specs R7 Specs Update

DATE INT. DATE DATE DATE DATE DATE DATE

PLAT SHEET TITLE DRYING SCHEMATIC STATION NUMBER PLAT SHEET NO.: N.T.S.

DRAWN BY: L. Peralta

CHECKED BY: DATE:

APPROVED BY: DATE: 10/30/20

CALIFORNIA WATER SERVICE COMPANY SPECIFICATIONS FOR INSTALLATION OF DUCTILE IRON AND POLYVINYL CHLORIDE (PVC) PRESSURE PIPE AND APPURTENANCES DISINFECTION AND DECHLORINATION OF NEW MAINS

DATE: 10/30/20 PROJECT ID: DRAWING NO.: CW-863-R7

SPECIFICATIONS FOR MATERIAL

All materials in contact with drinking water shall conform to NSF 61 standards unless specified otherwise. All chemicals used in pipe shall conform to NSF 40 standards.

Ductile Iron (DI) Pipe: All DI pipe shall comply with the latest revision of AWWA Standard C151 and shall be cement mortar lined in conformance with the latest revision of AWWA Standard C104.

Polyvinyl Chloride (PVC) Pipe: All PVC pipe shall be Class 235, DR 18, unless otherwise specified. All PVC pipe shall be manufactured by PVC Pipe.

PVC Pipe with Push-on Joints: All PVC pipe shall have Push-on Joint ends complete with gasket unless specified otherwise on the drawings.

PVC Cert-Lok™ VIP Restraint Joint Pipe: All PVC Cert-Lok™ VVIP Restraint Joint pipe shall be manufactured by Certi-Lox.

Steel (S/I) Pipe: All Steel pipe shall comply with the latest revision of AWWA Standard C200. The pipe and flange shall be manufactured by a recognized manufacturer.

Polyethylene (PE) Pipe: This section is for PE pipe for sizes 4" and larger and shall only be used when specified on the drawings.

Restrainted Mechanical Joint (MJ) Adapters and Flanges: All restrained adapters shall conform to the latest revision of AWWA C111 and C112.

Butterfly Valves: Butterfly valves may be used for valves greater than 12" nominal size. All butterfly valves shall comply with the latest revision of AWWA Standard C504.

Control Valves: All control valves shall be manufactured by Clay-Viol Company. Model number, body design and other specifications shall be as specified on the drawings.

Blow-Off Assemblies: All materials for blow off assemblies shall be as shown on the latest revision of drawing CW-122.

Service Materials: All pipe material specifications except copper tubing and plastic PE pipe shall be as shown on the latest revision of drawings CW-555, CW-436 or CW-1020.

Saddles: All saddles shall be as specified on the latest revision of the applicable size service standard drawings: 1" - CW-555 and 2" - CW-436 or CW-1020.

Copper Tubing: All copper tubing shall conform to the latest revision of ASTM Specification B88 and be Type K or L.

Polyethylene (PE) Service Pipes: All PE plastic pipe for services shall comply with the latest revision of ASTM D2239 with a Standard Code Designation of PE 4710.

Meter Boxes: All meter boxes for 1" services and 2" services shall be as specified on the latest revision of drawings CW-555, CW-436, or CW-1020.

Tracer Wire: Tracer wire shall be minimum #12 AWG solid copper wire with 45 mils of high modulus polyethylene jacketing.

Fire Hydrants: All fire hydrants shall be as specified on the district specific drawing or as approved by CWS Co. fire department.

Fire Hydrant Bury: All fire hydrant burys shall be manufactured from Ductile Iron to ASTM A536 standards and have a minimum working pressure rating of 200 PSI.

Specifications for Installation of Ductile Iron and Polyvinyl Chloride (PVC) Pressure Pipe and Appurtenances

Permits: All specification sheets, city/county or other environmental permits necessary for the installation of facilities must be obtained by California Water Service Company.

Compliance with all the Rules and Regulations of the California Occupational Safety and Health Act (CAL OSHA), Public Law 91-596, the "Williams' Steiger Occupational Safety and Health Act of 1970."

Line and Grade: The horizontal and vertical alignment for installation of the pipe shall be established in the field by the Contractor in accordance with the plans and specifications.

Final Backfill: In areas where required, the permanent protection and temporary pavement replacement must comply with specifications of the local governing authorities.

Water Mains: Water mains shall be installed at least 4 feet horizontally from any parallel pipeline conveying water or storm drainage.

Workmanship: The pipe shall be installed to a true line and grade except on curves where ductile iron pipe may be installed with joint deflections between adjacent lengths of pipe not to exceed 3 degrees.

Field-cut lengths of PVC and DI pipe may be used for making connections to valves, fittings, appurtenances and closures when the pipe is cut by a power saw.

Trench Bottom: The bottom of the trench shall be smooth and free from pieces of rock or other material that would tend to scratch, puncture or break the pipe or damage the polyethylene encasement.

IMPORTANT: All trench excavations shall be in accordance with the Rules and Regulations of the California Occupational Safety and Health Act (CAL OSHA).

Pressure Test: Prior to any testing, at least seven days shall elapse after the last concrete thrust or grout is placed in the trench.

Leakage: The test is started at a pressure of 150 pounds per square inch. A calibrated pressure chart recorder and a water meter shall be provided by the Company.

Disinfection of Mains: All mains that are installed by the Contractor shall be disinfected by the Contractor in accordance with the "Specifications for Disinfection of New Mains."

during the assembly. Push the gland toward the socket and center it around the pipe with the gland lip against the gaskets and bolts and hand tighten the bottom bolt first.

If restrained mechanical joint adapters are specified on the plans, the adapter assembly shall be installed in accordance with the manufacturer's recommendations.

The entire area of the fitting should be dry and free of dust, dirt or other foreign matter. Rust should be removed from the area to be joined.

Two layers of polywrap, half lapped, should be firmly applied over all areas of the coated and wrapped fittings. Backfilling may follow immediately after this wrapping.

Thrust Blocks: Concrete thrust blocks shall be provided for all fittings to prevent movement when the pipe is installed under pressure.

Embedment Backfill: The embedment backfill is 6 inches of sand bedding below the pipe and 12 inches of sand backfill above the pipe.

Final Backfill: In areas where required, the permanent protection and temporary pavement replacement must comply with specifications of the local governing authorities.

Water Mains: Water mains shall be installed at least 4 feet horizontally from any parallel pipeline conveying water or storm drainage.

Workmanship: The pipe shall be installed to a true line and grade except on curves where ductile iron pipe may be installed with joint deflections between adjacent lengths of pipe not to exceed 3 degrees.

Field-cut lengths of PVC and DI pipe may be used for making connections to valves, fittings, appurtenances and closures when the pipe is cut by a power saw.

Trench Bottom: The bottom of the trench shall be smooth and free from pieces of rock or other material that would tend to scratch, puncture or break the pipe or damage the polyethylene encasement.

IMPORTANT: All trench excavations shall be in accordance with the Rules and Regulations of the California Occupational Safety and Health Act (CAL OSHA).

Pressure Test: Prior to any testing, at least seven days shall elapse after the last concrete thrust or grout is placed in the trench.

Leakage: The test is started at a pressure of 150 pounds per square inch. A calibrated pressure chart recorder and a water meter shall be provided by the Company.

Disinfection of Mains: All mains that are installed by the Contractor shall be disinfected by the Contractor in accordance with the "Specifications for Disinfection of New Mains."

The Contractor shall reserve the right to perform the tie-ins to the existing system if they desire. In this situation, the Contractor will be responsible for providing the necessary materials.

TABLE 1A: ALLOWABLE LEAKAGE PER 1000 FT. OF DUCTILE IRON PIPELINE. Table with columns for Average Test Pressure, Nominal Pipe Diameter, and Leakage per hour for various pipe sizes and pressures.

TABLE 1B: ALLOWABLE LEAKAGE PER 1000 FT. OF PVC C-900 PIPELINE. Table with columns for Average Test Pressure, Nominal Pipe Diameter, and Leakage per hour for various pipe sizes and pressures.

TABLE II: Number of 5-grain Calcium Hypochlorite Tablets Specified for Disinfection of at least 25 ppm. Table with columns for Length of Section and Diameters from 4" to 18".

SPECIFICATIONS FOR DISINFECTION OF NEW MAINS BASED ON THE PROCEDURES OUTLINED IN THE LATEST REVISION OF ANSI/AWWA C651

- 1. Precursors shall be taken to prevent soiling of pipe, fittings, valves and other materials. Pipe and fittings shall be stored so as not to accumulate mud or water.
- 2. All pipe shall be free of foreign materials and debris before lowering the pipe into the trench.
- 3. If at any time chemical contamination occurs (e.g. hydraulic oil, gasoline, diesel, etc), the pipe exposed to the contamination shall be replaced and not used for potable water applications.

- 4. When the main is left unattended for any length of time, the ends shall be plugged or completely wrapped to prevent the entrance of water, foreign material or small animals.
- 5. Loading of new mains: A reduced pressure principle (RPP) backflow prevention assembly (USC approved and lead-free compliant) is required to be installed in line with the domestic supply on all new main installations.
- 6. The backflow prevention assembly on the New Main Disinfection Report in non-erasable ink or pen writing.

TABLE III: Specified for Disinfection of at least 25 ppm. Table with columns for Length of Section and Diameters from 4" to 18".

TABLE IV: Allowable Chlorination Rate. Table with columns for Length of Section and Diameters from 4" to 20".

SPECIFICATIONS FOR DECHLORINATION OF FLUSHED WATER

- 1. The discharge/disposal of all chlorinated water generated from the procedures in the "Specifications for Disinfection of New Mains" shall be the Contractor's responsibility.
- 2. If dechlorination of the water is required, then the chlorinated water that is discharged to a storm drain shall be dechlorinated by water industry accepted methods.
- 3. Determine the chlorine concentration of the water to be flushed. If the water to be flushed contains a detectable level of chlorine, then that water must be dechlorinated as follows:

- A. At a minimum, the Contractor must meet a total chlorine residual of the 0.01mg/L in the discharge water.
- B. At a minimum, the Contractor must document the discharge using Col Water BMP Discharge Form.
- C. At a minimum, the Contractor must document the discharge using Col Water BMP Discharge Form.

- 11. If the bacteriological tests are positive, or if the HPC results are greater than 500 CFU/ml, further flushing and confirmation samples will be necessary.
- 12. The Contractor's Inspector and Supervisor will complete, sign and submit the New Main Disinfection Report in non-erasable ink or pen writing.
- 13. Before a tie-in is performed, the inside surface of all materials such as the tee, pipe nipples, couplings, and tapping sleeve must be swabbed with NSF 60 approved 12.5% sodium hypochlorite solution in accordance with the latest revision of AWWA Standard C651.

Use Dow Corning 732 Sealant or equivalent (NSF 61 approved) to fasten the required number of 5-grain calcium hypochlorite tablets (See Tables I) to the top and at the upstream end of each length of pipe.

When using flexible couplings, apply NSF 60 approved sodium hypochlorite with a spray bottle method in the annular space between the coupling and the pipe.

Fill the pipe very slowly with potable water at a velocity of no more than 1ft/sec. to eliminate air pockets and ensure calcium hypochlorite tablets do not become detached from the interior pipe surface.

- 1. Calculate the total volume (ounces or gallons) of 12.5% hypochlorite solution needed, based on the pipe diameter and section length (See Table III and the example below Table III.)
- 2. Choose a suitable filling rate and determine the time required to fill the water main from Table IV.
- 3. Calculate the 12.5% hypochlorite dose rate using the results from 1 and 2 above.

TABLE III: Specified for Disinfection of at least 25 ppm. Table with columns for Length of Section and Diameters from 4" to 18".

TABLE IV: Allowable Chlorination Rate. Table with columns for Length of Section and Diameters from 4" to 20".

SPECIFICATIONS FOR DECHLORINATION OF FLUSHED WATER

- 1. The discharge/disposal of all chlorinated water generated from the procedures in the "Specifications for Disinfection of New Mains" shall be the Contractor's responsibility.
- 2. If dechlorination of the water is required, then the chlorinated water that is discharged to a storm drain shall be dechlorinated by water industry accepted methods.
- 3. Determine the chlorine concentration of the water to be flushed. If the water to be flushed contains a detectable level of chlorine, then that water must be dechlorinated as follows:

- A. At a minimum, the Contractor must meet a total chlorine residual of the 0.01mg/L in the discharge water.
- B. At a minimum, the Contractor must document the discharge using Col Water BMP Discharge Form.
- C. At a minimum, the Contractor must document the discharge using Col Water BMP Discharge Form.

- 11. If the bacteriological tests are positive, or if the HPC results are greater than 500 CFU/ml, further flushing and confirmation samples will be necessary.
- 12. The Contractor's Inspector and Supervisor will complete, sign and submit the New Main Disinfection Report in non-erasable ink or pen writing.
- 13. Before a tie-in is performed, the inside surface of all materials such as the tee, pipe nipples, couplings, and tapping sleeve must be swabbed with NSF 60 approved 12.5% sodium hypochlorite solution in accordance with the latest revision of AWWA Standard C651.

Butterfly Valves: Butterfly valves may be used for valves greater than 12" nominal size. All butterfly valves shall comply with the latest revision of AWWA Standard C504, and shall be provided with "Y-type" packing, left hand to open, nut fitted with 2" square apertures nuts, ductile iron body, stainless steel shaft. All butterfly valves shall be manufactured by Mueller Company, M & H Valve and Fitting Company, Pratt Company or Kennedy Valve Co.

Butterfly Valves: Butterfly valves may be used for valves greater than 12" nominal size. All butterfly valves shall comply with the latest revision of AWWA Standard C504, and shall be provided with "Y-type" packing, left hand to open, nut fitted with 2" square apertures nuts, ductile iron body, stainless steel shaft.

Butterfly Valves: Butterfly valves may be used for valves greater than 12" nominal size. All butterfly valves shall comply with the latest revision of AWWA Standard C504, and shall be provided with "Y-type" packing, left hand to open, nut fitted with 2" square apertures nuts, ductile iron body, stainless steel shaft.

Butterfly Valves: Butterfly valves may be used for valves greater than 12" nominal size. All butterfly valves shall comply with the latest revision of AWWA Standard C504, and shall be provided with "Y-type" packing, left hand to open, nut fitted with 2" square apertures nuts, ductile iron body, stainless steel shaft.

Butterfly Valves: Butterfly valves may be used for valves greater than 12" nominal size. All butterfly valves shall comply with the latest revision of AWWA Standard C504, and shall be provided with "Y-type" packing, left hand to open, nut fitted with 2" square apertures nuts, ductile iron body, stainless steel shaft.

Control Valves: All control valves shall be manufactured by Clay-Viol Company. Model number, body design and other specifications shall be as specified on the drawings. All valves shall have factory set controls or pilots as specified on the drawings. All control or pilot piping shall be copper with bronze fittings. Vaults for control valves shall be as specified on the drawings.

Check Valves: Unless specified otherwise, all check valves shall be swing type with spring and lever and shall comply with the latest revision of AWWA Standard C508. The valves shall have Class 125 flanged ends unless otherwise on the drawings. Check valves shall be manufactured by Mueller Company, Clay-Viol Company, Malvern Co., or other manufacturer.

Check Valves: Unless specified otherwise, all check valves shall be swing type with spring and lever and shall comply with the latest revision of AWWA Standard C508. The valves shall have Class 125 flanged ends unless otherwise on the drawings.

Check Valves: Unless specified otherwise, all check valves shall be swing type with spring and lever and shall comply with the latest revision of AWWA Standard C508. The valves shall have Class 125 flanged ends unless otherwise on the drawings.

Check Valves: Unless specified otherwise, all check valves shall be swing type with spring and lever and shall comply with the latest revision of AWWA Standard C508. The valves shall have Class 125 flanged ends unless otherwise on the drawings.

Check Valves: Unless specified otherwise, all check valves shall be swing type with spring and lever and shall comply with the latest revision of AWWA Standard C508. The valves shall have Class 125 flanged ends unless otherwise on the drawings.

Check Valves: Unless specified otherwise, all check valves shall be swing type with spring and lever and shall comply with the latest revision of AWWA Standard C508. The valves shall have Class 125 flanged ends unless otherwise on the drawings.

Check Valves: Unless specified otherwise, all check valves shall be swing type with spring and lever and shall comply with the latest revision of AWWA Standard C508. The valves shall have Class 125 flanged ends unless otherwise on the drawings.

Check Valves: Unless specified otherwise, all check valves shall be swing type with spring and lever and shall comply with the latest revision of AWWA Standard C508. The valves shall have Class 125 flanged ends unless otherwise on the drawings.

Check Valves: Unless specified otherwise, all check valves shall be swing type with spring and lever and shall comply with the latest revision of AWWA Standard C508. The valves shall have Class 125 flanged ends unless otherwise on the drawings.

Check Valves: Unless specified otherwise, all check valves shall be swing type with spring and lever and shall comply with the latest revision of AWWA Standard C508. The valves shall have Class 125 flanged ends unless otherwise on the drawings.



Table with columns for REVISIONS, DATE, and INT.

Table with columns for DISTRIBUTION MAP, PLAN SYSTEM, SCHEMATIC, and STATION SCHEMATIC.

PLAT SHEET NO.:

SCALE: AS NOTED

DRAWN BY:

DESIGNED BY:

TECH REVIEW: DATE:

CHECKED BY: DATE:

APPROVED BY: DATE:

Handwritten signatures and dates: 5/27/2021

SPECIAL TESTS & INSPECTION SCHEDULE

THE FOLLOWING ITEMS SHALL BE INSPECTED. "SPECIAL INSPECTION" SHALL CONFORM TO 2019 CBC 1705. SPECIAL INSPECTION AGENCIES AND/OR INDIVIDUALS SHALL BE RETAINED BY THE OWNER AND APPROVED BY THE BUILDING OFFICIAL PRIOR TO ANY WORK.

Table with columns: ITEM, REQUIRED, REMARKS. Row: POST INSTALLED ANCHORS, YES, VISUAL-INSTALLATION PROCEDURES ONLY (PER SECTION 1705.1.1)

NOTES FOR FOUNDATION

1. GENERAL. ALL CONSTRUCTION NOT SPECIFICALLY DETAILED SHALL CONFORM TO THE REQUIREMENTS OF THE 2019 CALIFORNIA BUILDING CODE (CBC) AND ANY LOCAL CODE REQUIREMENTS.

THE CONTRACTOR SHALL COMPARE THIS DRAWING WITH EXISTING CONDITIONS AT THE SITE, AND WITH ALL OTHER APPLICABLE DRAWINGS. CONTRACTOR SHALL VERIFY MEASUREMENTS OF ALL EXISTING FEATURES AFFECTING HIS WORK, AND SHALL REPORT ANY DISCREPANCIES TO THE CALIFORNIA WATER SERVICE COMPANY ENGINEER FOR CLARIFICATION AND ADJUSTMENT BEFORE PROCEEDING WITH THE WORK.

FOUNDATION PREPARATION: AREAS TO RECEIVE FILL SHALL BE SCARIFIED TO A DEPTH OF SIX INCHES AND MOISTURE-CONDITIONED TO A MINIMUM OF 2% ABOVE OPTIMUM MOISTURE CONTENT, AND RECOMPACTED TO A MINIMUM 90% OF THE MAXIMUM DRY DENSITY PER ASTM D1557. AGRG. SHALL BE A MINIMUM OF 6" CLASS 2 AGGREGATE BASE (AB) UNDER ANY PROPOSED FOUNDATION COMPACTED TO 95% MDD.

FOOTINGS SHALL BE AS DETAILED ON THE DRAWINGS. THE FOUNDATION DESIGN IS BASED UPON THE VALUES FOR CLASS 5 MATERIALS LISTED IN TABLE 1806.2 OF THE CBC. THE FOOTINGS HAVE BEEN DESIGNED FOR AN ALLOWABLE SOIL BEARING PRESSURE OF 1,500 PSF (DL+LL) PLUS ONE THIRD INCREASE FOR WIND AND SEISMIC LOADS.

THE AGGREGATE BASE, FORMS AND SUBGRADE SHALL BE THOROUGHLY WETTED BEFORE PLACEMENT OF CONCRETE.

2. CONCRETE. ALL CONCRETE SHALL DEVELOP A MINIMUM ULTIMATE COMPRESSIVE STRENGTH OF 3000 PSI AT 28 DAYS OF AGE (DESIGN BASED ON 2500 PSI-NO SPECIAL INSPECTION IS REQUIRED PER EXCEPTION 2.3 IN SECTION 1705.3 OF 2019 CBC). THE SLUMP SHALL BE THE MINIMUM CONSISTENT WITH PLACING CONDITIONS BUT SHALL NOT EXCEED 4 1/2".

PLACE CONCRETE IN ACCORDANCE WITH ACI-301. ENSURE THAT REINFORCEMENT AND EMBEDDED ITEMS ARE NOT DISTURBING PLACEMENT OF CONCRETE. TOP OF THE FLOOR SHALL BE TRUE TO INDICATED ELEVATIONS. VARIATIONS SHALL NOT EXCEED 1/8" IN 10 FEET. THE LEVEL BEARING AREA AT THE TOP OF THE FOUNDATION SHALL RECEIVE A HARD STEEL TROWEL FINISH, SMOOTH AND LEVEL. CONTRACTOR SHALL PATCH IMPERFECTIONS AS REQUIRED BY CLIENT. PROTECT CONCRETE FROM PREMATURE DRYING, MAINTAIN CONCRETE WITH MINIMAL MOISTURE LOSS AT A RELATIVELY CONSTANT TEMPERATURE FOR PERIOD NECESSARY FOR HYDRATION OF CEMENT AND HARDENING OF CONCRETE. ALL EXPOSED HORIZONTAL AND VERTICAL EDGES AND CORNERS SHALL HAVE 3/4" x 3/4" CHAMFERS.

NO ALUMINUM CONDUIT OR PRODUCTS CONTAINING ALUMINUM OR ANY OTHER MATERIAL INJURIOUS TO THE CONCRETE SHALL BE EMBEDDED IN THE CONCRETE.

3. REINFORCING STEEL. ALL BARS SHALL BE GRADE 60 DEFORMED BARS CONFORMING TO ASTM A615. REINFORCING BAR BENDS AND STANDARD HOOKS SHALL CONFORM TO ACI 318, LATEST EDITION. ALL BENDS SHALL BE STANDARD HOOKS UNLESS OTHERWISE SHOWN. BARS 20 FEET AND SHORTER IN LENGTH SHALL BE IN SINGLE LENGTH RUNS WITHOUT SPLICES. BARS LONGER THAN 20 FEET IN LENGTH SHALL BE SPLICED WITH 48 BAR DIAMETER LAPS (2'-0" FOR #4 BARS). SPLICES IN ADJACENT BAR RUNS SHALL BE WELL STAGGERED.

4. SPECIAL INSPECTION. PERIODIC SPECIAL INSPECTION MUST BE PERFORMED WHERE REQUIRED FOR CONCRETE EPOXY ANCHORS IN ACCORDANCE WITH SECTION 1705.1.1 OF THE 2019 CBC, WHEREBY SPECIAL INSPECTION IS DEFINED IN SECTION 202 OF THE 2019 CBC.

5. EPOXY ANCHORS. EPOXY ANCHORS SHALL BE ASTM F993 HAS-R 316 STAINLESS STEEL THREADED ROD WITH HILTI HIT-RE 500 V3. ALL EPOXY ANCHORS SHALL BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS & ICC REPORT #3814. VISUAL SPECIAL INSPECTION IS REQUIRED.

SPECIAL NOTE

THE FOUNDATION MUST BE SQUARE, AND THE ANCHOR BOLTS MUST BE ACCURATELY PLACED PLUMB. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE FOUNDATION.

DESIGN LOADS

SCOPE: PROVIDE STRUCTURAL FOUNDATION & ANCHORAGE CALCULATIONS & DRAWINGS FOR NEW PANELBOARD, HYDRAULIC ENCLOSURE, GENERATOR TAP BOX.

SECTION 1604.5 & TABLE 1604.5: RISK CATEGORY III

SECTION 1606 - DEAD LOADS: PANELBOARD 4.0 K, ATS & GENERATOR TAP BOX 0.24 K

SECTION 1607 - LIVE LOADS: N/A

SECTION 1608 - SNOW LOAD: N/A

SECTION 1609 - WIND DESIGN DATA: BASIC DESIGN SPEED, V (3s GUST) 98 MPH

NOMINAL DESIGN SPEED, V<sub>ref</sub> = V[0.6 (3s GUST)] 76 MPH

WIND EXPOSURE C

INTERNAL PRESSURE COEFFICIENT N/A

DESIGN WIND PRESSURE (ASCE7-16 SECTION 26.10.2), q<sub>s</sub> 19.67 PSF

DESIGN WIND LOAD (ASCE7-16 SECTION 29.4 & 29.7), F<sub>s</sub> 1.50 K

SECTION 1613 - EARTHQUAKE DESIGN DATA

LATITUDE 37.5296°

LONGITUDE -122.3411°

SITE CLASS D - default

SPECTRAL RESPONSE @ 0.2 SEC PERIOD, S<sub>ds</sub> 2.303

SPECTRAL RESPONSE @ 1.0 SEC PERIOD, S<sub>d1</sub> 0.993

SHORT PERIOD SITE COEFFICIENT @ 0.2 SEC PERIOD, F<sub>s</sub> 1.200

LONG PERIOD SITE COEFFICIENT @ 1.0 SEC PERIOD, F<sub>s1</sub> 1.700

MODIFIED SPECTRAL RESPONSE @ 0.2 SEC PERIOD, S<sub>ms</sub> 2.764

MODIFIED SPECTRAL RESPONSE @ 1.0 SEC PERIOD, S<sub>m1</sub> 1.637

DESIGN SPECTRAL RESPONSE COEFFICIENTS, S<sub>ps</sub> 1.843

S<sub>ps1</sub> 1.091

CHAPTER 13: ELEMENTAL DESIGN (ASCE 7-16 SECTION 13.3.1):

SEISMIC DESIGN CATEGORY E

BASIC SEISMIC FORCE RESISTING SYSTEM PANELBOARD

SEISMIC IMPORTANCE FACTOR, I<sub>s</sub> 1.5

AMPLIFICATION FACTOR, a<sub>s</sub> (TABLE 13.6-1) 2.5

RESPONSE MODIFICATION FACTOR, R<sub>s</sub> (TABLE 13.6-1) 6.0

HEIGHT FACTOR, z/h (ANCHORS TO SLAB; z=0) 0.0

SEISMIC DESIGN FORCE, F<sub>s</sub> F<sub>s</sub> = (0.4a<sub>s</sub>S<sub>ds</sub>W) / (R<sub>s</sub>I<sub>s</sub>) [1+2 z/h] = 0.461 W<sub>e</sub>

MINIMUM SEISMIC DESIGN FORCE, F<sub>s(min)</sub> F<sub>s(min)</sub> = 3(S<sub>ds</sub>)(W<sub>e</sub>) = 0.829 W<sub>e</sub> (CONTROLS)

CHAPTER 15: NON-BUILDING STRUCTURES (ASCE 7-16: SECTION 15.4.2):

SEISMIC DESIGN CATEGORY E






BASIC SEISMIC FORCE RESISTING SYSTEM OTHER SELF SUPPORT EQ.

SEISMIC IMPORTANCE FACTOR, I 1.25

RESPONSE MODIFICATION FACTOR, R 1.25

EQUATION 15.4-5 QE = .3(S<sub>ds</sub>)(W)(I) = 0.691 W

EQUATION 15.4-2 (IF S<sub>1</sub> > 0.6g) QE = (0.8)(S<sub>1</sub>)(W) = 0.770 W



PANELBOARD, HYDRAULIC ENCLOSURE & RECEPTACLE BOX FOUNDATION PLAN & DETAIL

NOTE: CONTRACTOR SHALL ANCHOR PANELBOARD TO FOUNDATION AFTER CONTRACTOR HAS PLACED PANELBOARD ON FOUNDATION.



Project information block including Pacific Engineering Group, Inc. details, drawing date (05/26/2021), and project ID (118772).

TITLE: MPS - SAN MATEO STA. 031 PANELBOARD, HYDRAULIC ENCLOSURE & GENERATOR TAP BOX FOUNDATION PLAN & DETAILS

DISTRICT: 116-MPS

DATE: 05/26/2021

PROJECT ID: 118772

DRAWING NO.: MPS-5657

SHT 1 OF 1



REVISIONS:


DISTRIBUTION MAP

DATE: INT:

PLAT SHEET

SYSTEM SCHEMATIC

STATION SCHEMATIC

PLAT SHEET NO.:

SCALE:

AS NOTED

DRAWN BY:

DESIGNED BY:

TECH REVIEW: DATE:

CHECKED BY: DATE:

5/27/2021

APPROVED BY: DATE:

5/27/2021

MPS - SAN MATEO STA. 031  
 BOOSTER PUMP  
 FOUNDATION PLAN & DETAILS

TITLE:

DISTRICT:

116-MPS

DATE:

05/26/2021

PROJECT ID:

118772

DRAWING NO.:

MPS-5644

SHT 1 OF 1

SPECIAL TESTS & INSPECTION SCHEDULE

THE FOLLOWING ITEMS SHALL BE INSPECTED. "SPECIAL INSPECTION" SHALL CONFORM TO 2019 CBC 1705. SPECIAL INSPECTION AGENCIES AND/OR INDIVIDUALS SHALL BE RETAINED BY THE OWNER AND APPROVED BY THE BUILDING OFFICIAL PRIOR TO ANY WORK. FOR MATERIAL TESTING REQUIREMENTS, SEE SPECIFICATIONS AND/OR GENERAL NOTES. TESTING AGENCY SHALL SEND COPIES OF ALL STRUCTURAL TESTING AND INSPECTION REPORTS DIRECTLY TO THE BUILDING OFFICIAL AND ENGINEER.

ITEM	REQUIRED	REMARKS
POST INSTALLED ANCHORS	YES	VISUAL-INSTALLATION PROCEDURES ONLY (PER SECTION 1705.1.1)

NOTES FOR FOUNDATION

1. GENERAL  
 ALL CONSTRUCTION NOT SPECIFICALLY DETAILED SHALL CONFORM TO THE REQUIREMENTS OF THE 2019 CALIFORNIA BUILDING CODE (CBC) AND ANY LOCAL CODE REQUIREMENTS. ALL DETAILS, SECTIONS AND NOTES SHOWN ON THE DRAWINGS ARE INTENDED TO BE TYPICAL AND SHALL APPLY TO SIMILAR SITUATIONS ELSEWHERE UNLESS OTHERWISE NOTED.

THE CONTRACTOR SHALL COMPARE THIS DRAWING WITH EXISTING CONDITIONS AT THE SITE, AND WITH ALL OTHER APPLICABLE DRAWINGS. CONTRACTOR SHALL VERIFY MEASUREMENTS OF ALL EXISTING FEATURES AFFECTING HIS WORK, AND SHALL REPORT ANY DISCREPANCIES TO THE CALIFORNIA WATER SERVICE COMPANY ENGINEER FOR CLARIFICATION AND ADJUSTMENT BEFORE PROCEEDING WITH THE WORK. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR VERIFICATION OF ALL DIMENSIONS SHOWN ON THIS DRAWING WITH THE REQUIREMENTS OF EXISTING CONDITIONS AND ALL RELATED NEW EQUIPMENT.

FOUNDATION PREPARATION: AREAS TO RECEIVE FILL SHALL BE SCARIFIED TO A DEPTH OF SIX INCHES AND MOISTURE-CONDITIONED TO A MINIMUM OF 2% ABOVE OPTIMUM MOISTURE CONTENT, AND RECOMPACTED TO A MINIMUM 90% OF THE MAXIMUM DRY DENSITY PER ASTM D1557. THERE SHALL BE A MINIMUM OF 6" CLASS 2 AGGREGATE BASE (AB) UNDER ANY PROPOSED FOUNDATION COMPACTED TO 95% MDD.

FOOTINGS SHALL BE AS DETAILED ON THE DRAWINGS. THE FOUNDATION DESIGN IS BASED UPON THE VALUES FOR CLASS 5 MATERIALS LISTED IN TABLE 1806.2 OF THE CBC. THE FOOTINGS HAVE BEEN DESIGNED FOR AN ALLOWABLE SOIL BEARING PRESSURE OF 1,500 PSF (DL+LL) PLUS ONE THIRD INCREASE FOR WIND AND SEISMIC LOADS.

THE AGGREGATE BASE, FORMS AND SUBGRADE SHALL BE THOROUGHLY WETTED BEFORE PLACEMENT OF CONCRETE.

2. CONCRETE  
 ALL CONCRETE SHALL DEVELOP A MINIMUM ULTIMATE COMPRESSIVE STRENGTH OF 3000 PSI AT 28 DAYS OF AGE (DESIGN BASED ON 2500 PSI-NO SPECIAL INSPECTION IS REQUIRED PER EXCEPTION 2.3 IN SECTION 1705.3 OF 2019 CBC). THE SLUMP SHALL BE THE MINIMUM CONSISTENT WITH PLACING CONDITIONS BUT SHALL NOT EXCEED 4 1/2".

PLACE CONCRETE IN ACCORDANCE WITH ACI-301. ENSURE THAT REINFORCEMENT AND EMBEDDED ITEMS ARE NOT DISTURBING PLACEMENT OF CONCRETE. TOP OF THE FLOOR SHALL BE TRUE TO INDICATED ELEVATIONS. VARIATIONS SHALL NOT EXCEED 1/8" IN 10 FEET. THE LEVEL BEARING AREA AT THE TOP OF THE FOUNDATION SHALL RECEIVE A HARD STEEL TROWEL FINISH, SMOOTH AND LEVEL. CONTRACTOR SHALL PATCH IMPERFECTIONS AS REQUIRED BY CLIENT. PROTECT CONCRETE FROM PREMATURE DRYING, MAINTAIN CONCRETE WITH MINIMAL MOISTURE LOSS AT A RELATIVELY CONSTANT TEMPERATURE FOR PERIOD NECESSARY FOR HYDRATION OF CEMENT AND HARDENING OF CONCRETE. ALL EXPOSED HORIZONTAL AND VERTICAL EDGES AND CORNERS SHALL HAVE 3/4" x 3/4" CHAMFERS.

NO ALUMINUM CONDUIT OR PRODUCTS CONTAINING ALUMINUM OR ANY OTHER MATERIAL INJURIOUS TO THE CONCRETE SHALL BE EMBEDDED IN THE CONCRETE.

3. REINFORCING STEEL  
 ALL BARS SHALL BE GRADE 60 DEFORMED BARS CONFORMING TO ASTM A615. REINFORCING BAR BENDS AND STANDARD HOOKS SHALL CONFORM TO ACI 318, LATEST EDITION. ALL BENDS SHALL BE STANDARD HOOKS UNLESS OTHERWISE SHOWN. BARS 20 FEET AND SHORTER IN LENGTH SHALL BE IN SINGLE LENGTH RUNS WITHOUT SPLICES. BARS LONGER THAN 20 FEET IN LENGTH SHALL BE SPLICED WITH 48 BAR DIAMETER LAPS (2'-0" FOR #4 BARS). SPLICES IN ADJACENT BAR RUNS SHALL BE WELL STAGGERED.

4. SPECIAL INSPECTION  
 PERIODIC SPECIAL INSPECTION MUST BE PERFORMED WHERE REQUIRED FOR CONCRETE EPOXY ANCHORS IN ACCORDANCE WITH SECTION 1705.1.1 OF THE 2019 CBC, WHEREBY SPECIAL INSPECTION IS DEFINED IN SECTION 202 OF THE 2019 CBC.

5. EPOXY ANCHORS  
 EPOXY ANCHORS SHALL BE ASTM F953 HAS-R 316 STAINLESS STEEL THREADED ROD WITH HILTI HIT-RE 500 V3. ALL EPOXY ANCHORS SHALL BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS & ICC REPORT #3814. VISUAL SPECIAL INSPECTION IS REQUIRED.

SPECIAL NOTE

THE FOUNDATION MUST BE SQUARE, AND THE ANCHOR BOLTS MUST BE ACCURATELY PLACED PLUMB. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE FOUNDATION.

DESIGN LOADS

SCOPE: PROVIDE STRUCTURAL FOUNDATION & ANCHORAGE CALCULATIONS & DRAWINGS FOR NEW BOOSTER PUMP w/ACOUSTICAL SHELTER.

SECTION 1604.5 & TABLE 1604.5: RISK CATEGORY	III
SECTION 1606 - DEAD LOADS	
BOOSTER PUMP	146 lbs
ACOUSTICAL SHELTER	300 lbs
SECTION 1607 - LIVE LOADS	N/A
SECTION 1608 - SNOW LOAD	N/A

SECTION 1609 - WIND DESIGN DATA	
BASIC DESIGN SPEED, V (3s GUST)	98 MPH
NOMINAL DESIGN SPEED, V <sub>ref</sub> = V [0.6 (3s GUST)]	76 MPH
WIND EXPOSURE	C
INTERNAL PRESSURE COEFFICIENT	N/A
DESIGN WIND PRESSURE (ASCE7-16 SECTION 26.10.2), q <sub>s</sub>	19.4 PSF
DESIGN WIND LOAD (ASCE7-16 SECTION 29.4 & 29.7), F <sub>s</sub>	0.35 K (SHELTER)


SECTION 1613 - EARTHQUAKE DESIGN DATA	
LATITUDE	37.5996°
LONGITUDE	-122.3411°
SITE CLASS	D-default
SPECTRAL RESPONSE @ 0.2 SEC PERIOD, S <sub>s</sub>	2.303
SPECTRAL RESPONSE @ 1.0 SEC PERIOD, S <sub>1</sub>	0.963
SHORT PERIOD SITE COEFFICIENT @ 0.2 SEC PERIOD, F <sub>a</sub>	1.200
LONG PERIOD SITE COEFFICIENT @ 1.0 SEC PERIOD, F <sub>v</sub>	1.700
MODIFIED SPECTRAL RESPONSE @ 0.2 SEC PERIOD, S <sub>ms</sub>	2.784
MODIFIED SPECTRAL RESPONSE @ 1.0 SEC PERIOD, S <sub>ms1</sub>	1.637
DESIGN SPECTRAL RESPONSE COEFFICIENTS, S <sub>DS</sub>	1.843
	S <sub>DS1</sub> 1.091

CHAPTER 13: ELEMENTAL DESIGN (ASCE 7-16 SECTION 13.3.1):	
SEISMIC DESIGN CATEGORY	E
BASIC SEISMIC FORCE RESISTING SYSTEM	INSTRUMENT CABINET/SHEET METAL FRAMING PUMP


SEISMIC IMPORTANCE FACTOR, I <sub>e</sub>	1.5
AMPLIFICATION FACTOR, a <sub>s</sub> (TABLE 13.6-1)	2.5 ; 1.0
RESPONSE MODIFICATION FACTOR, R <sub>s</sub> (TABLE 13.6-1)	6.0 ; 2.5
HEIGHT FACTOR, z/h (ANCHORS TO SLAB; z=0)	0
SEISMIC DESIGN FORCE, F <sub>s</sub>	$F_s = \frac{0.4a_s W_p}{(R_s/I_e)} [1+2 \frac{z}{h}] = 0.461 W_p$
	$F_{s(max)} = 3(S_{ds})(W_p) = 0.829 W_p$
MINIMUM SEISMIC DESIGN FORCE, F <sub>s(min)</sub>	$F_{s(min)} = \frac{0.4a_s W_p}{(R_s/I_e)} = 0.442 W_p$
	(CONTROLS)

CHAPTER 15: NON-BUILDING STRUCTURES (ASCE 7-16: SECTION 15.4.2):	
SEISMIC DESIGN CATEGORY	E
BASIC SEISMIC FORCE RESISTING SYSTEM	OTHER SELF SUPPORT EQ.
SEISMIC IMPORTANCE FACTOR, I	1.25
RESPONSE MODIFICATION FACTOR, R	1.25


EQUATION 15.4-5	QE = 3(S <sub>ds</sub> )(I)(W) = 0.691 W
EQUATION 15.4-2 (IF S1>0.6g)	QE = $\frac{0.8(S_1)(W)}{R}$ = 0.770 W



FOUNDATION DETAIL (PLAN)  
 SCALE = 1" = 1'-0"



BASE PLAN  
 SCALE = 1" = 1'-0"




SECTION A-A  
 SCALE = 1" = 1'-0"

BOOSTER PUMP & ACOUSTICAL SHELTER FOUNDATION PLAN & DETAIL





21-030 Pacific Engineering Group, Inc.  
 3699 Blue Larkspur Lane, Suite 104 Monterey, CA 93940  
 ph. (831) 333-0644 fax. (831) 333-0645

DRAWN BY:	E. IBARRA	CHECKED BY:	E.I	DATE:	05/26/2021
DESIGNED BY:	E. IBARRA	APPROVED BY:	[Signature]	DATE:	05/26/2021



NOT VALID WITHOUT NET SIGNATURE

USERNAME: D:\Users\9/12/2022 10:53 AM  
 FILENAME: C:\Capital\_Projects\116\_Mid\_Penninsula\00118772\_Sta\_31\_ASCENSION HEIGHTS BAYWOOD TANK 2 - DESIGN\500 - Drawings\working drawings\Electrical\Dan 8-22-2022\MPS5476 R2 single line 8-17-2022.dwg



DEPARTMENT

REVISIONS:  
 R1- REVISED LAYOUT AND SINGLE LINE DIAGRAM  
 08/11/2021  
 R2- REVISED PEAK TRANSFORMER PAD LOCATION & SECONDARY SERVICE CONDUIT ROUTE, ADD TRANSFORMER PAD FOR THE SINGLE PHASE EXISTING METERS. 08/23/2022

DISTRICTION:  DATE:   
 MAP SHEET:   
 SYSTEM SCHEMATIC:   
 STATION SCHEMATIC:

PLAT SHEET NO.: **SM-31-22**


SCALE: **AS SHOWN**

DRAWN BY: **D. HEARN**

DESIGNED BY: **M. MACATIAG**

TECH REVIEW: **M. MACATIAG** DATE: 9/13/2022

APPROVED BY: **M. MACATIAG** DATE: 9/13/2022



TITLE: **MPS - SAN MATEO STA 031  
 INSTALL TANK AND BOOSTER PUMP  
 EQUIPMENT LAYOUT AND SINGLE LINE DIAGRAM**

DISTRICT: **116-MPS**


SAN MATEO

DATE: **5/5/2021**


PROJECT ID: **00118772**

DRAWING NO.: **MPS-5476 R2**

SHT 1 OF 1




USERNAME: D:\Users\8/30/2022 1:22 PM  
 FILENAME: C:\Capital\_Projects\116\_Mid\_Penninsula\00118772\_Sta\_31\_ASCENSION HEIGHTS BAYWOOD TANK 2 - DESIGN\500 - Drawings\working drawings\Electrical Dan 8-22-2022\MPS5597 - Conduit Layout and Details 8-17-2022.dwg



**LEGEND AND ABBREVIATIONS**

ABOVE GROUND	---
UNDERGROUND	- - - -
GROUND ROD	⊙
RADIO ANTENNA	⋈
EXISTING	(E)
CONDUIT TRENCH	- - - -
BOLLARDS	○
DEMO	▨
FIXED BOLLARD	○
REMOVABLE BOLLARD	(R)

**STATION ADDRESS**  
 OFF OF BEL AIRE ROAD, SAN MATEO, CA  
 94051 ALAMEDA COUNTY  
 APN# 098-034802000



**LIST OF CONDUITS**

ITEM	SIZE	FILL	DESCRIPTION	FROM	TO
U1	▲▲	▲▲	UTILITY 120/240V, 3PH, 4W SECONDARY FEED TO METER PANEL	PG&E TRANSFORMER (PAD)	METER PANEL (P/B SEC 1)
G1	N/A	N/A	MIN. 3/4"x10' CU GND ROD (PER LOCAL & NEC CODES)	PANELBOARD	GROUND WELL
G2****	1"	(1) #6 AWG BARE CU	GROUNDING ELECTRODE CONDUCTOR	PANELBOARD	GND ROD - GROUND WELL
G3****	1"	(1) #4 AWG BARE CU***	UFER GROUND	PANELBOARD FOUNDATION	P/B SECTION 2
G4****	1"	(1) #8 AWG BARE CU	BOOSTER A SHELTER BONDING	PANELBOARD GROUND BUS	BOOSTER A SHELTER
G5****	1"	(1) #8 AWG BARE CU	BOOSTER B SHELTER BONDING	PANELBOARD GROUND BUS SHELTER A	BOOSTER B SHELTER
G6****	1"	(1) #8 AWG BARE CU	TANK 2 BONDING	PANELBOARD GROUND BUS	TANK 2 GROUND TAB****
P1	2"	(3) #1 AWG CU, (1) #1 NEUT, (1) #8 GND	EMERGENCY POWER FOR PORTABLE GENERATOR	CAMLOCK RECEPTACLE	ATS - P/B SECTION 2
P2	1"	(3) #10 AWG CU, #10 GND	BOOSTER A FEEDER	P/B SECTION 4	BOOSTER A SHELTER
P3	1"	(2) #12 AWG CU, (1) #12 GND	BOOSTER A SPACE HEATER	P/B SECTION 4	BOOSTER A SHELTER
P4	1"	(3) #10 AWG CU, (1) #10 GND	BOOSTER B FEEDER	P/B SECTION 4	BOOSTER B SHELTER
P5	1"	(2) #12 AWG CU, (1) #12 GND	BOOSTER B SPACE HEATER	P/B SECTION 4	BOOSTER B SHELTER
P6	1"	(2) #12 AWG CU, (1) #12 GND	BOOSTER B SHELTER FANS	P/B SECTION 4	BOOSTER B SHELTER
P7	1"	(2) #12 AWG CU, (1) #12 GND	BOOSTER B SHELTER FANS	P/B SECTION 3	(E) CATHODIC PROTECTION PANEL (TANK 1)
P8	1"	(2) #12 AWG CU, (1) #12 GND	CATHODIC PROTECTION PANEL (TANK 2)	P/B SECTION 3	CATHODIC PROTECTION PANEL****
P9	1"	(2) #12 AWG CU, (1) #12 GND	TANK 2 MIXER	P/B SECTION 4	TANK 2 MIXER CONTROL BOX
P10	1"	(2) #10 AWG CU, (1) #10 GND	TAK 2 MIXER	P/B SECTION 4	TANK 2 MIXER JUNCTION BOX (VIA P/B, P/B)
P11	1"	(2) #12 AWG CU, (1) #12 GND	TANK 2 MIXER CONTROL BOX (VIA, P/B, P/B)	P/B SECTION 4	TANK 2 MIXER JUNCTION BOX****
C1	1"	(8) #16 AWG CU	HYDENC HEATER AND RECEPTACLE	P/B SECTION 4	HYDRAULIC ENCLOSURE
C2	1"	(8) #16 AWG CU	RECEPTACLE FOR PORTABLE GENSET HEATER AND BATTERY CHARGER	P/B SECTION 4	WEATHER PROOF GFCI RECEPTACLE
C3	1"	3/8" NYLON TUBE*	BOOSTER A CONTROLS	P/B SECTION 4	BOOSTER A SHELTER
C4	1"	COMBO CABLE (PROVIDED BY CWS)	BOOSTER B CONTROLS	P/B SECTION 4	BOOSTER B SHELTER
C5	1 1/2"	LMR-400 (PROVIDED BY CWS)	DISHARGE PRESSURE	P/B SECTION 4	HYDRAULIC ENCLOSURE
C6	1"	(4) #14 AWG CU, (1) #14 GND, (2) #14 SPARE	FLOWMETER	P/B SECTION 4	FLOWMETER (UNDERGROUND VAULT)
C7	1"	BELDEN CABLE**	ANTENNA (SEE CW-989 FOR SPECIFIC DETAIL)	RTU - P/B SECTION 4	RADIO ANTENNA
C8	1"	(2) #14 AWG CU, (3) #14 SPARE	(E) ALTITUDE VALVE, POWER & STATUS	P/B SECTION 3	(E) ALTITUDE VALVE (UNDERGROUND VAULT)
C9	1"	BELDEN CABLE**	(E) TANK 1 LEVEL	P/B SECTION 3	(E) TANK 1 LEVEL TRANSDUCER
C10	1"	(4) #14 AWG CU	ALTITUDE VALVE STATUS	P/B SECTION 3	ALTITUDE VALVE (UNDERGROUND VAULT)
C11	1"	(2) #14 AWG CU, (2) #14 AWG	TANK 2 LEVEL	RTU - P/B SECTION 4	TANK 2 LEVEL TRANSDUCER (ENCLOSURE BOX)****
C12	1"	(4) #14 AWG CU	TANK 2 INTUSION	P/B SECTION 4	TANK 2 (LADDER)
C13	1"	BELDEN CABLE**	START/STOP COMMAND	P/B SECTION 4	TANK 2 MIXER CONTROL BOX
C14	1"	BELDEN CABLE**	(E) TANK 1 INTUSION	P/B SECTION 4	(E) TANK 1 (LADDER)
S1	1"	PULL ROPE	DISHARGE PRESSURE TRANSMITTER	P/B SECTION 4	KDCR1 (HYDENC)
S2	1"	PULL ROPE	TANK 2 MIXER STATUS	P/B SECTION 4	TANK 2 MIXER CONTROL BOX
S3	1"	PULL ROPE	SPARE	P/B SECTION 4	FLOWMETER (UNDERGROUND VAULT)
S4	1"	PULL ROPE	SPARE	P/B SECTION 3	(E) ALTITUDE VALVE (UNDERGROUND VAULT)
S5	1"	PULL ROPE	SPARE	P/B SECTION 3	(E) CATHODIC PROTECTION PANEL
S6	1"	PULL ROPE	SPARE	P/B SECTION 3	(E) TANK 1
S7	1"	PULL ROPE	SPARE	P/B SECTION 4	ALTITUDE VALVE (UNDERGROUND VAULT)
S8	1"	PULL ROPE	SPARE	P/B SECTION 4	TANK 2
S9	1"	PULL ROPE	SPARE	P/B SECTION 3	PULLBOX PB1 (POWER)
S10	1"	PULL ROPE	SPARE	P/B SECTION 3	PULLBOX PB1 (POWER)
S11	1"	PULL ROPE	SPARE	P/B SECTION 4	PULLBOX PB2 (CONTROL)
S12	1"	PULL ROPE	SPARE	P/B SECTION 4	PULLBOX PB2 (CONTROL)


▲▲ PACIFIC GAS AND ELECTRIC SPECIFICATION  
 \* NYLON TUBING SHALL BE HUDSON EXTRUSION, INC. 3/8" O.D. MODEL NSF 51/61 (OR NSF CERTIFIED EQUAL)  
 \*\* BELDEN CABLE SHALL BE 18 AWG SHIELDED WIRE, BELDEN #9341  
 \*\*\* UFER GROUND, #4 AWG BARE STRANDED COPPER, MIN. 20' LONG, SEE DETAIL N  
 \*\*\*\* TANK VENDOR TO DETERMINE FINAL LOCATION  
 \*\*\*\*\* CONDUIT SLEEVE, CONNECT GROUNDING BARE COPPER TO THE NEAREST POINT OF PANELBOARD GROUND BUS

**LIST OF EQUIPMENT TO BE SUPPLIED & INSTALLED BY ELECTRICAL CONTRACTOR**

ITEM	DESCRIPTION
GEN TAP BOX	400A GENERATOR TAP BOX ASSEMBLY, CAMLOCK RECEPTACLE MALE CONNECTION (PSI CONTROL SOLUTION INC)
CAMLOCK CABLE	CAMLOCK POWER CABLE ASSEMBLED, (5) #1 DLO FLEX CABLE, 50 FEET, 16 SERIES COLOR CONNECTORS (BY/VIOWIG), MALE & FEMALE, TESTED BY PSI
DR3	RECEPTACLE FOR PORTABLE GENERATOR (HEATER AND CHARGER), HUBBEL OR LEVITON MAKE, 20A, 120VAC, ENCLOSED IN RAIN PROOF & WEATHER PROOF BOX AND COVER
GROUNDING WELL	GROUNDING ACCESS WELL, WITH GROUND ROD AND CONNECTION SEE GROUNDING WELL DETAIL
PB1, PB2	PULLBOXES SHALL BE TRAFFIC RATED, CHRISTY #R139 OR EQUAL
LS	INSTRUSION LIMIT SWITCH, SCHNEIDER XCKJ10541 (QTY:2)

**LIST OF EQUIPMENT TO BE SUPPLIED BY CALWATER & INSTALLED BY ELECTRICAL CONTRACTOR**

ITEM	DESCRIPTION
PANELBOARD	TESCO 100A PANELBOARD
HYDENC	HYDRAULIC ENCLOSURE EQUIPPED WITH PRESSURE TRANSMITTER, HEATER AND GFCI OUTLET
ANTENNA	RADIO ANTENNA
RTU	LEVEL TANK ENCLOSURE EQUIPPED WITH ROSEMOUNT PRESSURE TRANSMITTER
FM1	ROSEMOUNT 6705, 6" FLOW METER



**ENGINEERING**  
**CALIFORNIA WATER SERVICE**  
**DEPARTMENT**

REVISIONS:  
 R-1 REVISED WIRE SPEC REMOVED DR3 IN EQUIPMENT LIST APPEND FLOWMETER IN EQUIPMENT LIST, DH 7/7/2021  
 R-2 REVISED PG&E TRANSFORMER PAD LOCATION & SECONDARY SERVICE CONDUIT ROUTE, ADD TRANSFORMER PAD FOR THE SINGLE PHASE EXISTING METERS, ADD CABLE FOR THE TANK MIXER, DH 6-23-2022

DISTRICT: 116-MPS  
 SAN MATEO  
 DATE: 5/5/2021  
 PROJECT ID: 00118772  
 DRAWING NO.: MPS-5597 R2  
 SHEET 1 OF 3

**REGISTERED PROFESSIONAL ENGINEER**  
**MANDY MACATIAG**  
 No. E22351  
 ELECTRICAL  
 STATE OF CALIFORNIA

Checked by: 9/13/2022  
 Approved by: 9/13/2022

PLAT SHEET NO.: SM-31-22  
 SCALE: AS SHOWN  
 DRAWN BY: D. HEARN  
 DESIGNED BY: M. MACATIAG  
 TECH REVIEW: DATE:

TITLE: MPS - SAN MATEO STA 031 TANK AND BOOSTER PUMP CONDUIT LAYOUT & DETAILS





USERNAME: D:\Users\8/30/2022 1:23 PM  
 FILENAME: C:\Capital\_Projects\116\_Mid\_Penninsula\00118772\_Sta\_31\_ASCENSION HEIGHTS BAYWOOD TANK\2 - DESIGN\500 - Drawings\working drawings\Electrical\Don 8-22-2022\MPS5597 - Conduit Layout and Details 8-17-2022.dwg

WIRE APPLICATION AND COLOR CODE REQUIREMENTS				
APPLICATION	SUB APPLICATION	WIRE TYPE	SIZE	COLOR CODING
CONTROL PANELS (DOES NOT INCLUDE RTU PANELS)	INTERNAL 120/240VAC POWER	MTW	#12 FOR 20A CKTS #14 FOR 15A CKTS #16 FOR <15A CKTS	BK - L1 HOT, RD - L2 HOT, WH - NEUTRAL, GN - GROUND
	INTERNAL DEVICE WIRING CIRCUITS	MTW	#12 FOR 20A CKTS #14 FOR 15A CKTS #16 FOR <15A CKTS	BK - L1 HOT LEG, RD - L2 HOT LEG, BL - BETWEEN DEVICES, WH - NEUTRAL
	INTERNAL 24VDC DIGITAL DEVICE WIRING CIRCUITS	MTW	#16 MAX	RD - (+), BwR - (-)
	INTERNAL ANALOG SIGNAL WIRING	TSP/TST	#18 MAX	RD OR WH (+), BK (-)
	INSTRUMENT SHLD/GROUND	MTW	#18 MAX	GwY
FIELD WIRING	480V POWER WIRING	XHHW-2	AS REQ'D BY CIRCUIT SIZE	<=4/0: BN-OR-YL (A-B-C PHASES) >4/0: BK WITH BN-OR-YL PHASE TAPING AT TERMINATION POINTS
	120/240V, 3PH POWER WIRING	XHH2-2	AS REQ'D BY CIRCUIT SIZE	<=4/0: BK, RD FOR TWO 120V PHASES, OR FOR WILD LEG >4/0: BK WITH BK, RD & OR PHASE TAPING AT TERMINATION POINTS
	120/240VAC DIST. CKTS	XHHW-2	AS REQ'D BY CIRCUIT SIZE	BK - L1, RD - L2, WH - NEUTRAL, GN - GROUND
	120VAC CONTROL WIRING	THHN/THWN	#12 FOR 20A CKTS #14 FOR 15A CKTS #16 FOR <15A CKTS	BK - HOT LEG, PU - BETWEEN DEVICES & 120VDC DI CIRCUIT WIRING, WH - NEUTRAL
	24VDC DIGITAL WIRING	THHN/THWN	#16 MAX	RD (+), BwR (-)
	ANALOG SIGNAL WIRING	TSP/TST	#16 MAX	RD OR WH (+), BK (-), GwY - SHLD/GND


**COLOR CODE ABBREVIATIONS**

BK - BLACK	BL - BLUE
BN - BROWN	BwR - BLACK W/RED STRIPE
GN - GREEN	GwY - GREEN W/YELLOW STRIPE
GY - GRAY	OR - ORANGE
PU - PURPLE	RD - RED
WH - WHITE	YL - YELLOW

FIELD WIRING WIRE APPLICATION AND COLOR CODE REQUIREMENTS			
APPLICATION	WIRE TYPE	SIZE	COLOR CODING
480V POWER WIRING	XHHW-2	AS REQ'D BY CIRCUIT SIZE	<=4/0: BN-OR-YL (A-B-C PHASES) >4/0: BK WITH BN-OR-YL PHASE TAPING AT TERMINATION POINTS
120/240V, 3PH POWER WIRING	XHH2-2	AS REQ'D BY CIRCUIT SIZE	<=4/0: BK, RD FOR TWO 120V PHASES, OR FOR WILD LEG >4/0: BK WITH BK, RD & OR PHASE TAPING AT TERMINATION POINTS
120/240VAC DIST. CKTS	XHHW-2	AS REQ'D BY CIRCUIT SIZE	BK - L1, RD - L2, WH - NEUTRAL, GN - GROUND
120VAC CONTROL WIRING	THHN/THWN	#12 FOR 20A CKTS #14 FOR 15A CKTS #16 FOR <15A CKTS	BK - HOT LEG, PU - BETWEEN DEVICES & 120VDC DI CIRCUIT WIRING, WH - NEUTRAL
24VDC DIGITAL WIRING	THHN/THWN	#16 MAX	RD (+), BwR (-)
ANALOG SIGNAL WIRING	TSP/TST	#16 MAX	RD OR WH (+), BK (-), GwY - SHLD/GND

**COLOR CODE ABBREVIATIONS**


BK - BLACK	BL - BLUE
BN - BROWN	BwR - BLACK W/RED STRIPE
GN - GREEN	GwY - GREEN W/YELLOW STRIPE
GY - GRAY	OR - ORANGE
PU - PURPLE	RD - RED
WH - WHITE	YL - YELLOW




**BILL OF MATERIALS**

ITEM	QTY.	DESCRIPTION
1	AS REQ.	GROUND CONNECTOR, GROUND POST, BURNDY #KC26B1
2	AS REQ.	LOCKWASHER, 1/2", SILICON BRONZE
3	AS REQ.	NUT, HEX, 1/2"-13, SILICON BRONZE
4	AS REQ.	BOLT, MACHINE, 1/2"-20x1", W/NUT
5	AS REQ.	LOCKWASHER, 1/2"
6	1	SQUARE D #PK27GA GROUND BAR MTD ON GND BUS EACH SECTION
7	2	BAR, FLAT COPPER, 1/4" x 2"
8	1	GROUND ROD, COPPER, 3/4"x10'
9	AS REQ.	GROUND ROD CLAMP (HARGER 305)
10	1	CHRISTY BOX, WITH COVER MARKED GROUND
11	AS REQ.	REBAR GROUNDING CLAMP (JONES REBAR CLAMP J30-DB)


- NOTE:
- GROUND ELECTRODE CONDUCTOR THAT CONNECT DIRECT TO GROUND RING ELECTRODE TO BE SIZED ACCORDING TO NEC, TABLE 250.66
  - GROUND ELECTRODE CONDUCTOR THAT CONNECT DIRECT TO GROUND ROD OR PIPE NOT REQUIRED TO BE LARGER THAN #6, NEC 250.66 (A)
  - GROUND ELECTRODE CONDUCTOR THAT CONNECT DIRECT TO CONCRETE ENCASED ELECTRODE IS NOT REQUIRED TO BE LARGER THAN #4, NEC 250.66 (B)
  - GROUND CLAMP NUMBER ARE AS NEEDED, SHOULD BE INSTALLED PER NEC 250.52 (A)(3)



**DETAIL "K"**  
 CONDUITS STUBBING UP IN  
 OUTDOOR ENVIRONMENT  
 (N.T.S.)




**DETAIL "L"**  
 MINIMUM SPACING OF  
 BURIED CONDUITS  
 (N.T.S.)



**DETAIL "M"**  
 TANK LEVEL TRANSMITTER ENCLOSURE  
 FRAME SUPPORT  
 (N.T.S.)

**DETAIL "N"**  
 OUTDOOR SERVICE GROUNDING DETAIL  
 (N.T.S.)




**BILL OF MATERIALS**


ITEM	QTY.	DESCRIPTION
1	1 FT	CONDUIT, 1", PVC, SCH. 40 (NOTE 1)
2	1	ANCHOR, CONCRETE, 1/4"-20
3	1	BOLT, MACHINE, 1/4"-20x1", GALVANIZED
4	1	LOCKWASHER, 1/4", GALVANIZED
5	1	ONE HOLE CLAMP, 1", CROUSE-HINDS #MW512
6	1	CLAMP, 1", CROUSE-HINDS #CB3
7	1	GROUND CONNECTOR, GROUND POST, BURNDY #KC26B1
8	1	LOCKWASHER, 1/2", SILICON BRONZE
9	1	NUT, HEX, 1/2"-13, SILICON BRONZE

- NOTE:
- IF INSTALLED OUTDOOR USE 1" RGS CONDUIT WITH BUSHING. IT SHALL BE WRAPPED WITH 10-MIL TAPE ABOVE THE GRADE OR FLOOR.

**DETAIL "O"**  
 STORAGE TANK BONDING DETAIL  
 (N.T.S.)



**DETAIL "O"**  
 MAG METER WITH HYDRO CONDUIT  
 (N.T.S.)



**DETAIL "P"**  
 CONDUITS STUBBING UP IN ANY OUTDOOR  
 BOOSTER PUMP  
 (N.T.S.)



REVISIONS:  
 R-1 REVISED WIRE SPEC. REMOVED DR2 IN EQUIPMENT LIST. APPEND FLOWMETER IN EQUIPMENT LIST. CH 7/7/2021  
 R-2 REVISED PEAK TRANSFORMER PAD LOCATION & SECONDARY SERVICE CONDUIT ROUTE. ADD TRANSFORMER PAD FOR THE SINGLE PHASE EXISTING METERS. ADD CABLE FOR THE TANK MIXER. CH 6-23-2022

DISTRIBUTION MAP   
 PLAN SHEET   
 SYSTEM SCHEMATIC   
 STATION SCHEMATIC

PLAT SHEET NO.:  
**SM-31-22**

SCALE:  
**AS SHOWN**


DRAWN BY:  
**D. HEARN**

DESIGNED BY:  
**M. MACATIAG**

TECH REVIEW: DATE:

CHECKED BY: DATE:  
*Mano* 9/13/2022

APPROVED BY: DATE:  
*Macatiag* 9/13/2022



MPS - SAN MATEO STA 031  
 TANK AND BOOSTER PUMP  
 CONDUIT LAYOUT & DETAILS

TITLE:  
 DISTRICT:  
**116-MPS**


SAN MATEO  
 DATE:

5/5/2021  
 PROJECT ID:

00118772  
 DRAWING NO.:


MPS-5597 R2  
 SHEET 3 OF 3

USERNAME: Dhearn 9/13/2022 10:30 AM  
 FILENAME: G:\Capital\_Projects\116\_Mid\_Peninsula\00118772\_Station\1\_ASCENSION\_HEIGHTS\_BAYWOOD\_TANK\_V2 - DESIGN\500 - Drawings\working drawings\Electrical  
 Dwg 8-22-2022\MPS5596 - RTU Terminal 6-23-2022.dwg



(CONTINUED ABOVE RIGHT)


(CONTINUED FROM BELOW LEFT)



**LEGEND AND ABBREVIATIONS**

WIRING TO BE SUPPLIED AND INSTALLED IN FIELD  
 WIRING TO BE SUPPLIED AND INSTALLED BY PANELBOARD MANUFACTURER  
 BELDEN SHIELDED CABLE #9341, 18 GA. STRANDED, FOIL SHIELD & DRAIN SUPPLIED & INSTALLED IN FIELD  
 BELDEN SHIELDED CABLE #9341, 18 GA. STRANDED, FOIL SHIELD & DRAIN SUPPLIED & INSTALLED BY PANELBOARD MANUFACTURER  
 DATA - WIRING TO BE SUPPLIED AND INSTALLED BY PANELBOARD MANUFACTURER  
 ▲ TERMINAL BLOCK IN RTU  
 ■ OR ○ OTHER TERMINAL BLOCKS/CONNECTIONS

**ENGINEERING**



**DEPARTMENT**

REVISIONS:  
 R-1 ADED MIXER TANK START/STOP COMMAND AND STATUS WIRING TERMINATION BY 6/23/2022

NO.	DATE	BY

DISTRIBUTION:  
 MD  DATE:   
 PLAT SHEET    
 SYSTEM SCHEMATIC    
 STATUS SCHEMATIC


PLAT SHEET NO.:  
**SM-31-22**

SCALE:  
**AS SHOWN**

DRAWN BY:  
**D. HEARN**

DESIGNED BY:  
**M. MACATIAG**

TECH REVIEW: DATE:   
 CHECKED BY: DATE:   
 APPROVED BY: DATE:   
 9/13/2022  
 9/13/2022



**TITLE:**  
 MPS - SAN MATEO STA 031  
 TANK AND BOOSTER PUMP  
 RTU TERMINAL WIRING DIAGRAM

**DISTRICT:**  
 116-MPS

**DATE:**  
 6/22/2021

**PROJECT ID.:**  
 00118772

**DRAWING NO.:**  
 MPS-5596 R1

**SHEET 1 OF 1**



NO.	DATE	DESCRIPTION

DISTRIBUTION LIST:  DATE:

PLAT SHEET:

SYSTEM SCHEMATIC:

STATION SCHEMATIC:

PLAT SHEET NO.:

SCALE: AS SHOWN


DRAWN BY: D. HEARN

DESIGNED BY: M. MACATIAG

TECH REVIEW: DATE:


CHECKED BY: DATE: 7/16/2021

APPROVED BY: DATE: 7/16/2021



**LEGEND AND ABBREVIATION**

---	WIRING TO BE SUPPLIED AND INSTALLED BY PANELBOARD MANUFACTURER
---	WIRING TO BE SUPPLIED AND INSTALLED IN FIELD
▲	TERMINAL BLOCK IN RTU (SEE DWG# CW-1030-R3)
(F)	FEMALE CONNECTION
LS	DOOR LIMIT SWITCH
⊙	GROUND CONNECTION THROUGH GROUND ROD
Ⓚ	20 AMP GFCI TYPE RECEPTACLE
(E)	EXISTING



**SHEET NOTES**

1. THE B PHASE SHALL BE THAT PHASE HAVING THE HIGHER VOLTAGE TO GROUND ON A 3-PHASE, 4 WIRE DELTA CONNECTED SYSTEMS.

(E) POTABLE GENERATOR 50KW  
60HZ, 120/240V, 3P, 4W  
PROVIDED BY CWS

(LC1) LOAD CENTER

TITLE: MPS - SAN MATEO STA 031  
TANK AND BOOSTER PUMP  
ELECTRICAL SCHEMATIC

DISTRICT: 116-MPS

PROJECT ID: 00118772

DATE: 6/22/2021

DRAWING No.: MPS-5595

SHT 1 OF 2



REVISIONS:


DISTRIBUTION MAP

PLAT SHEET

SYSTEM SCHEMATIC

STATION SCHEMATIC

PLAT SHEET No.:

SCALE:  
AS SHOWN


DRAWN BY:  
D. HEARN

DESIGNED BY:  
M. MACATIAG

TECH REVIEW: DATE:

CHECKED BY: DATE: 7/16/2021  
Manding

APPROVED BY: DATE: 7/16/2021  
Manding



TITLE:  
MPS - SAN MATEO STA 031  
TANK AND BOOSTER PUMP  
ELECTRICAL SCHEMATIC

DISTRICT:  
116-MPS



SAN MATEO

DATE:  
6/22/2021



PROJECT ID:  
00118772

DRAWING No.:  
MPS-5595


SHT 2 OF 2




**DETAIL "A"**  
CONNECTION DIAGRAM  
FOR VFD PID CONTROL




FRONT EXTERIOR VIEW  
(EXTERIOR DOORS AND SUN SHADE REMOVED FOR CLARITY)




RIGHT SIDE VIEW




RELAY DETAIL  
N.T.S.




FRONT INTERIOR VIEW  
(EXTERIOR/INTERIOR DOORS AND SUN SHADE REMOVED FOR CLARITY)



REAR VIEW



BASE DETAIL



- NOTES:
- ONE NP10 REQUIRED PER EACH PANELBOARD SECTION.
  - BOLT NAME PLATE TO PANELBOARD.



REVISIONS:

NO.	DATE	BY

DISTRIBUTION MAP  DATE:   

PLAT SHEET  DATE:   

SYSTEM SCHEMATIC  DATE:   

STATION SCHEMATIC  DATE:   

PLAT SHEET NO.:

SCALE:

AS SHOWN

DRAWN BY:

D. HEARN

DESIGNED BY:

M. MACATIAG


TECH REVIEW:    DATE:   

CHECKED BY:    DATE:   

APPROVED BY:    DATE:   

7/16/2021

REGISTERED PROFESSIONAL ENGINEER



MPS - SAN MATEO STA 031  
TANK AND BOOSTER PUMP  
PANELBOARD LAYOUT

TITLE:

DISTRICT:  
116-MPS

SAN MATEO

DATE:  
6/22/2021

PROJECT ID:  
00118772

DRAWING No.:  
MPS-5598



DEPARTMENT

REVISIONS:

DISTRIBUTION MAP SHEET SYSTEM SCHEMATIC STATION SCHEMATIC

PLAT SHEET NO.:

SCALE:

AS SHOWN

DRAWN BY:

D. HEARN

DESIGNED BY:

M. MACATIAG


TECH REVIEW: DATE:

CHECKED BY: DATE:

Macatiag

APPROVED BY: DATE:

7/16/2021



TITLE: MPS - SAN MATEO STA 031 TANK AND BOOSTER PUMP PANELBOARD LAYOUT

TITLE:

DISTRICT:

116-MPS

SAN MATEO

DATE:

6/22/2021

PROJECT ID:

00118772

DRAWING NO.:

MPS-5598

SHT 2 OF 2

LIST OF EQUIPMENT TO BE SUPPLIED BY CWSC AND INSTALLED & WIRED BY PANELBOARD MANUFACTURER

Table with 5 columns: ITEM, QUANTITY, MFR, PART NUMBER, DESCRIPTION. Includes items like ATS, FT1.

OUTDOOR PANELBOARD MANUFACTURING NOTES:

- 1. PANELBOARD SHALL BE NEMA 3R RATED FOR OUTDOOR, MADE OF 12GA. STEEL, 20" DEEP.
2. PANELBOARD SHALL BE RATED FOR A MINIMUM OF 35,000 AMPS A.I.C. CURRENT RATING...
3. ALL EQUIPMENT INSTALLED IS REQUIRED TO BE LISTED AND LABELED BY UNDERWRITER LABORATORIES...

LABELING FOR LOAD CENTER (LC1)

Table with 2 columns: ITEM, DESCRIPTION. Lists components like TANK 2 MIXER CONTROL BOX, THERMOSTATS, FANS, etc.

INSTALL NAMEPLATES AS SHOWN NAMEPLATE SCHEDULE (1" X 3") UNLESS OTHERWISE SPECIFIED

Table with 2 columns: ITEM, DESCRIPTION. Lists nameplates for various components like NP1, NP2, NP3, etc.

LIST OF EQUIPMENT TO BE SUPPLIED, INSTALLED AND WIRED BY PANELBOARD MANUFACTURER

Table with 5 columns: ITEM, QUANTITY, MFR, PART NUMBER, DESCRIPTION. Detailed list of electrical components and their specifications.

PANELBOARD WIRE APPLICATION AND COLOR CODE REQUIREMENTS

Table with 4 columns: SUB APPLICATION, WIRE TYPE, SIZE, COLOR CODING. Defines wire types and color codes for different applications.

COLOR CODE ABBREVIATIONS

- BK - BLACK
BL - BLUE
BN - BROWN
BwR - BLACK W/RED STRIPE
GN - GREEN
GwY - GREEN W/YELLOW STRIPE
GY - GRAY
OR - ORANGE
RD - RED
WH - WHITE
YL - YELLOW

ELECTRICAL WIRING 17-1 WIRE TABLE FOR PANELBOARDS WIRE APPLICATION TYPE AND COLOR CODING FOR PANELBOARDS

CONTROL PANEL WIRE APPLICATION AND COLOR CODE REQUIREMENTS (DOES NOT APPLY TO RTU PANELS)

Table with 4 columns: APPLICATION, WIRE TYPE, SIZE, COLOR CODING. Defines wire types and color codes for control panels.

COLOR CODE ABBREVIATIONS

- BK - BLACK
BL - BLUE
BN - BROWN
BwR - BLACK W/RED STRIPE
GN - GREEN
GwY - GREEN W/YELLOW STRIPE
GY - GRAY
OR - ORANGE
RD - RED
WH - WHITE
YL - YELLOW

ELECTRICAL WIRING 17-2 WIRE TABLE FOR CONTROL PANELS WIRE APPLICATION TYPE AND COLOR CODING FOR PANELBOARDS



DEPARTMENT

REVISIONS:

DATE: INT.
DATE: EXT.
DESCRIPTION:
MAP:
PLAT SHEET:
SYSTEM SCHEMATIC:
STATION SCHEMATIC:

PLAT SHEET NO.:

SCALE:

N.T.S.

DRAWN BY:

T. PHAM

DESIGNED BY:

M. MACATIAG

CHECKED BY: DATE: 7/16/2021

APPROVED BY: DATE: 7/16/2021

REGISTERED PROFESSIONAL ENGINEER
NANDY MACATIAG
ELECTRICAL
STATE OF CALIFORNIA
No. E22351



TITLE:

MPS-SAN MATEO STATION 031
TANK AND BOOSTER PUMP
ELECTRICAL - HYDRAULIC ENCLOSURE

DISTRICT:

116-MPS

SAN MATEO

DATE:

5-21-2021

PROJECT ID.:

00118772

DRAWING NO.:

MPS-5599

SHT 1 OF 1

NOTES TO HYDRAULIC ENCLOSURE FABRICATOR

GROUNDING

THE PANEL FABRICATOR SHALL PROVIDE A GROUNDING POINT IN THE HYDRAULIC ENCLOSURE TIED TO A GROUNDING SCREW OR LUG.

HYDRAULIC AND ELECTRICAL EQUIPMENT

- 1. THE PANEL FABRICATOR SHALL PROVIDE ALL THE ELECTRICAL AND HYDRAULIC EQUIPMENT DESIGNATED IN THE LIST OF EQUIPMENT.
2. THE PANEL FABRICATOR SHALL PROVIDE ALL NECESSARY MOUNTING PLATES AND BRACKETS UPON WHICH TO MOUNT THE EQUIPMENT SHOWN.
3. ALL EQUIPMENT IN THE HYDRAULIC ENCLOSURE SHALL BE SECURED AS BEST AS PRACTICABLE TO PREVENT DISLODGE AND/OR VIBRATION.
4. THE PANEL FABRICATOR SHALL ASSURE THAT ALL HYDRAULIC CONNECTIONS WITHIN THE HYDRAULIC ENCLOSURE WILL NOT LEAK.
5. THE PANEL FABRICATOR SHALL DEMONSTRATE TO CWS THE LEAK INTEGRITY OF THE HYDRAULIC EQUIPMENT. A NOTIFICATION OF NO LESS THAN TWO BUSINESS DAYS PRIOR TO THIS DEMONSTRATION SHALL BE GIVEN TO CWS.
6. THE EXTERIOR COLOR SHALL BE ANSI 61 GRAY.
7. THE INTERIOR COLOR SHALL BE ANSI 61 GRAY.
8. THE PANEL SHALL BE MADE FROM GALVANIZED STEEL.
9. THE PANEL FABRICATOR SHALL PROVIDE AND INSTALL LIMIT SWITCH FOR FUTURE USE.
10. PRESSURE TRANSMITTER (PT3), SHOULD BE MOUNTED WITH "WIRING TERMINATION SIDE" TOWARDS FRONT OF HYDENC PANEL. THE HYDENC PANEL FABRICATOR SHALL PROVIDE A SPACER TO SECURELY MOUNT THE TRANSMITTERS TO THE BACKPANEL AND TO FACILITATE FIELD DISMOUNTING OF THE TRANSMITTERS.
11. DIMENSIONS SHOWN ARE APPROXIMATE. CONTRACTOR WILL DETERMINE EXACT DIMENSIONS.
12. ANY CHANGES TO DRAWING OR OF MATERIAL WILL REQUIRE APPROVAL FROM CALWATER PRIOR TO CHANGE. CONTRACTOR SHALL SUPPLY CALWATER AN AS-BUILT DRAWING OF ALL CHANGES.

WIRING

- 1. UNLESS OTHERWISE SPECIFIED, ALL WIRING IN THE HYDRAULIC ENCLOSURE SPECIFIED IN THE ELECTRICAL DRAWINGS IS TO BE DONE BY THE PANEL FABRICATOR.
2. ALL WIRING SHALL BE DONE IN ACCORDANCE WITH THE NATIONAL AND LOCAL ELECTRICAL CODES AND ALL OTHER APPLICABLE CODES.
3. ALL CONDUCTORS SO IDENTIFIED ON THE ELECTRICAL DRAWINGS SHALL BE LABELED WITH THEIR RESPECTIVE WIRE NUMBERS USING SELF-ADHESIVE LABELS. THESE LABELS SHALL BE SO AFFIXED AS TO HAVE THE NUMBER CLEARLY VISIBLE AND CAPABLE OF BEING READ FROM LEFT-TO-RIGHT OR FROM BOTTOM-TO-TOP.
4. ALL TERMINAL BLOCKS AND TERMINALS SHALL BE IDENTIFIED WITH LABELS AND NUMBERED ACCORDING TO THE ELECTRICAL DRAWINGS.
5. UNLESS OTHERWISE SPECIFIED HEREIN, ALL CONDUCTORS SHALL BE A MINIMUM OF #12 AWG, STRANDED COPPER WITH THHN OR THWN INSULATION.
6. UNLESS OTHERWISE SPECIFIED, ALL INSTRUMENT CABLES SHALL BE BELDEN #9341.
7. PROVIDE AN ADDITIONAL 15% TERMINALS AS SPARES FOR EVERY TYPE USED.
8. NO MORE THAN TWO WIRES TO LAND ON A TERMINAL.

FIELD YARD ADDRESS

UPON FINAL APPROVAL OF CWS, THE PANEL FABRICATOR SHALL DELIVER THE HYDRAULIC ENCLOSURE TO:

CALIFORNIA WATER SERVICE
BAYSHORE DISTRICT OFFICE
341 NORTH DELAWARE STREET
SAN MATEO, CA 94401-1727

NOTES TO ELECTRICAL INSTALLATION CONTRACTOR

GROUNDING

GROUNDING SHALL BE DONE IN ACCORDANCE WITH ALL APPLICABLE NATIONAL AND LOCAL ELECTRICAL CODES AND THE CWS GROUNDING DETAILS CONTAINED HEREIN.

CONDUITS

- 1. ALL CONDUITS SHALL BE INSTALLED PER CALWATER DRAWING MPS-5599
2. ELECTRICAL CONDUITS INSTALLED INTO HYDRAULIC ENCLOSURE BY THE ELECTRICAL INSTALLATION CONTRACTOR SHALL BE DONE ONLY IN THE AREAS INDICATED.
3. ALL ELECTRICAL CONDUITS ENTERING HYDRAULIC ENCLOSURE SHALL USE MYERS HUBS.
4. THE ELECTRICAL INSTALLATION CONTRACTOR SHALL PROVIDE A CORD GRIP FITTING IN THE INTERIOR OF HYDRAULIC ENCLOSURE FOR THE PRESSURE LINE.

WIRING

- 1. UNLESS OTHERWISE SPECIFIED, ALL WIRING TO THE TERMINAL BLOCK TB4 IN HYDRAULIC ENCLOSURE SHALL BE DONE IN THE FIELD BY THE ELECTRICAL INSTALLATION CONTRACTOR.
2. ALL WIRING SHALL BE DONE IN ACCORDANCE WITH THE NATIONAL AND LOCAL ELECTRICAL CODES AND ALL OTHER APPLICABLE CODES.
3. ALL CONDUCTORS SO IDENTIFIED ON THE ELECTRICAL DRAWINGS SHALL BE LABELED WITH THEIR RESPECTIVE WIRE NUMBERS USING SELF-ADHESIVE LABELS. THESE LABELS SHALL BE SO AFFIXED AS TO HAVE THE NUMBER CLEARLY VISIBLE AND CAPABLE OF BEING READ FROM LEFT-TO-RIGHT OR FROM BOTTOM-TO-TOP.
4. BEFORE ENERGIZING, ALL TERMINALS IN HYDRAULIC ENCLOSURE SHALL BE CHECKED AND TIGHTENED IN THE FIELD BY THE ELECTRICAL INSTALLATION CONTRACTOR. TIGHTENING OF TERMINATIONS SHALL BE ACCORDING TO THE TERMINAL MANUFACTURER'S RECOMMENDED TORQUE RANGE AND SHALL NOT EXCEED THE MAXIMUM TORQUE SO SPECIFIED.

FIELD YARD ADDRESS

CALIFORNIA WATER SERVICE
BAYSHORE DISTRICT OFFICE
341 NORTH DELAWARE STREET
SAN MATEO, CA 94401-1727


HYDENC EQUIPMENT LIST

Table with columns: Item #, Item ID, Qty, Description, Hydenc Fabricator (Supply/Install), CWS (Supply/Install), Installation Contractor (Supply/Install), Item #. Lists various electrical and hydraulic components.

HYDENC NAMEPLATE LIST

(FABRICATOR TO INSTALL NAMEPLATES SHOWN)

Table with columns: Item, Description, Size, Notes. Lists nameplates for components like receptacles, enclosures, transmitters, heaters, etc.







## **APPENDIX B**

### **Impervious Surface and Drainage Exhibit**




**LEA & BRAZE ENGINEERING, INC.**  
 CIVIL ENGINEERS • LAND SURVEYORS  
 SACRAMENTO REGION  
 BAY AREA REGION  
 SACRAMENTO COUNTY, CALIFORNIA 95661  
 HAYWARD, CALIFORNIA 94545  
 (P) (510) 887-4086 (F) (916) 966-1338  
 (F) (510) 887-3019 (F) (916) 797-7363  
 WWW.LEA-BRAZE.COM


**ASCENSION HEIGHTS  
 SUBDIVISION  
 SAN MATEO, CALIFORNIA**  
 (UNINCORPORATED) SAN MATEO COUNTY

**IMPERVIOUS SURFACE  
 AND DRAINAGE EXHIBIT**


REVISIONS	BY
JOB NO:	2161285
DATE:	02-02-23
SCALE:	1" = 20'
DESIGN BY:	RC
DRAWN BY:	ATL
SHEET NO:	



**PRE-DEVELOPMENT**



**POST-DEVELOPMENT**



PEAK FLOW SUMMARY			
	PRE-DEVELOPMENT	POST-DEVELOPMENT	CHANGE IN RUNOFF
Q <sub>10</sub> PEAK FLOW (UNMITIGATED)	0.43 CFS	0.45 CFS	+0.02 CFS INCREASE
Q <sub>10</sub> PEAK FLOW (MITIGATED)	0.43 CFS	0.34 CFS	-0.09 CFS NET DECREASE

IMPERVIOUS SURFACE INFORMATION				
TOTAL SITE AREA =	22,500 SQUARE FEET = 0.517 ACRES			
IMPERVIOUS AREAS	EXISTING (sq-ft.)	REMOVED (sq-ft.)	NEW (sq-ft.)	PROPOSED (sq-ft.)
WATER TANK AND CONCRETE PADS	3,244	752	1,231	3,723
<b>TOTAL IMPERVIOUS AREA</b>	<b>3,244</b>	<b>752</b>	<b>1,231</b>	<b>3,723</b>
<b>NET CHANGE IN IMPERVIOUS AREA</b>	<b>+479 SQFT. NET INCREASE</b>			

**10-Year Storm - Runoff Analysis** Rainfall Duration=10 min, Inten=2.10 in/hr  
 Prepared by Lea & Braze Engineering, Inc. Printed 1/12/2023  
 HydroCAD® 10.10-3a s/n 02830 © 2020 HydroCAD Software Solutions LLC


**Summary for Subcatchment 1S: Pre-Development Runoff**

Runoff = 0.43 cfs @ 0.17 hrs, Volume= 256 cf, Depth= 0.14"

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-2.00 hrs, dt= 0.00 hrs  
 Rainfall Duration=10 min, Inten=2.10 in/hr

Area (sf)	C	Description
3,244	0.95	Pre-development impervious area
19,256	0.30	Pre-development pervious area
22,500	0.39	Weighted Average
19,256		85.58% Pervious Area
3,244		14.42% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed Tc



**10-Year Storm - Runoff Analysis** Rainfall Duration=10 min, Inten=2.10 in/hr  
 Prepared by Lea & Braze Engineering, Inc. Printed 1/12/2023  
 HydroCAD® 10.10-3a s/n 02830 © 2020 HydroCAD Software Solutions LLC


**Summary for Subcatchment 2S: Post-Development Runoff**

Runoff = 0.45 cfs @ 0.17 hrs, Volume= 269 cf, Depth= 0.14"

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-2.00 hrs, dt= 0.00 hrs  
 Rainfall Duration=10 min, Inten=2.10 in/hr

Area (sf)	C	Description
3,723	0.95	Post-development impervious area
18,777	0.30	Post-development pervious area
22,500	0.41	Weighted Average
18,777		83.45% Pervious Area
3,723		16.55% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed Tc



**10-Year Storm - Runoff Analysis** Rainfall Duration=10 min, Inten=2.10 in/hr  
 Prepared by Lea & Braze Engineering, Inc. Printed 1/12/2023  
 HydroCAD® 10.10-3a s/n 02830 © 2020 HydroCAD Software Solutions LLC


**Summary for Subcatchment 3S: Area of Collection**

Runoff = 0.13 cfs @ 0.17 hrs, Volume= 81 cf, Depth= 0.33"

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-2.00 hrs, dt= 0.00 hrs  
 Rainfall Duration=10 min, Inten=2.10 in/hr

Area (sf)	C	Description
2,907	0.95	Collected impervious area
0	0.30	Collected pervious area
2,907	0.95	Weighted Average
2,907		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Assumed Tc



**10-Year Storm - Runoff Analysis** Rainfall Duration=10 min, Inten=2.10 in/hr  
 Prepared by Lea & Braze Engineering, Inc. Printed 1/12/2023  
 HydroCAD® 10.10-3a s/n 02830 © 2020 HydroCAD Software Solutions LLC

**Summary for Pond 4P: Treatment Planter**

Inflow Area = 2,907 sf, 100.00% Impervious, Inflow Depth = 0.33"  
 Inflow = 0.13 cfs @ 0.17 hrs, Volume= 81 cf  
 Outflow = 0.02 cfs @ 0.05 hrs, Volume= 81 cf, Atten= 88%, Lag= 0.0 min  
 Primary = 0.02 cfs @ 0.05 hrs, Volume= 81 cf  
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf

Routing by Dyn-Stor-Ind method, Time Span= 0.00-2.00 hrs, dt= 0.00 hrs  
 Peak Elev= 100.44' @ 0.31 hrs Surf. Area= 140 sf Storage= 62 cf


Plug-Flow detention time= 32.0 min calculated for 81 cf (100% of inflow)  
 Center-of-Mass det. time= 32.0 min ( 42.0 - 10.0 )

Volume	Invert	Avail. Storage	Storage Description
#1	100.00'	105 cf	7.00'W x 20.00'L x 0.75'H Prismatic

Device	Routing	Invert	Outlet Devices
#1	Primary	100.00'	5.000 in/hr Exfiltration over Surface area
#2	Secondary	100.50'	12.00" x 12.00" Horiz. Orifice/Gate C= 0.600 Limited to weir flow at low heads

**Primary OutFlow** Max=0.02 cfs @ 0.05 hrs HW=100.01' (Free Discharge)  
 1=Exfiltration (Exfiltration Controls 0.02 cfs)

**Secondary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=100.00' (Free Discharge)  
 2=Orifice/Gate ( Controls 0.00 cfs)





## **APPENDIX C**

### **Drainage and Treatment Plan**

# CALWATER TANK - DRAINAGE & TREATMENT PLAN BEL AIRE ROAD SAN MATEO, CALIFORNIA




**LEA & BRAZE ENGINEERING, INC.**  
 CIVIL ENGINEERS • LAND SURVEYORS  
 SACRAMENTO REGION  
 12500 BUCKLEWAY WEST, SUITE # 300  
 ROSELAND, CALIFORNIA 94661  
 HAWAII REGION  
 2000 W. WILSON AVENUE, SUITE 200  
 HONOLULU, HAWAII 96819  
 (P) (510) 887-4086 (F) (916) 966-1338  
 (P) (510) 887-3019 (F) (916) 967-7363  
 WWW.LEABRAZE.COM

## LEGEND

EXISTING	PROPOSED	DESCRIPTION
----	----	BOUNDARY
----	----	PROPERTY LINE
----	----	RETAINING WALL
----	----	LANDSCAPE RETAINING WALL
---	---	RAINWATER TIGHTLINE
---	---	SUBDRAIN LINE
---	---	TIGHTLINE
---	---	STORM DRAIN LINE
---	---	SANITARY SEWER LINE
---	---	WATER LINE
---	---	GAS LINE
---	---	PRESSURE LINE
---	---	JOINT TRENCH
---	---	SET BACK LINE
---	---	CONCRETE VALLEY GUTTER
---	---	EARTHEN SWALE
CB	CB	CATCH BASIN
JB	JB	JUNCTION BOX
Ad	Ad	AREA DRAIN
SDMH	SDMH	CURB INLET
SSMH	SSMH	STORM DRAIN MANHOLE
222.57 INV	222.57 INV	FIRE HYDRANT
200	200	SANITARY SEWER MANHOLE
200	200	STREET SIGN
200	200	SPOT ELEVATION
200	200	FLOW DIRECTION
200	200	DEMOLISH/REMOVE
200	200	BENCHMARK
200	200	CONTOURS
200	200	TREE TO BE REMOVED

## ABBREVIATIONS

AB	AGGREGATE BASE	MAX	MAXIMUM
AC	ASPHALT CONCRETE	MH	MANHOLE
ACC	ACCESSIBLE	MIN	MINIMUM
AD	AREA DRAIN	MON.	MONUMENT
BC	BEGINNING OF CURVE	MRO	METERED RELEASE OUTLET
B & D	BEARING & DISTANCE	(N)	NEW
BM	BENCHMARK	NO.	NUMBER
BIO	BIORETENTION AREA	NTS	NOT TO SCALE
BUB	BUBBLER BOX	O.C.	ON CENTER
BW/FG	BOTTOM OF WALL/FINISH GRADE	O/P	OVER
CB	CATCH BASIN	(PA)	PLANTING AREA
C & G	CURB AND GUTTER	PE	PEDESTRIAN
CPP	CORRUGATED PLASTIC PIPE (SMOOTH INTERIOR)	PIV	POST INDICATOR VALVE
CO	CLEANOUT	PSS	PUBLIC SERVICES EASEMENT
COTG	CLEANOUT TO GRADE	R	PROPERTY LINE
CONC	CONCRETE	PP	POWER POLE
CONST	CONSTRUCT or -TION	PUE	PUBLIC UTILITY EASEMENT
CONC COR	CONCRETE CORNER	PVC	POLYVINYL CHLORIDE
CY	CUBIC YARD	R	RADIUS
D	DIAMETER	RCP	REINFORCED CONCRETE PIPE
DI	DROP INLET	RIM	RIM ELEVATION
DIP	DUCTILE IRON PIPE	RW	RAINWATER
EA	EACH	R/W	RIGHT OF WAY
EC	END OF CURVE	S	SLOPE
EG	EXISTING GRADE	S.A.D.	SEE ARCHITECTURAL DRAWINGS
EL	ELEVATIONS	SAN	SANITARY
EP	EDGE OF PAVEMENT	SD	STORM DRAIN
EQ	EQUIPMENT	SDMH	STORM DRAIN MANHOLE
EW	EACH WAY	SHT	SHEET
(E)	EXISTING	SI	STREET INLET
FC	FACE OF CURB	S.L.D.	SEE LANDSCAPE DRAWINGS
FF	FINISHED FLOOR	SPEC	SPECIFICATION
FG	FINISHED GRADE	SS	SANITARY SEWER
FH	FIRE HYDRANT	SSCO	SANITARY SEWER CLEANOUT
FL	FLOW LINE	SSMH	SANITARY SEWER MANHOLE
FS	FINISHED SURFACE	ST	STREET
G	GAS	STA	STATION
GA	GAGE OR GAUGE	STD	STANDARD
GB	GRADE BREAK	STRUCT	STRUCTURAL
HDPE	HIGH DENSITY CORRUGATED POLYETHYLENE PIPE	T	TELEPHONE
HORIZ	HORIZONTAL	TC	TOP OF CURB
HI PT	HIGH POINT	TEMP	TEMPORARY
H&T	HUB & TACK	TOW	TOP OF WALL
ID	INSIDE DIAMETER	TP	TOP OF PAVEMENT
INV	INVERT ELEVATION	TW/FG	TOP OF WALL/FINISH GRADE
JB	JUNCTION BOX	TYP	TYPICAL
JT	JOINT TRENCH	VC	VERTICAL CURVE
JP	JOINT UTILITY POLE	VCP	VITRIFIED CLAY PIPE
L	LENGTH	VERT	VERTICAL
LNDR	LANDING	W/	WITH
LF	LINEAR FEET	WL	WATER LINE
		WM	WATER METER
		WWF	WELDED WIRE FABRIC



KEY MAP

1" = 100'

## NOTES

- ALL DISTANCES AND DIMENSIONS ARE IN FEET AND DECIMALS.
- UNDERGROUND UTILITY LOCATION IS BASED ON SURFACE EVIDENCE.
- BUILDING FOOTPRINTS ARE SHOWN TO FINISHED MATERIAL (STUCCO/SIDING) AT GROUND LEVEL.
- FINISH FLOOR ELEVATIONS ARE TAKEN AT DOOR THRESHOLD (EXTERIOR).

## EASEMENT NOTE


A CURRENT TITLE REPORT FOR THE SUBJECT PROPERTY HAS NOT BEEN EXAMINED BY LEA & BRAZE ENGINEERING, INC. EASEMENTS OF RECORD MAY EXIST THAT ARE NOT SHOWN ON THIS MAP. EASEMENTS SHOWN PER ADJOINING SUBDIVISIONS.

## SITE BENCHMARK

SURVEY CONTROL POINT  
MAG AND SHINER SET IN ASPHALT  
ELEVATION = 587.30'  
(ASSUMED)

## PROJECT INFORMATION

AREA:	0.52±ACRES
ASSESSOR'S PARCEL NOS:	041-111-020
<b>UTILITY SERVICES:</b>	
STORM DRAIN:	SAN MATEO COUNTY
SANITARY SEWER:	SAN MATEO COUNTY
WATER:	CALIFORNIA WATER SERVICES
FIRE:	SAN MATEO COUNTY FIRE SERVICE
CABLE:	COMCAST
GAS & ELECTRICAL:	PACIFIC GAS & ELECTRIC (PG&E)
TELEPHONE:	AT&T



VICINITY MAP  
NO SCALE

## OWNER'S INFORMATION

OWNER:  
CALIFORNIA WATER SERVICES  
408-367-8394

## REFERENCES

- THIS GRADING AND DRAINAGE PLAN IS SUPPLEMENTAL TO:
- TOPOGRAPHIC SURVEY BY LEA & BRAZE ENGINEERING, INC. ENTITLED: "TOPOGRAPHIC SURVEY" BEL AIRE DRIVE SAN MATEO, CA JOB#2161284 DATED: 9-20-17
  - SOIL REPORT BY MICHELUCCI & ASSOCIATES, INC. ENTITLED: "GEOTECHNICAL & ENGINEERING GEOLOGIC INVESTIGATION" PROPOSED ASCENSION HEIGHTS SUBDIVISION SAN MATEO COUNTY, CA JOB# 01-3186 DATE: DECEMBER 16, 2002 REVISED DATE: DECEMBER 5, 2013 SUPPLEMENT TO REPORT: AUGUST 24, 2018
  - SITE PLAN BY CALIFORNIA WATER SERVICE ENTITLED: "STATION 031 - ASCENSION DR & BEL AIR RD INSTALL TANK AND BOOSTER PUMP" BEL AIRE DRIVE SAN MATEO, CA DATED: 04-07-21

THE CONTRACTOR SHALL REFER TO THE ABOVE NOTED SURVEY AND PLAN, AND SHALL VERIFY BOTH EXISTING AND PROPOSED ITEMS ACCORDING TO THEM.

**CONTRACTOR COURTESY NOTE:**  
CONTRACTOR TO PROVIDE 72-HOUR COURTESY NOTICE FOR NOISE AND DUST (INCLUDING POINT OF CONTACT) TO COMMUNITY PRIOR TO COMMENCEMENT OF OPERATIONS.

**NOTE:**  
**FOR CONSTRUCTION STAKING SCHEDULING OR QUOTATIONS PLEASE CONTACT ALEX ABAYA AT LEA & BRAZE ENGINEERING (510)887-4086 EXT 116.**  
aabaya@leabraze.com

## SHEET INDEX

DTP-1.0	TITLE SHEET
DTP-2.0	DRAINAGE & TREATMENT PLAN
DTP-3.0	DETAILS
DTP-4.0	SPECIFICATIONS
ER-1	EROSION CONTROL PLAN
ER-2	EROSION CONTROL DETAILS
BMP	BEST MANAGEMENT PRACTICES

**CALWATER TANK  
DRAINAGE & TREATMENT PLAN  
SAN MATEO, CALIFORNIA**  
(UNINCORPORATED) SAN MATEO COUNTY

TITLE SHEET

REVISIONS	BY
JOB NO:	2161285
DATE:	02-01-23
SCALE:	AS NOTED
DESIGN BY:	AH
DRAWN BY:	MGF
SHEET NO:	



**DTP-1.0**



**LEA & BRAZE ENGINEERING, INC.**  
 CIVIL ENGINEERS • LAND SURVEYORS  
 SACRAMENTO REGION  
 1500 S. BUCKLEY WEST  
 HAYWARD, CALIFORNIA 94545  
 (P) (510) 887-4086 (F) (916) 966-1338  
 (F) (510) 887-3019 (F) (916) 797-1363  
 WWW.LEABRAZE.COM

**CALWATER TANK  
 DRAINAGE & TREATMENT PLAN  
 SAN MATEO, CALIFORNIA**  
 (UNINCORPORATED) SAN MATEO COUNTY

**DRAINAGE &  
 TREATMENT PLAN**



- STORM DRAIN KEYNOTES 1 TO 6**
- 1. INSTALL (N) ON-SITE STORM DRAIN SYSTEM. USE MINIMUM 6" HDPE (ADS N-12) W/ SMOOTH INTERIOR WALLS. MAINTAIN 24" MINIMUM COVER AND SLOPED AT 1% MINIMUM AT ALL TIMES UNLESS OTHERWISE NOTED. PROVIDE CLEANOUT TO GRADE AT MAJOR CHANGES IN DIRECTION. AVOID USING 90° BENDS AND INSTEAD USE (2) 45° BENDS AND WYE CONNECTIONS.
  - 2. INSTALL (N) SUBDRAIN. USE PERFORATED 4" PVC (SDR-35) WITH HOLES DOWN AND SLOPED AT 1% MINIMUM SURROUND WITH 3/4" DRAIN ROCK WRAPPED IN FILTER FABRIC (MIRAFI 140N). MIRADRAIN OR OTHER LEA & BRAZE PREAPPROVED DRAINAGE SYSTEM MAY ALSO BE USED. AVOID USING 90° BENDS AND INSTEAD USE (2) 45° BENDS AND WYE CONNECTIONS. PROVIDE CLEANOUT TO GRADE AT MAJOR CHANGES IN DIRECTION AND AT 100' MAXIMUM INTERVALS. SUBDRAIN SHALL REMAIN A DEDICATED SEPARATE SYSTEM UNTIL IT CONNECTS TO STORM DRAIN SYSTEM OR OUTFALL AS SHOWN.
  - 3. CONSTRUCT (N) DRAINAGE DEPRESSION SWALE SLOPED AT 1% MINIMUM TOWARDS POSITIVE OUTFALL. SEE DETAIL 2 ON SHEET DTP-3.0.
  - 4. INSTALL (N) 'CHRISTY V-12' CATCH BASIN W/ CONCRETE BOTTOM FLUSH W/ LOWEST OUTGOING INVERT. PLACE BOX ON 6" CLASS 2 AGGREGATE BASE MATERIAL. SEE DETAIL 1 ON SHEET DTP-3.0.
  - 5. INSTALL (N) BIO-RETENTION POND PER SAN MATEO COUNTY C-3/C-6 MANUAL. SEE DETAIL 3 ON SHEET DTP-3.0.
  - 6. INSTALL (N) PIPE CROSSING PROTECTION PER DETAIL 4 ON SHEET DTP-3.0.


**NOTE:**  
 FOR CONSTRUCTION STAKING  
 SCHEDULING OR QUOTATIONS  
 PLEASE CONTACT ALEX ABBAYA  
 AT LEA & BRAZE ENGINEERING  
 (510) 887-4086 EXT 116.  
 aabaya@leabraze.com

**\* BUILDING PAD NOTE:**  
 ADJUST PAD LEVEL AS  
 REQUIRED. REFER TO  
 STRUCTURAL SECTIONS  
 FOR SLAB SECTION OR  
 CRAWL SPACE DEPTH  
 TO ESTABLISH PAD  
 LEVEL.




REVISIONS	BY


JOB NO: 2161285  
 DATE: 02-01-23  
 SCALE: AS NOTED  
 DESIGN BY: AH  
 DRAWN BY: MCF  
 SHEET NO:  
**DTP-2**  
 01 OF 7 SHEETS




1 CATCH BASIN  
DTP-3.0 NTS




4 PIPE CROSSING  
DTP-3.0 NTS



2 DRAINAGE DEPRESSION SWALE DETAIL  
DTP-3.0 NTS



3 BIO-TREATMENT AREA  
DTP-3.0 NTS



**LEA & BRAZE ENGINEERING, INC.**  
CIVIL ENGINEERS • LAND SURVEYORS  
SACRAMENTO REGION  
1000 J STREET, SUITE 300  
ROSELAND, CALIFORNIA 94661  
(P) (916) 966-1338  
(F) (916) 966-1338  
WWW.LEABRAZE.COM

CALWATER TANK  
DRAINAGE & TREATMENT PLAN  
SAN MATEO, CALIFORNIA  
(UNINCORPORATED) SAN MATEO COUNTY

DETAILS

REVISIONS	BY

JOB NO: 2161285  
DATE: 02-01-23  
SCALE: NTS  
DESIGN BY: AH  
DRAWN BY: MCF  
SHEET NO:

**DTP-3.0**

3 OF 7 SHEETS





### PURPOSE:

THE PURPOSE OF THIS PLAN IS TO STABILIZE THE SITE TO PREVENT EROSION OF GRADED AREAS AND TO PREVENT SEDIMENTATION FROM LEAVING THE CONSTRUCTION AREA AND AFFECTING NEIGHBORING SITES, NATURAL AREAS, PUBLIC FACILITIES OR ANY OTHER AREA THAT MIGHT BE AFFECTED BY SEDIMENTATION. ALL MEASURES SHOWN ON THIS PLAN SHOULD BE CONSIDERED THE MINIMUM REQUIREMENTS NECESSARY. SHOULD FIELD CONDITIONS DICTATE ADDITIONAL MEASURES, SUCH MEASURES SHALL BE PER CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL AND THE CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION. LEA & BRAZE ENGINEERING SHOULD BE NOTIFIED IMMEDIATELY SHOULD CONDITIONS CHANGE.

### EROSION CONTROL NOTES:

- IT SHALL BE THE OWNER'S/CONTRACTOR'S RESPONSIBILITY TO MAINTAIN CONTROL OF THE ENTIRE CONSTRUCTION OPERATION AND TO KEEP THE ENTIRE SITE IN COMPLIANCE WITH THIS EROSION CONTROL PLAN.
- THE INTENTION OF THIS PLAN IS FOR INTERIM EROSION AND SEDIMENT CONTROL ONLY. ALL EROSION CONTROL MEASURES SHALL CONFORM TO CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL, THE CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION, AND THE LOCAL GOVERNING AGENCY FOR THIS PROJECT.
- OWNER/CONTRACTOR SHALL BE RESPONSIBLE FOR MONITORING EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO, DURING, AND AFTER STORM EVENTS. PERSON IN CHARGE OF MAINTAINING EROSION CONTROL MEASURES SHOULD WATCH LOCAL WEATHER REPORTS AND ACT APPROPRIATELY TO MAKE SURE ALL NECESSARY MEASURES ARE IN PLACE.
- SANITARY FACILITIES SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
- DURING THE RAINY SEASON, ALL PAVED AREAS SHALL BE KEPT CLEAR OF EARTH MATERIAL AND DEBRIS. THE SITE SHALL BE MAINTAINED SO AS TO MINIMIZE SEDIMENTATION RUNOFF TO ANY STORM DRAINAGE SYSTEM, INCLUDING EXISTING DRAINAGE SWALES AND WATERCOURSES.
- CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION AND WATER POLLUTION WILL BE MINIMIZED. COMPLIANCE WITH FEDERAL, STATE AND LOCAL LAWS CONCERNING POLLUTION SHALL BE MAINTAINED AT ALL TIMES.
- CONTRACTOR SHALL PROVIDE DUST CONTROL AS REQUIRED BY THE APPROPRIATE FEDERAL, STATE AND LOCAL AGENCY REQUIREMENTS.
- ALL MATERIALS NECESSARY FOR THE APPROVED EROSION CONTROL MEASURES SHALL BE IN PLACE BY OCTOBER 15TH.
- EROSION CONTROL SYSTEMS SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE RAINY SEASON, OR FROM OCTOBER 15TH THROUGH APRIL 15TH, WHICHEVER IS LONGER.
- IN THE EVENT OF RAIN, ALL GRADING WORK IS TO CEASE IMMEDIATELY AND THE SITE IS TO BE SEALED IN ACCORDANCE WITH THE APPROVAL EROSION CONTROL MEASURES AND APPROVED EROSION CONTROL PLAN.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR CHECKING AND REPAIRING EROSION CONTROL SYSTEMS AFTER EACH STORM.
- ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED BY LOCAL JURISDICTION'S ENGINEERING DEPARTMENT OR BUILDING OFFICIALS.
- MEASURES SHALL BE TAKEN TO COLLECT OR CLEAN ANY ACCUMULATION OR DEPOSIT OF DIRT, MUD, SAND, ROCKS, GRAVEL OR DEBRIS ON THE SURFACE OF ANY STREET, ALLEY OR PUBLIC PLACE OR IN ANY PUBLIC STORM DRAIN SYSTEMS. THE REMOVAL OF AFORESAID SHALL BE DONE BY STREET SWEEPING OR HAND SWEEPING. WATER SHALL NOT BE USED TO WASH SEDIMENTS INTO PUBLIC OR PRIVATE DRAINAGE FACILITIES.
- EROSION CONTROL MEASURES SHALL BE ON-SITE FROM SEPTEMBER 15TH THRU APRIL 15TH.
- ALL EROSION CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED THROUGHOUT THE RAINY SEASON OR FROM OCTOBER 15TH THROUGH APRIL 15TH, WHICHEVER IS GREATER.
- PLANS SHALL BE DESIGNED TO MEET C3 REQUIREMENTS OF THE MUNICIPAL STORMWATER REGIONAL PERMIT("MRP") NPDES PERMIT CAS 612008.
- THE CONTRACTOR TO NPDES (NATIONAL POLLUTION DISCHARGE ELIMINATION SYSTEM) BEST MANAGEMENT PRACTICES (BMP) FOR SEDIMENTATION PREVENTION AND EROSION CONTROL TO PREVENT DELETERIOUS MATERIALS OR POLLUTANTS FROM ENTERING THE TOWN OR COUNTY STORM DRAIN SYSTEMS.
- THE CONTRACTOR MUST INSTALL ALL EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO THE INCEPTION OF ANY WORK ONSITE AND MAINTAIN THE MEASURES UNTIL THE COMPLETION OF ALL LANDSCAPING.
- THE CONTRACTOR SHALL MAINTAIN ADJACENT STREETS IN A NEAT, CLEAN DUST FREE AND SANITARY CONDITION AT ALL TIMES AND TO THE SATISFACTION OF THE TOWN INSPECTOR. THE ADJACENT STREET SHALL AT ALL TIMES BE KEPT CLEAN OF DEBRIS, WITH DUST AND OTHER NUISANCE BEING CONTROLLED AT ALL TIMES. THE CONTRACTOR BE RESPONSIBLE FOR ANY CLEAN UP ON ADJACENT STREETS AFFECTED BY THE BY THEIR CONSTRUCTION. METHOD OF STREET CLEANING SHALL BE BY DRY SWEEPING OF ALL PAVED AREAS. NO STOCKPILING OF BUILDING MATERIALS WITHIN THE TOWN RIGHT-OF-WAY.
- SEDIMENTS AND OTHER MATERIALS SHALL NOT BE TRACKED FROM THE SITE BY VEHICLE TRAFFIC. THE CONTRACTOR SHALL INSTALL A STABILIZED CONSTRUCTION ENTRANCE PRIOR TO THE INSPECTION OF ANY WORK ONSITE AND MAINTAIN IT FOR THE DURATION OF THE CONSTRUCTION PROCESS SO AS TO NOT INHIBIT SEDIMENTS FROM BEING DEPOSITED INTO THE PUBLIC RIGHT-OF-WAY UNTIL THE COMPLETION OF ALL LANDSCAPING.
- THE CONTRACTOR SHALL PROTECT DOWN SLOPE DRAINAGE COURSES, STREAMS AND STORM DRAINS WITH ROCK FILLED SAND BAGS, TEMPORARY SWALES, SILT FENCES, AND EARTH PERMS IN CONJUNCTION OF ALL LANDSCAPING.
- STOCKPILED MATERIALS SHALL BE COVERED WITH VISQUEEN OR A TARPULIN UNTIL THE MATERIAL IS REMOVED FROM THE SITE. ANY REMAINING BARE SOIL THAT EXISTS AFTER THE STOCKPILE HAS BEEN REMOVED SHALL BE COVERED UNTIL A NATURAL GROUND COVER IS ESTABLISHED OR IT IS SEEDED OR PLANTED TO PROVIDE GROUND COVER PRIOR TO THE FALL RAINY SEASON.
- EXCESS OR WASTE CONCRETE MUST NOT BE WASHED INTO THE PUBLIC RIGHT-OF-WAY OR ANY OTHER DRAINAGE SYSTEM. PROVISIONS SHALL BE MADE TO RETAIN CONCRETE WASTES ON SITE UNTIL THEY CAN BE DISPOSED OF AS SOLID WASTE.
- TRASH AND CONSTRUCTION RELATED SOLID WASTES MUST BE DEPOSITED INTO A COVERED RECEPTACLE TO PREVENT CONTAMINATION AND DISPERSAL BY WIND

### EROSION CONTROL NOTES CONTINUED:

- FUELS, OILS, SOLVENTS AND OTHER TOXIC MATERIALS MUST BE STORED IN ACCORDANCE WITH THEIR LISTING AND ARE NOT TO CONTAMINATE THE SOIL AND SURFACE WATERS. ALL APPROVED STORAGE CONTAINERS ARE TO BE PROTECTED FROM THE WEATHER. SPILLS MUST BE CLEANED UP IMMEDIATELY AND DISPOSED OF IN A PROPER MANNER. SPILLS MUST NOT BE WASHED INTO THE DRAINAGE SYSTEM,
- DUST CONTROL SHALL BE DONE BY WATERING AND AS OFTEN AS REQUIRED BY THE TOWN INSPECTOR.
- SILT FENCE(S) AND/OR FIBER ROLL(S) SHALL BE INSTALLED PRIOR TO SEPTEMBER 15TH AND SHALL REMAIN IN PLACE UNTIL THE LANDSCAPING GROUND COVER IS INSTALLED. CONTRACTOR SHALL CONTINUOUSLY MONITOR THESE MEASURES, FOLLOWING AND DURING ALL RAIN EVENTS, TO PUBLIC OWNED FACILITIES.

### EROSION CONTROL MEASURES:


- THE FACILITIES SHOWN ON THIS PLAN ARE DESIGNED TO CONTROL EROSION AND SEDIMENT DURING THE RAINY SEASON, OCTOBER 15TH TO APRIL 15. EROSION CONTROL FACILITIES SHALL BE IN PLACE PRIOR TO OCTOBER 15TH OF ANY YEAR. GRADING OPERATIONS DURING THE RAINY SEASON WHICH LEAVE DENUDED SLOPES SHALL BE PROTECTED WITH EROSION CONTROL MEASURES IMMEDIATELY FOLLOWING GRADING ON THE SLOPES.
- SITE CONDITIONS AT TIME OF PLACEMENT OF EROSION CONTROL MEASURES WILL VARY. APPROPRIATE ACTION INCLUDING TEMPORARY SWALES, INLETS, HYDROSEEDING, STRAW BALES, ROCK SACKS, ETC. SHALL BE TAKEN TO PREVENT EROSION AND SEDIMENTATION FROM LEAVING SITE. EROSION CONTROL MEASURES SHALL BE ADJUSTED AS THE CONDITIONS CHANGE AND THE NEED OF CONSTRUCTION SHIFT.
- CONSTRUCTION ENTRANCES SHALL BE INSTALLED PRIOR TO COMMENCEMENT OF GRADING. ALL CONSTRUCTION TRAFFIC ENTERING ONTO THE PAVED ROADS MUST CROSS THE STABILIZED CONSTRUCTION ENTRANCES. CONTRACTOR SHALL MAINTAIN STABILIZED ENTRANCE AT EACH VEHICLE ACCESS POINT TO EXISTING PAVED STREETS. ANY MUD OR DEBRIS TRACKED ONTO PUBLIC STREETS SHALL BE REMOVED DAILY AND AS REQUIRED BY THE GOVERNING AGENCY.
- EXPOSED SLOPES THAT ARE NOT VEGETATED SHALL BE HYDROSEEDED. IF HYDROSEEDING IS NOT USED OR IS NOT EFFECTIVE BY OCTOBER 15, THEN OTHER IMMEDIATE METHODS SHALL BE IMPLEMENTED, SUCH AS EROSION CONTROL BLANKETS, OR A THREE-STEP APPLICATION OF 1) SEED, MULCH, FERTILIZER 2) BLOWN STRAW 3) TACKIFIER AND MULCH. HYDROSEEDING SHALL BE IN ACCORDANCE WITH THE PROVISIONS OF SECTION 20" EROSION CONTROL AND HIGHWAY PLANTING" OF THE STANDARD SPECIFICATION OF THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION, AS LAST REVISED. REFER TO THE EROSION CONTROL SECTION OF THE GRADING SPECIFICATIONS THAT ARE A PART OF THIS PLAN SET FOR FURTHER INFORMATION.
- INLET PROTECTION SHALL BE INSTALLED AT OPEN INLETS TO PREVENT SEDIMENT FROM ENTERING THE STORM DRAIN SYSTEM. INLETS NOT USED IN CONJUNCTION WITH EROSION CONTROL ARE TO BE BLOCKED TO PREVENT ENTRY OF SEDIMENT. MINIMUM INLET PROTECTION SHALL CONSIST OF A ROCK SACKS OR AS SHOWN ON THIS PLAN
- THIS EROSION AND SEDIMENT CONTROL PLAN MAY NOT COVER ALL THE SITUATIONS THAT MAY ARISE DURING CONSTRUCTION DUE TO UNANTICIPATED FIELD CONDITIONS. VARIATIONS AND ADDITIONS MAY BE MADE TO THIS PLAN IN THE FIELD. A REPRESENTATIVE OF LEA & BRAZE ENGINEERING SHALL PERFORM A FIELD REVIEW AND MAKE RECOMMENDATIONS AS NEEDED. CONTRACTOR IS RESPONSIBLE TO NOTIFY LEA & BRAZE ENGINEERING AND THE GOVERNING AGENCY OF ANY CHANGES.
- THE EROSION CONTROL MEASURES SHALL CONFORM TO THE LOCAL JURISDICTION'S STANDARDS AND THE APPROVAL OF THE LOCAL JURISDICTION'S ENGINEERING DEPARTMENT.
- STRAW ROLLS SHALL BE PLACED AT THE TOE OF SLOPES AND ALONG THE DOWN SLOPE PERIMETER OF THE PROJECT. THEY SHALL BE PLACED AT 25 FOOT INTERVALS ON GRADED SLOPES. PLACEMENT SHALL RUN WITH THE CONTOURS AND ROLLS SHALL BE TIGHTLY END BUTTED. CONTRACTOR SHALL REFER TO MANUFACTURERS SPECIFICATIONS FOR PLACEMENT AND INSTALLATION INSTRUCTIONS.

### REFERENCES:



- CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD'S FIELD MANUAL FOR EROSION AND SEDIMENTATION CONTROL
- CALIFORNIA STORM WATER QUALITY ASSOCIATION BEST MANAGEMENT PRACTICES HANDBOOK FOR CONSTRUCTION

### PERIODIC MAINTENANCE:

- MAINTENANCE IS TO BE PERFORMED AS FOLLOWS:
  - DAMAGES CAUSED BY SOIL EROSION OR CONSTRUCTION SHALL BE REPAIRED AT THE END OF EACH WORKING DAY.
  - SWALES SHALL BE INSPECTED PERIODICALLY AND MAINTAINED AS NEEDED.
  - SEDIMENT TRAPS, BERMS, AND SWALES ARE TO BE INSPECTED AFTER EACH STORM AND REPAIRS MADE AS NEEDED.
  - SEDIMENT SHALL BE REMOVED AND SEDIMENT TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT HAS ACCUMULATED TO A DEPTH OF 1' FOOT.
  - SEDIMENT REMOVED FROM TRAP SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.
  - RILLS AND GULLIES MUST BE REPAIRED.
- GRAVEL BAG INLET PROTECTION SHALL BE CLEANED OUT WHENEVER SEDIMENT DEPTH IS ONE HALF THE HEIGHT OF ONE GRAVEL BAG.
- STRAW ROLLS SHALL BE PERIODICALLY CHECKED TO ASSURE PROPER FUNCTION AND CLEANED OUT WHENEVER THE SEDIMENT DEPTH REACHED HALF THE HEIGHT OF THE ROLL.
- SILT FENCE SHALL BE PERIODICALLY CHECKED TO ASSURE PROPER FUNCTION AND CLEANED OUT WHENEVER THE SEDIMENT DEPTH REACHES ONE FOOT IN HEIGHT.
- CONSTRUCTION ENTRANCE SHALL BE REGRAVELLED AS NECESSARY FOLLOWING SILT/SOIL BUILDUP.
- ANY OTHER EROSION CONTROL MEASURES SHOULD BE CHECKED AT REGULAR INTERVALS TO ASSURE PROPER FUNCTION



### EROSION CONTROL LEGEND



SWPPP NOTE:  
REFER TO PROJECT SWPPP FOR ADDITIONAL INFORMATION.

NOTE:  
SEAL ALL OTHER INLETS NOT INTENDED TO ACCEPT STORM WATER AND DIRECT FLOWS TEMPORARILY TO FUNCTIONAL SEDIMENTATION BASIN INLETS. -TYP




**LEA & BRAZE ENGINEERING, INC.**  
CIVIL ENGINEERS • LAND SURVEYORS  
SACRAMENTO REGION  
2400 COLLEGE BLVD., SUITE # 300  
ROSELAND, CALIFORNIA 95661  
(P) (916) 966-1338  
(F) (916) 967-7363  
WWW.LEABRAZE.COM

**CALWATER TANK  
DRAINAGE & TREATMENT PLAN  
SAN MATEO, CALIFORNIA**


**EROSION CONTROL  
PLAN**

REVISIONS	BY


JOB NO: 2161285  
DATE: 02-01-23  
SCALE: 1"=20'  
DESIGN BY: AH  
DRAWN BY: MCF  
SHEET NO:




1 INLET PROTECTION  
ER-2 NTS



2 STREET INLET PROTECTION  
ER-2 NTS




3 GRAVEL BAG AT STREET FLOW LINE  
ER-2 NTS




4 CONSTRUCTION ENTRANCE  
ER-2 NTS

**NOTES:**  
 STABILIZED CONSTRUCTION SITE ACCESS SHALL BE CONSTRUCTED OF 3" TO 4" WASHED, FRACTURED STONE AGGREGATE.  
 MATERIAL SHALL BE PLACED TO A MINIMUM THICKNESS OF 12". LENGTH OF ENTRANCE SHALL BE A MINIMUM OF 50'.  
 WIDTH SHALL BE A MIN. OF 15' OR GREATER IF NECESSARY TO COVER ALL VEHICULAR INGRESS AND EGRESS. PROVIDE AMPLE TURNING RADIUS.  
 THE ENTRANCE SHALL BE KEPT IN GOOD CONDITION BY OCCASIONAL TOP DRESSING WITH MATERIAL AS SPECIFIED IN ABOVE NOTE.  
 ACCESSES SHALL BE INSPECTED WEEKLY DURING PERIODS OF HEAVY USAGE, MONTHLY DURING NORMAL USAGE, AND AFTER EACH RAINFALL, WITH MAINTENANCE PROVIDED AS NECESSARY.  
 PERIODIC TOP DRESSING SHALL BE DONE AS NEEDED.




**NOTE:**  
 1. STRAW ROLL INSTALLATION REQUIRES THE PLACEMENT AND SECURE STAKING OF THE ROLL IN A TRENCH, 3" TO 5" DEEP, DUG ON CONTOUR. RUNOFF MUST NOT BE ALLOWED TO RUN UNDER OR AROUND ROLL.  
 2. CONTRACTOR IS RESPONSIBLE FOR REGULAR MAINTENANCE AND INSPECTION. THE SILT SHALL BE CLEANED OUT WHEN IT REACHES HALF THE HEIGHT OF THE ROLL.

5 STRAW ROLLS  
ER-2 NTS



6 CONCRETE WASHOUT  
ER-2 NTS

**NOTES:**  
 ACTUAL LAYOUT DETERMINED IN FIELD.  
 THE CONCRETE WASHOUT SIGN SHALL BE INSTALLED WITHIN 10' OF THE TEMPORARY CONCRETE WASHOUT FACILITY.



7 SILT FENCE  
ER-2 NTS

**NOTE:**  
 PREMANUFACTURED SILT FENCE PRODUCTS MAY BE USED IN LIEU OF WIRE FENCE. INSTALL PER MANUFACTURER'S RECOMMENDATIONS AND MAINTAIN KEYING OF FABRIC PER THIS DETAIL.  
**NOTE:**  
 IT IS ESSENTIAL THAT THE WIRE/FABRIC BE FULLY EMBEDDED INTO THE GROUND SO RUN-OFF CANNOT FLOW FREELY UNDER FENCE.




**LEA & BRAZE ENGINEERING, INC.**  
 CIVIL ENGINEERS • LAND SURVEYORS  
 SACRAMENTO REGION  
 300 JACOBSON WAY, WEST  
 SACRAMENTO, CALIFORNIA 95831  
 (P) (916) 966-1338  
 (F) (916) 966-1338  
 WWW.LEABRAZE.COM

**CALWATER TANK  
 DRAINAGE & TREATMENT PLAN  
 SAN MATEO, CALIFORNIA**  
 (UNINCORPORATED) SAN MATEO COUNTY

**EROSION CONTROL  
 DETAILS**

REVISIONS	BY




SAN MATEO COUNTYWIDE  
**Water Pollution  
Prevention Program**

Clean Water. Healthy Community.

# Construction Best Management Practices (BMPs)

Construction projects are required to implement the stormwater best management practices (BMP) on this page, as they apply to your project, all year long.

## Materials & Waste Management



### Non-Hazardous Materials

- ❑ Berm and cover stockpiles of sand, dirt or other construction material with tarps when rain is forecast or if not actively being used within 14 days.
- ❑ Use (but don't overuse) reclaimed water for dust control.

### Hazardous Materials

- ❑ Label all hazardous materials and hazardous wastes (such as pesticides, paints, thinners, solvents, fuel, oil, and antifreeze) in accordance with city, county, state and federal regulations.
- ❑ Store hazardous materials and wastes in water tight containers, store in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecast.
- ❑ Follow manufacturer's application instructions for hazardous materials and be careful not to use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.
- ❑ Arrange for appropriate disposal of all hazardous wastes.

### Waste Management

- ❑ Cover waste disposal containers securely with tarps at the end of every work day and during wet weather.
- ❑ Check waste disposal containers frequently for leaks and to make sure they are not overfilled. Never hose down a dumpster on the construction site.
- ❑ Clean or replace portable toilets, and inspect them frequently for leaks and spills.
- ❑ Dispose of all wastes and debris properly. Recycle materials and wastes that can be recycled (such as asphalt, concrete, aggregate base materials, wood, gyp board, pipe, etc.)
- ❑ Dispose of liquid residues from paints, thinners, solvents, glues, and cleaning fluids as hazardous waste.

### Construction Entrances and Perimeter

- ❑ Establish and maintain effective perimeter controls and stabilize all construction entrances and exits to sufficiently control erosion and sediment discharges from site and tracking off site.
- ❑ Sweep or vacuum any street tracking immediately and secure sediment source to prevent further tracking. Never hose down streets to clean up tracking.

## Equipment Management & Spill Control




### Maintenance and Parking

- ❑ Designate an area, fitted with appropriate BMPs, for vehicle and equipment parking and storage.
- ❑ Perform major maintenance, repair jobs, and vehicle and equipment washing off site.
- ❑ If refueling or vehicle maintenance must be done onsite, work in a bermed area away from storm drains and over a drip pan or drop cloths big enough to collect fluids. Recycle or dispose of fluids as hazardous waste.
- ❑ If vehicle or equipment cleaning must be done onsite, clean with water only in a bermed area that will not allow rinse water to run into gutters, streets, storm drains, or surface waters.
- ❑ Do not clean vehicle or equipment onsite using soaps, solvents, degreasers, or steam cleaning equipment.

### Spill Prevention and Control

- ❑ Keep spill cleanup materials (e.g., rags, absorbents and cat litter) available at the construction site at all times.
- ❑ Inspect vehicles and equipment frequently for and repair leaks promptly. Use drip pans to catch leaks until repairs are made.
- ❑ Clean up spills or leaks immediately and dispose of cleanup materials properly.
- ❑ Do not hose down surfaces where fluids have spilled. Use dry cleanup methods (absorbent materials, cat litter, and/or rags).
- ❑ Sweep up spilled dry materials immediately. Do not try to wash them away with water, or bury them.
- ❑ Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.
- ❑ Report significant spills immediately. You are required by law to report all significant releases of hazardous materials, including oil. To report a spill: 1) Dial 911 or your local emergency response number, 2) Call the Governor's Office of Emergency Services Warning Center, (800) 852-7550 (24 hours).

## Earthmoving



- ❑ Schedule grading and excavation work during dry weather.
- ❑ Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.
- ❑ Remove existing vegetation only when absolutely necessary, and seed or plant vegetation for erosion control on slopes or where construction is not immediately planned.
- ❑ Prevent sediment from migrating offsite and protect storm drain inlets, gutters, ditches, and drainage courses by installing and maintaining appropriate BMPs, such as fiber rolls, silt fences, sediment basins, gravel bags, berms, etc.
- ❑ Keep excavated soil on site and transfer it to dump trucks on site, not in the streets.

### Contaminated Soils

- ❑ If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:
  - Unusual soil conditions, discoloration, or odor.
  - Abandoned underground tanks.
  - Abandoned wells
  - Buried barrels, debris, or trash.

## Paving/Asphalt Work




- ❑ Avoid paving and seal coating in wet weather or when rain is forecast, to prevent materials that have not cured from contacting stormwater runoff.
- ❑ Cover storm drain inlets and manholes when applying seal coat, tack coat, slurry seal, fog seal, etc.
- ❑ Collect and recycle or appropriately dispose of excess abrasive gravel or sand. Do NOT sweep or wash it into gutters.
- ❑ Do not use water to wash down fresh asphalt concrete pavement.

### Sawcutting & Asphalt/Concrete Removal

- ❑ Protect nearby storm drain inlets when saw cutting. Use filter fabric, catch basin inlet filters, or gravel bags to keep slurry out of the storm drain system.
- ❑ Shovel, absorb, or vacuum saw-cut slurry and dispose of all waste as soon as you are finished in one location or at the end of each work day (whichever is sooner!).
- ❑ If sawcut slurry enters a catch basin, clean it up immediately.

## Concrete, Grout & Mortar Application




- ❑ Store concrete, grout, and mortar away from storm drains or waterways, and on pallets under cover to protect them from rain, runoff, and wind.
- ❑ Wash out concrete equipment/trucks offsite or in a designated washout area, where the water will flow into a temporary waste pit, and in a manner that will prevent leaching into the underlying soil or onto surrounding areas. Let concrete harden and dispose of as garbage.
- ❑ When washing exposed aggregate, prevent washwater from entering storm drains. Block any inlets and vacuum gutters, hose washwater onto dirt areas, or drain onto a bermed surface to be pumped and disposed of properly.

## Landscaping



- ❑ Protect stockpiled landscaping materials from wind and rain by storing them under tarps all year-round.
- ❑ Stack bagged material on pallets and under cover.
- ❑ Discontinue application of any erodible landscape material within 2 days before a forecast rain event or during wet weather.


## Painting & Paint Removal



### Painting Cleanup and Removal

- ❑ Never clean brushes or rinse paint containers into a street, gutter, storm drain, or stream.
- ❑ For water-based paints, paint out brushes to the extent possible, and rinse into a drain that goes to the sanitary sewer. Never pour paint down a storm drain.
- ❑ For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent in a proper container. Filter and reuse thinners and solvents. Dispose of excess liquids as hazardous waste.
- ❑ Paint chips and dust from non-hazardous dry stripping and sand blasting may be swept up or collected in plastic drop cloths and disposed of as trash.
- ❑ Chemical paint stripping residue and chips and dust from marine paints or paints containing lead, mercury, or tributyltin must be disposed of as hazardous waste. Lead based paint removal requires a state-certified contractor.

## Dewatering



- ❑ Discharges of groundwater or captured runoff from dewatering operations must be properly managed and disposed. When possible send dewatering discharge to landscaped area or sanitary sewer. If discharging to the sanitary sewer call your local wastewater treatment plant.
- ❑ Divert run-on water from offsite away from all disturbed areas.
- ❑ When dewatering, notify and obtain approval from the local municipality before discharging water to a street gutter or storm drain. Filtration or diversion through a basin, tank, or sediment trap may be required.
- ❑ In areas of known or suspected contamination, call your local agency to determine whether the ground water must be tested. Pumped groundwater may need to be collected and hauled off-site for treatment and proper disposal.

**Storm drain polluters may be liable for fines of up to \$10,000 per day!**



## **APPENDIX D**

### **Tree Removal and Replacement Plans**

EXISTING ANTENNA WILL BE REPLACE & MOVED TO NEW LOCATION

NO TREE PLANTING DUE TO EXISTING PIPING & FUTURE UNDERGROUND UTILITIES.

EXISTING TREE REMOVED FOR CONSTRUCTION (TYP.)

EXISTING TREES TO REMAIN (TYP.)

EXISTING DEAD TREES REMOVED DUE TO STORM DAMAGE (TYP.)

EXISTING TREE REMOVED FOR CONSTRUCTION (TYP.)

EXISTING TREES TO REMAIN (TYP.)

EXISTING DEAD TREES REMOVED DUE TO STORM DAMAGE (TYP.)

EXISTING TREE REMOVED FOR CONSTRUCTION (TYP.)

EXISTING TREES TO REMAIN (TYP.)

EXISTING DEAD TREES REMOVED DUE TO STORM DAMAGE (TYP.)

EXISTING TREE REMOVED FOR CONSTRUCTION (TYP.)

EXISTING TREES TO REMAIN (TYP.)

EXISTING DEAD TREES REMOVED DUE TO STORM DAMAGE (TYP.)

EXISTING TREE REMOVED FOR CONSTRUCTION (TYP.)

EXISTING TREES TO REMAIN (TYP.)

EXISTING DEAD TREES REMOVED DUE TO STORM DAMAGE (TYP.)

EXISTING TREE REMOVED FOR CONSTRUCTION (TYP.)

EXISTING TREES TO REMAIN (TYP.)

EXISTING DEAD TREES REMOVED DUE TO STORM DAMAGE (TYP.)

EXISTING TREE REMOVED FOR CONSTRUCTION (TYP.)

EXISTING TREES TO REMAIN (TYP.)

EXISTING DEAD TREES REMOVED DUE TO STORM DAMAGE (TYP.)




EXISTING TREE REMOVED FOR CONSTRUCTION (TYP.)

EXISTING TREES TO REMAIN (TYP.)

**EXISTING CONDITIONS**

SCALE: 1/8" = 1'-0"

**LEGENDS:**


-  EXISTING TREES TO REMAIN (TYP.)
-  EXISTING DEAD TREES REMOVED DUE TO STORM DAMAGE.
-  EXISTING TREE REMOVED FOR CONSTRUCTION (TYP.)

LOT 12

LOT 11

LOT 15

LOT 19



LANDS OF CALIFORNIA WATER SERVICE COMPANY

TELECOM STATIONS AND / OR ANTENNAS (TYP.)

FENCE LINES (TYP.)

CAL WATER SERVICE PROPERTY LINE (TYP.)


LOT 10

LOT 11

LOT 12

LOT 15


LOT 19



LANDS OF CALIFORNIA WATER SERVICE COMPANY

**PLANTING PLAN**

SCALE: 1/8" = 1'-0"



SEE SHEET L-3 FOR PLANTING NOTES, LEGENDS AND DETAILS.

**ROBERT MOWAT ASSOCIATES**  
 LANDSCAPE ARCHITECTURE + LAND PLANNING  
 1501 N. Broadway Suite 400 Walnut Creek, CA 94596  
 Phone 925.705.7424 Fax 925.954.1390  
 www.rmlandscape.com


**BEL AIRE HEIGHTS SUBDIVISION**  
 1700 S. EL CAMINO REAL, #100  
 SAN MATEO, CA 94402

**EXISTING CONDITIONS & PLANTING PLAN**

DATE 10-13-21  
 REVISIONS  
 1 PLANT & IRR. SITE PLAN REV. 5-4-23  
 2 CAL WATER COMMENTS 6-5-23

BEL AIRE HEIGHTS, SAN MATEO, CA  
 SHEET  
**L-1**  
 OF 3

© COPYRIGHT 2021 Robert Mowat Associates. No portion of this drawing may be reproduced, duplicated, or copied in any way without the express written consent of Robert Mowat Associates. This drawing is prepared for this particular site and may not be utilized for another site location.



**IRRIGATION PLAN**

SCALE: 1/8" = 1'-0"


**IRRIGATION LEGENDS**

- 6 STATIONS RAINMASTER EAGLE PLUS WITH CENTRAL COMPATABILITY W/ RAIN CLIK.
- POINT OF CONNECTION SERVICE BY OTHERS, COORDINATE EXACT LOCATION W/ CAL WATER
- 2" PLASTIC GLOBE GATE VALVE IN AMETEK BOX W/ GRAVEL.
- WATTS PRESSURE REDUCER IF REQUIRED
- REDUCED PRESSURE FEBCO 3/4" #825Y BACKFLOW PREVENTER ASSEMBLY W/ PRIME 2X PAINTED 2X DARK GREEN, GALV. STEEL ENCLOSURE WITH FROST BLANKET (OR EQ.)
- HUNTER 1" PGV VALVE WITH FLOW CONTROL AND ACCU SYNC ADJUSTABLE PRESSURE REGULATOR.
- SCH 40 - PVC MAINLINE, BURY MIN. 18" DEEP, SIZE PER PLAN, 24" FOR ROADWAYS. THE CONTRACTOR SHALL INSTALL CONC. THRUST BLOCKS AT ALL JOINTS ON 2" AND LARGER MAINLINES. IF IRRIGATION CONTRACTOR IDENTIFIES AN ALTERNATE ROUTE FOR MAINLINE, THEY SHALL NOTIFY THE OWNER & LANDSCAPE ARCHITECT FOR A MEETING, SITE OBSERVATION AND DISCUSSION BEFORE PROCEEDING WITH THE WORK.
- SCH 40 PVC LATERAL LINE BELOW GRADE - BURY 12" ±.
- SCH 40 PVC SLEEVE, BURY 24" DEEP, SIZE PER PLAN

SYMBOL	DISTRIBUTOR	TYPE	MODEL#	RADIUS	ARC	DESCRIPTION	FLOW
	HUNTER	PRS40 W/MP1000	PROS-12-PRS40-CV-MP1000360	12"	360°	12" POP-UP SHRUB MP ROTOR HEAD	.84 GPM
	HUNTER	PRS40 W/MP1000	PROS-12-PRS40-CV-MP1000210	12"	270°	12" POP-UP SHRUB MP ROTOR HEAD	.63 GPM
	HUNTER	PRS40 W/MP1000	PROS-12-PRS40-CV-MP100090	12"	180°	12" POP-UP SHRUB MP ROTOR HEAD	.42 GPM
	HUNTER	PRS40 W/MP1000	PROS-12-PRS40-CV-MP100090	12"	90°	12" POP-UP SHRUB MP ROTOR HEAD	.21 GPM
	HUNTER	BUBBLER	PCB-50	NA	360°	BUBBLER IN PREF. PIPE	0.5 GPM


**IRRIGATION NOTES**

- THIS DESIGN IS DIAGRAMMATIC. ALL PIPING, VALVES, ETC. SHOWN WITHIN THE PAVED AREAS OR BUILDINGS IS FOR DESIGN CLARIFICATION ONLY AND SHALL BE INSTALLED IN PLANTING AREAS WHERE POSSIBLE. AVOID CONFLICTS WITH PLANTING, PIPING, UTILITIES AND ARCHITECTURE WHERE POSSIBLE.
- DO NOT WILLFULLY INSTALL THE SYSTEMS SHOWN ON THE DRAWINGS WHEN IT IS OBVIOUS IN THE FIELD THAT OBSTRUCTIONS, GRADE DIFFERENCES, GPM AVAILABILITY, OR PRESSURES EXIST THAT MAY NOT HAVE BEEN INCLUDED IN THE ENGINEERING. SUCH OBSTRUCTIONS OR DIFFERENCES SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE CITY AND LAND ARCH. FOR A DECISION. IN THE EVENT THAT NOTIFICATION IS NOT PERFORMED, THE IRRIGATION CONTRACTOR SHALL ASSUME ALL RESPONSIBILITY FOR ANY REVISIONS NECESSARY.
- 120 VOLT ELECTRICAL POWER OUTLET AT THE AUTOMATIC CONTROLLER LOCATION SHALL BE PROVIDED BY OTHERS. THE IRRIGATION CONTRACTOR SHALL MAKE FINAL HOOK-UP FROM REMOTE CONTROL VALVES TO CONTROLLER.
- IT IS THE RESPONSIBILITY OF THE IRRIGATION CONTRACTOR TO FAMILIARIZE THEMSELVES WITH ALL GRADE DIFFERENCES, LOCATION OF WALLS, RETAINING WALLS, UTILITIES, PIPING, BUILDINGS, ETC. THEY SHALL COORDINATE THEIR WORK WITH THE GENERAL CONTRACTOR FOR THE INSTALLATION OR PIPE SLEEVES THROUGH WALLS, UNDER ROADWAYS, STRUCTURES, ETC.
- THE IRRIGATION SYSTEM SHALL BE INSTALLED IN CONFORMANCE WITH ALL APPLICABLE STATE AND LOCAL CODES AND ORDINANCES BY A LICENSED LANDSCAPE CONTRACTOR AND EXPERIENCED WORKMEN. CONTRACTOR TO OBTAIN AND PAY FOR ALL IRRIGATION PERMITS AND REQUIRED FEES.
- CONTRACTOR IS TO CONFIRM THE LOCATION OF EXISTING UTILITIES AND UNDERGROUND STRUCTURES PRIOR TO THE EXCAVATION OF TRENCHES. CONTRACTOR TO REPAIR ANY DAMAGE CAUSED BY, OR DURING THE PERFORMANCE OF, HIS WORK AT NO ADDITIONAL COST TO THE CITY.
- SYSTEM IS BASED UPON A STATIC MAINLINE PRESSURE OF 55 P.S.I. A PRESSURE REDUCER MAY (MAY NOT) BE REQUIRED SO THAT THE STATIC MAINLINE PRESSURE AS MEASURED AT THE POINT OF CONNECTION (AFTER THE BACK FLOW DEVICE) IS DRIP 35 P.S.I. AFTER CALCULATING PRESSURE LOSSES, THE SYSTEM IS DESIGNED TO OPERATE AT APPROXIMATELY 35-40 P.S.I. WORKING PRESSURE AT THE HEADS. THROUGH ANY ONE VALVE, THE SYSTEM IS DESIGNED TO OPERATE AT A MAXIMUM OF 18 GPM.
- CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SLEEVING REQUIRED FOR ELECTRICAL AND IRRIGATION. CONTRACTOR TO COORDINATE AND LOCATE ANY ELECTRICAL AND IRRIGATION SLEEVES PRIOR TO CONCRETE POUR. LANDSCAPE ARCHITECT TO REVIEW LAYOUT PRIOR TO CONCRETE POUR. SLEEVES TO BE SCH. 40 PVC PIPE, SET IN A 2" SAND BED CONTINUOUS AROUND ENTIRE SLEEVE, WITH MARKING TAPE AT EACH END. EXTEND PAST PAVING 6" TRENCHES ARE TO BE OF SUFFICIENT DEPTH TO PROVIDE 18" OF COVER OVER MAINLINE LATERAL LINES PRIOR TO THE INSTALLATION OF IRRIGATION HEADS. MAINLINE TO BE VISUALLY INSPECTED FOR LEAKS UNDER FULL OPERATING PRESSURE PRIOR TO BACKFILLING. MAINLINE UNDER STREETS TO BE 24" DEEP, MINIMUM.
- FLUSH MAINLINES PRIOR TO THE INSTALLATION OF REMOTE CONTROL VALVES. FLUSH LATERAL LINES PRIOR TO THE INSTALLATION OF IRRIGATION HEADS. MAINLINE TO BE VISUALLY INSPECTED FOR LEAKS UNDER FULL OPERATING PRESSURE PRIOR TO BACKFILLING.
- IRRIGATION CONTROL WIRE SHALL BE #14 U.L. APPROVED FOR DIRECT BURIAL. COMMON WIRE SHALL BE #14 U.L. APPROVED FOR DIRECT BURIAL, WHITE IN COLOR. WIRES TO BE MULTI-STRAND #18-9 REMOTE CONTROL VALVES SHALL BE A COLOR OTHER THAN WHITE. ALL SPLICES SHALL BE MADE WITHIN REMOTE CONTROL VALVE BOXES. LEAVE 24" EXCESS WIRE COIL AT REMOTE CONTROL LOCATIONS.
- REMOTE CONTROL VALVE BOXES SHALL BE INSTALLED FLUSH WITH FINISH GRADE (NOT NECESSARILY PLUMB). ALIGN VALVE BOXES WITH ADJACENT PAVEMENT EDGES OR STRUCTURES. VALVE BOXES SHALL BE PLASTIC WITH BOLT DOWN LIDS AND WITH WHITE NUMBERED VALVE STATIONS IN STENCILS.
- ALL EXCAVATIONS SHALL BE BACKFILLED TO 90% COMPACTION (MIN.). CONTRACTOR TO REPAIR SETTLED TRENCHES FOR ONE YEAR AFTER COMPLETION OF WORK.
- CONTRACTOR TO MAKE MINOR ADJUSTMENTS IN HEAD LOCATIONS AND ADJUST HEADS FOR RADIUS (ARC IF APPLICABLE), TO OPTIMUM COVERAGE, AND TO ELIMINATE SPRAYING ONTO PAVEMENT, BUILDINGS, AND WALLS. ADD HEADS AS NECESSARY FOR HEAD TO HEAD COVERAGE. INSTALL FLAT HEADS NEAR BLDGS.
- CONTRACTOR TO MAINTAIN A SET OF "AS-BUILT" DRAWINGS THROUGHOUT THE COURSE OF CONSTRUCTION AND DELIVER THESE DRAWINGS TO THE OWNER / HOA UPON THE COMPLETION OF WORK. THE DRAWINGS SHALL BE IN REPRODUCIBLE FORM.
- CONTRACTOR SHALL GUARANTEE THE SYSTEM AND MATERIALS TO BE FREE FROM DEFECTS FOR A PERIOD OF ONE YEAR STARTING WITH ACCEPTANCE AT THE FINAL SITE REVIEW.
- ALL HEADS WHICH MAY EXPERIENCE LOW HEAD DRAINAGE SHOULD HAVE IN-LINE OR IN-HEAD CHECK VALVES INSTALLED.
- THE IRRIGATION CONTRACTOR SHOULD ARRANGE WITH THE LAND ARCH. & CITY REP. FOR A SITE REVIEW OF THE SYSTEM. CALL WITH TWO DAYS PRIOR NOTICE TO ARRANGE REVIEW DATES. REVIEWS WILL BE SCHEDULED TO REVIEW:
  - PRESSURE TEST TO MAIN LINE PRIOR TO BACKFILLING TRENCHES.
  - COVER TEST OF SPRINKLER SYSTEM PRIOR TO PLANTING.
  - FINAL WALK-THROUGH OF ALL ASPECTS OF THE IRRIGATION SYSTEM.
- WATER JET ALL IRRIGATION TRENCHES, TYPICAL.
- ALL CONTROLLERS SHALL HAVE A MAP OR IRRIGATION ZONE DESCRIPTION PLACED IN THE CONTROLLER CABINET.
- DETECTABLE WARNING TAPE SHALL BE INSTALLED DIRECTLY OVER ALL IRRIGATION MAIN LINES. THE TAPE SHALL BE SIX INCHES (6") WIDE, 5-MIL AND HAVE ALUMINUM BACKING TO MAKE IT EASY TO FIND UNDERGROUND USING A NON-FERROUS LOCATOR. TAPE SHALL HAVE "CAUTION BURIED WATER LINE BELOW" PRINTED IN BLACK LETTERING ON A BLUE BACKGROUND.




**POP-UP SPRAY HEAD**

NOT TO SCALE




**POST MOUNT CONTROLLER**

NOT TO SCALE




**ISOLATION GATE VALVE**

NOT TO SCALE




**REDUCED PRESSURE BACKFLOW**

NOT TO SCALE



**POP-UP BUBBLER HEAD AT TREES**

NOT TO SCALE



**REMOTE CONTROL VALVE**

NOT TO SCALE

**ROBERT MOWAT ASSOCIATES**  
 LANDSCAPE ARCHITECTURE + LAND PLANNING  
 1501 N. Broadway Suite 400 Walnut Creek, CA 94596  
 Phone 925.705.7424 Fax 925.954.1390  
 www.rmlandscape.com

**BEL AIRE HEIGHTS SUBDIVISION**  
 1700 S. EL CAMINO REAL, #100  
 SAN MATEO, CA 94402

**IRRIGATION PLANS, NOTES & LEGENDS & DETAILS**

DATE 10-13-21  
 REVISIONS  
 1. PLANT & IRR. SITE PLAN REV. 5-4-23  
 2. CAL WATER COMMENTS 6-5-23

SHEET  
**L-2**  
 OF 3

BEL AIRE HEIGHTS, SAN MATEO, CA  
 © COPYRIGHT 2021 Robert Mowat Associates. No portion of this drawing may be reproduced, duplicated, or copied in any way without the express written consent of Robert Mowat Associates. This drawing is prepared for this particular site and may not be utilized for another site location.

# PLANTING LEGEND

SYMBOL	SIZE	BOTANICAL NAME	COMMON NAME	WATER USE	QUANTITY
	24" BOX	QUERCUS AGRIFOLIA	COAST LIVE OAK	LOW	13
	15 GAL	HETEROMELESE ARBUTIFOLIA	TOYON	LOW	5
	5 GAL	ARCTOSTAPHYLOS 'HOWARD MCMINN'	MANZANITA	LOW	17
	5 GAL	PRUNUS LAURACERASUS	ENGLISH LAUREL	LOW	8
	1 GAL	VERBENA LILACINA 'DE LA MINA'	DE LA MINA VERBENA	LOW	37
	1 GAL	COTONEASTER DAMMERI 'LOWFAST'	BEARBERRY COTONEASTER	LOW	3'-6" O.C.
	1 GAL	CAREX DIVULSA (TUMULICOLA)	BERKELEY SEDGE	LOW	2'-0" O.C.

## PLANTING NOTES

- ALL WORK SHALL BE PERFORMED BY A LICENSED LANDSCAPE CONTRACTOR AND PERSONNEL FAMILIAR WITH THE WORK AND UNDER THE SUPERVISION OF A QUALIFIED PLANTING FOREMAN.
- PLANT MATERIAL LOCATIONS ARE DIAGRAMMATIC AND SUBJECT TO CHANGE IN THE FIELD AS DIRECTED BY THE LANDSCAPE ARCHITECT. LOCATE PLANT MATERIALS TO SCREEN UTILITIES, IRRIGATION DEVICES, ETC. AS MUCH AS POSSIBLE YET ALLOW ACCESS TO THEM.
- ALL TREES SHALL BE STAKED AS SHOWN IN THE DETAILS.
- THE OWNER RESERVES THE RIGHT TO MAKE SUBSTITUTIONS, ADDITIONS AND DELETIONS IN THE PLANTING SCHEME AS NECESSARY WHILE WORK IS IN PROGRESS. SUCH CASES ARE TO BE ACCOMPANIED BY EQUITABLE ADJUSTMENTS IN THE CONTRACT PRICE IF WHEN NECESSARY.
- THE PLANT COUNT IS FOR THE CONTRACTOR'S CONVENIENCE. IN CASE OF A DISCREPANCY, THE PLAN SHALL GOVERN.
- LOOSEN THE TOP 10" OF TOPSOIL AND BLEND THE TOP 6" LAYER OF SOIL W/ FOLLOWING AMOUNTS / 1000 SQUARE FEET:


  - 6.0 CU. YDS. NITROGEN STABILIZED ORGANIC AMENDMENT\*
  - 50.0 LBS. GYPSUM
  - 25.0 LBS. NITROFORM (38-0-0)
  - 50.0 LBS. TREBLE SUPERPHOSPHATE (0-45-0)
  - 25.0 LBS. POTASSIUM SULFATE (0-0-50)
  - 15.0 LBS. FERROUS SULFATE (10% FE)

THE TOP 12" OF PLANT BACKFILL AROUND THE SIDES OF THE ROOTBALL OF TREES AND SHRUBS SHALL CONSIST OF THE ABOVE AMENDED SOIL PREPARED AS FOLLOWS:


  - 3 PARTS PULVERIZED SITE SOIL
  - 1 PART NITROGEN STABILIZED ORGANIC AMENDMENT\*
  - 1.0 LBS. IRON SULFATE

UNIFORMLY BLENDED WITH: (AMOUNT / CUBIC YARD BACKFILL MIX)


  - 3/4 POUND 6-20-20 COMPLETE FERTILIZER
  - 1/4 POUND POTASSIUM SULFATE (0-0-50)
- THE LANDSCAPE CONTRACTOR SHALL GUARANTEE ALL TREES FOR A PERIOD OF ONE YEAR AND ALL SHRUBS AND GROUND COVERS FOR A PERIOD OF 90 DAYS.
- ANY REQUIREMENTS IN THE PLANS SHALL BE CONSIDERED BINDING. IN CASE OF DISCREPANCIES THE OWNER AND LAND ARCH. SHALL BE IMMEDIATELY NOTIFIED FOR A DECISION BEFORE PROCEEDING WITH THE WORK.
- THERE SHALL BE REGULAR SITE VISITS BY THE LANDSCAPE ARCHITECT AND THE OWNER THROUGHOUT CONSTRUCTION AND A FINAL SITE REVIEW.
  - TO INSPECT PLANTS ON ARRIVAL FROM NURSERY
  - AT TIME OF PLANTING
  - A FINAL SITE REVIEW
- ALL PLANT MATERIAL NOT APPROVED BY LANDSCAPE ARCHITECT MAY BE SUBJECT TO REJECTION.
- ALL WORK SHALL BE INSTALLED IN CONFORMANCE WITH ALL LOCAL CODES AND ORDINANCES. THE LANDSCAPE CONTRACTOR SHALL OBTAIN ALL REQUIRED PERMITS. PROTECT EXISTING TREES AS NECESSARY. FENCE AS NECESSARY. LOCATE ALL UTILITIES BEFORE PROCEEDING WITH THE WORK. COORDINATE ALL DIGGING AND TRENCHING PRIOR TO BEGINNING WORK WITH THE PROJECT SUPERVISOR FIRST.
- THE DESIGN INTENT OF THE PLANTING PLAN IS TO ESTABLISH AND IMMEDIATE, ATTRACTIVE AND MATURE LANDSCAPE APPEARANCE. FUTURE PLANT GROWTH WILL NECESSITATE TRIMMING, SHAPING, PRUNING AND IN MOST CASES, REMOVAL OF TREES AND SHRUBS AS PART OF AN ON-GOING MAINTENANCE PROGRAM.
- ALL PLANT PITS SHALL BE FREE FROM ROCKS AND DEBRIS GREATER THAN 2" IN DIAMETER. APPLY "RONSTAR" OR "ELANCO XL" PRE-EMERGENT HERBICIDE TO ALL PLANTED SHRUB AREAS. APPLY HERBICIDE IN STRICT ACCORDANCE WITH MANUFACTURER'S SPECS.
- THE LANDSCAPE SHALL BE WEED FREE AT THE TIME OF THE FINAL WALK-THROUGH. CONTRACTOR TO PROVIDE MAINTENANCE DURING CONSTRUCTION AND FOR A PERIOD OF 60 DAYS FOLLOWING OWNER'S ACCEPTANCE OF THE COMPLETION OF THE FINAL PUNCH LIST AS PART OF THEIR BID. ALL PRUNING, SPRAYING, FERTILIZING, CLEAN-UP AND ASSOCIATED LANDSCAPE PRACTICES SHALL BE INCLUDED. THE 60 DAY MAINTENANCE PERIOD DOES NOT END UNTIL FINAL ACCEPTANCE BY THE OWNER IS GRANTED.
- CONTRACTOR TO SUBMIT UNIT PRICES FOR THE POSSIBLE ADDITION OF PLANTS TO THE PROJECT. SUBMIT UNIT PRICES FOR 15 GALLON TREES, 5 GALLON SHRUBS, 1 GALLON SHRUBS, GROUNDCOVER AT 50 FT. PRICES.
- 2" LAYER OF SHREDDED FIR BARK OVER ALL SHRUB/GROUNDCOVER AREAS.
- ON ALL SLOPES 2:1 OR GREATER, INSTALL JUTE MESH NETTING, LAP MIN. 12", STAPLE AT 24" O.C. TYP.
- ALL PLANT MATERIAL SHALL BE OF THE QUALITY AND SIZE IN ACCORDANCE WITH THE AMERICAN STANDARDS FOR NURSERY STOCK GUIDELINES, LATEST EDITION.
- THE CONTRACTOR IS RESPONSIBLE FOR THE REMOVAL FROM THE OWNER'S PROPERTY ALL WASTE MATERIAL GENERATED BY FROM THE PLANTING OPERATIONS.
- LANDSCAPE CONTRACTOR TO SHALL COORDINATE ALL WORK WITH RELATED SUB-CONTRACTORS AND WITH THE GENERAL CONSTRUCTION CONTRACTOR OF THE PROJECT.




426.25 PLANTING DETAIL



426.35 PLANTING DETAIL



426.24 PLANTING DETAIL



1 GOOD NEIGHBOR FENCE SCALE: 1/2" = 1' - 0" 180.01 GOOD NEIGHBOR FENCE

**ROBERT MOWAT ASSOCIATES**  
 LANDSCAPE ARCHITECTURE + LAND PLANNING  
 1501 N. Broadway Suite 400 Walnut Creek, CA 94596  
 Phone 925.705.7424 Fax 925.954.1390  
 www.rmatlandscape.com

**BEL AIRE HEIGHTS SUBDIVISION**  
 1700 S. EL CAMINO REAL, #100  
 SAN MATEO, CA 94402

**PLANTING NOTES, LEGENDS & DETAILS**

DATE 10-13-21  
 REVISIONS  
 PLANT & IRR. SITE PLAN REV. 5-4-23  
 CAL WATER COMMENTS 6-5-23

SHEET  
**L-3**  
 OF 3

© COPYRIGHT 2021 Robert Mowat Associates. No portion of this drawing may be reproduced, duplicated, or copied in any way without the express written consent of Robert Mowat Associates. This drawing is prepared for this particular site and may not be utilized for another site location.





## **APPENDIX E**

### **Revised Mitigation Monitoring and Reporting Program**

Ascension Heights Water Tank  
Project - Addendum to the Ascension  
Heights Subdivision Project

Revised Mitigation Monitoring and  
Reporting Program

SCH No. 2013102009

JUNE 2023

PREPARED FOR

**County of San Mateo  
Planning and Building Department**

PREPARED BY

**SWCA Environmental Consultants**

## REVISED MITIGATION MONITORING AND REPORTING PROGRAM

The California Environmental Quality Act (CEQA) requires that a Lead Agency establish a program to monitor and report on mitigation measures adopted as part of the environmental review process to avoid or reduce the severity and magnitude of potentially significant environmental impacts associated with project implementation. CEQA (Public Resources Code Section 21081.6 (a) (1)) requires that a Mitigation Monitoring and Reporting Program (MMRP) be adopted at the time that the public agency determines to approve a project for which an EIR has been prepared, to ensure that mitigation measures identified in the EIR are fully implemented.

The MMRP for the Ascension Heights Water Tank Project is presented below in the Revised Mitigation and Monitoring Reporting Program table. The table includes the full text of project-specific mitigation measures identified in the final EIR. The MMRP describes implementation and monitoring procedures, responsibilities, and timing for each mitigation measure identified in the EIR, including:

- **Significant Impact:** Identifies the Impact Number and statement from the final EIR.
- **Mitigation Measure:** Provides full text of the mitigation measure as provided in the final EIR.
- **Monitoring/Reporting Action(s):** Designates responsibility for implementation of the mitigation measure and when appropriate, summarizes the steps to be taken to implement the measure.
- **Mitigation Timing:** Identifies the stage of the project during which the mitigation action will be taken.
- **Monitoring Schedule:** Specifies procedures for documenting and reporting mitigation implementation.
- **Completion Status:** indicates whether the mitigation has been completed.

The County of San Mateo may modify how a mitigation measure will be implemented, as long as the alternative means ensure compliance during project implementation. The responsibilities of mitigation implementation, monitoring, and reporting extend to several County departments and offices. The manager or department lead of the identified unit or department will be directly responsible for ensuring the responsible party complies with the mitigation. The Planning and Building Department is responsible for the overall administration of the program and for assisting relevant departments and project managers in their oversight and reporting responsibilities. The Planning and Building Department is also responsible for ensuring the relevant parties understand their charge and complete the required procedures accurately and on schedule.

## Revised Mitigation Monitoring and Reporting Program

Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
<b>AESTHETICS</b>					
<p><b>Impact 4.1-1:</b> The Proposed Project could have a substantial adverse effect on a scenic vista; could substantially damage scenic resources, including trees; and could substantially degrade the existing visual character or quality of the site and its surroundings.</p>	<p><b>Mitigation Measure 4.1-1a:</b> Prior to recordation of the final map, the project applicant shall submit a landscape plan for review and approval by the San Mateo County Planning Department (County Planning Department). The landscape plan shall include the location, size, and species of any proposed landscaping and shall include, but not be limited to, hedges or other appropriate vegetation that will provide opaque screening between the northeastern edge of the project site and the residences along the southern side of Parrott Drive. In addition, all proposed landscaping shall be of native, non-invasive species. Areas used for the storage of landscape maintenance or other equipment, supplies, or debris shall be shielded from view by fencing, landscaping or other means. Prior to final approval of the final map, a site inspection shall be required by the County Planning Department to verify that all approved landscaping has been implemented or bonds posted for performance; a maintenance bond shall be required. All perimeter landscaping shall serve to screen and/or enhance views of the project site from surrounding roadways and neighborhoods.</p>	<p>Applicant / San Mateo County Planning and Building Department</p>	<p>Prior to the approval of each phase of the Final Map</p>	<p>Site inspection to verify compliance with mitigation measure.</p>	<p>Complete. Landscape plan approved by San Mateo County for Subdivision Project.</p>
	<p><b>Mitigation Measure 4.1-1b.</b> Prior to the issuance of a grading permit “hard card,” the applicant is required to submit a tree replacement plan that shall not exceed the following specifications:</p> <ul style="list-style-type: none"> <li>• For each loss of a significant indigenous tree, there shall be a replacement with three or more trees, as determined by the Community Development Director, of the same species using at least 5-gallon size stock.</li> <li>• For each loss of a significant exotic tree, there shall be a replacement with three or more trees, as determined by the Community Development Director that the substitute tree can survive and</li> </ul>	<p>California Department of Fish and Wildlife / San Mateo County Planning and Building Department shall oversee tree placement</p>	<p>Prior/ during construction</p>	<p>Site inspection to verify compliance with mitigation measures during construction; and subsequent monitoring as stipulated in the measure.</p>	<p>Complete. Landscape Plan approved for Subdivision Project.</p>

Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
	flourish in the regional climatic conditions. <ul style="list-style-type: none"> <li>Replacement trees shall require a surety deposit for both performance (installation of tree, staking, and providing an irrigation system) and maintenance. Maintenance shall be required for no less than two and no more than five years as determined by the Community Development Director.</li> </ul>				
<b>AIR QUALITY AND GREENHOUSE GAS EMISSIONS</b>					
<b>Impact 4.2-1:</b> Construction of the Proposed Project has the potential to generate emissions of ROG, NOx, PM10, and PM2.5.	<b>Mitigation Measure 4.2-1a:</b> The applicant shall ensure through the enforcement of contractual obligations that construction contractors implement a fugitive dust abatement program during construction, which shall include the following elements consistent with the Basic Construction Mitigation Measures recommended by the Bay Area Air Quality Management District (BAAQMD): <ul style="list-style-type: none"> <li>Cover all trucks hauling soil, sand, and other loose materials or require all trucks to maintain at least two feet of freeboard.</li> <li>Cover all exposed stockpiles.</li> <li>Water all exposed roadway and construction areas two times a day.</li> <li>Sweep paved streets three times daily (with water sweepers) if visible soil material is carried onto adjacent streets.</li> <li>Limit traffic speeds on unpaved roads to 15 miles per hour (mph).</li> <li>After grading is complete, construction of paved surfaces (e.g., roadways, driveways, sidewalks, building pads) should be completed as soon as possible unless protected by seeding, soil binders, or other similar measures.</li> <li>Limit idling time to a maximum of five minutes and turn off equipment when not in use; clear signage indicating this shall be displayed at the project site access point.</li> <li>All construction equipment shall be maintained and properly tuned in accordance with manufacturer's</li> </ul>	San Mateo County Planning and Building Department / Construction Contractors / BAAQMD	During construction.	Site inspection to verify compliance with mitigation measures during construction; applicable forms submitted to BAAQMD.	Ongoing.

Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
	<p>specifications and shall be checked by a certified visible emissions evaluator.</p> <ul style="list-style-type: none"> <li>• Suspend excavation and grading activity when winds (instantaneous gusts) exceed 25 mph.</li> <li>• Any burning of cleared vegetation shall be conducted according to the rules and regulations of the BAAQMD’s Regulation 5 (BAAQMD, 2008). Prior notification to BAAQMD shall be made by submitting an Open Burning Prior Notification Form to BAAQMD’s office in San Francisco.</li> <li>• A publicly visible sign shall be posted with the telephone number and person to contact at the County regarding dust complaints. A response and corrective action shall occur within 48 hours. The BAAQMD’s phone number shall also be visible to ensure compliance with applicable regulations.</li> </ul>				
	<p><b>Mitigation Measure 4.2-1b:</b> The project applicant shall ensure though contractual obligations with construction contractors that the following Best Management Practices (BMPs) shall be implemented during all stages of construction:</p> <ul style="list-style-type: none"> <li>• All heavy duty construction equipment be equipped with diesel particulate matter filters.</li> <li>• Only low ROG coatings shall be utilized.</li> <li>• <del>The applicant shall use only Tier 2 or better heavy-duty construction equipment.</del> The project applicant shall use Tier 4 Interim engines for all 75 horsepower or greater diesel-powered equipment, except where the project applicant establishes to the satisfaction of the County that Tier 4 Interim equipment is not available.</li> </ul>	<p>San Mateo County Planning and Building Department / Construction Contractors / Bay Area Air Quality Management District</p>	<p>During construction.</p>	<p>Site inspection to verify compliance with mitigation measures during construction</p>	<p>Ongoing.</p>
<p><b>Impact 4.2-8:</b> Construction and operation of the Proposed Project has the potential to result in cumulatively considerable emissions</p>	<p><b>Mitigation Measure 4.2-8:</b> The applicant shall purchase CO2e emissions reduction credits in the amount of 249 MT prior to the start of construction. GHG CO2e emissions reduction credits are generated by projects that reduce their GHG emissions by the use of technology or a reduction in business over business as usual. The CO2e emission reduction credits must be permanently retired by</p>	<p>Applicant / San Mateo County Planning and Building Department to verify purchase.</p>	<p>Prior to start of construction</p>	<p>Purchase credits and submit applicable forms to County Planning and Building.</p>	<p>Complete. Credits purchased February 22, 2022.</p>

Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
of GHGs.	the project applicant, thereby reducing annual emissions for the lifetime of the Proposed Project.				
<b>BIOLOGICAL RESOURCES</b>					
<p><b>Impact 4.3-3:</b> Construction activities have the potential to result in the disturbance of nesting or foraging habitat for northern harrier, burrowing owl, and white-tailed kite.</p>	<p><b>Mitigation Measure 4.3-3a:</b> Prior to the commencement of construction activities on the project site during the nesting season, a qualified biologist shall conduct a minimum of two protocol level preconstruction surveys for listed bird species during the recommended survey periods for the nesting season that coincides with the commencement of construction activities:</p> <ul style="list-style-type: none"> <li>• Northern harrier: Present year-round, breeds March through August;</li> <li>• Burrowing owl: Present year-round, breeds primarily March through August, but can be February- December; and</li> <li>• White-tailed kite: Present year-round, breeding occurs in autumn. Nesting season begins in February and ends in August.</li> </ul> <p>These surveys will occur in accordance with the USFWS Division of Migratory Bird Management Guidelines for Raptor Conservation in the United States (2008). The qualified biologist shall conduct surveys within 14 days of commencement for Northern harrier, burrowing owl, and white-tailed kite in the project site and within 0.25 miles of construction activities where legally permitted. The biologist will use binoculars to visually determine whether nests occur beyond the 0.25-mile survey area if access is denied on adjacent properties. If no active nests are identified on or within 0.25 miles of construction activities within the recommended survey periods, a letter report summarizing the survey results shall be submitted to the County and the CDFW within 30 days following the survey, and no further mitigation for nesting habitat is required. Evidence, in the form of a letter report documenting the results of the survey, shall be submitted to the County prior to the issuance of any grading or building permits within the project site.</p>	California Department of Fish and Wildlife / San Mateo County Planning and Building Department	Prior to issuance of grading building permits.	Verify completion of surveys and submittal of letter reports.	Complete. Biological surveys completed in April 2017



Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
	<p><b>Mitigation Measure 4.3-3b:</b> If active listed bird nests are found within 0.25 mile of construction activities, the biologist shall contact the County and CDFW within one day following the pre- construction survey to report the findings. For purposes of this mitigation requirement, construction activities are defined to include heavy equipment operation associated with construction (use of cranes or draglines, new rock crushing activities) or other project-related activities that could cause nest abandonment or forced fledging within 0.25 mile of a nest site during the identified nesting period. Should an active nest be present within 0.25 mile of construction areas, then CDFW shall be consulted to establish an appropriate noise buffer, develop take avoidance measures, and implement a monitoring and reporting program prior to any construction activities occurring within 0.25 mile of the nest/burrow. The monitoring program would require that a qualified biologist shall monitor all activities that occur within the established buffer zone to ensure that disruption of the nest/burrow or forced fledging does not occur. Should the biologist determine that the construction activities are disturbing the nest/burrow, the biologist shall halt construction activities until CDFW is consulted. The construction activities shall not commence until the CDFW determines that construction activities would not result in abandonment of the nest/burrow site. If the CDFW determines that take may occur, the applicant would be required to obtain a CESA take permit. Should the biologist determine that the nest/burrow has not been disturbed during construction activities within the buffer zone, then a letter report summarizing the survey results will be submitted to the County and CDFW and no further mitigation for nesting habitat is required.</p>	<p>California Department of Fish and Wildlife / San Mateo County Planning and Building Department</p>	<p>Prior to construction.</p>	<p>Verify completion of surveys and additional stipulated mitigation if necessary.</p>	<p>Complete. Biological surveys completed in April 2018</p>
<p><b>Impact 4.3-4:</b> Grading and construction activities have the potential to result in the disturbance of nesting habitat for migratory</p>	<p><b>Mitigation Measure 4.3-4a:</b> A qualified biologist shall conduct a pre-construction bird survey for nesting within 14 days prior to commencement of construction activities if anticipated to commence during the appropriate nesting season (between February 1 and August 31). The qualified biologist shall document and submit the results</p>	<p>California Department of Fish and Wildlife / San Mateo County Planning and Building</p>	<p>Prior to construction.</p>	<p>Verify completion of surveys and submittal of letter reports.</p>	<p>Complete. Biological surveys completed in April 2019</p>

Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
birds and other birds of prey.	of the pre-construction survey in a letter to CDFW and the County within 30 days following the survey. The letter shall include: a description of the methodology including dates of field visits, the names of survey personnel, a list of references cited and persons contacted, and a map showing the location(s) of any bird nests observed on the project site. If no active nests are identified during the pre-construction survey, then no further mitigation is required. Evidence, in the form of a letter report documenting the results of the survey, shall be submitted to the County Planning Department prior to the issuance of any grading or building permits within the project site.	Department			
	<b>Mitigation Measure 4.3-4b:</b> If any active nests are identified during the pre- construction survey within the project site, a buffer zone will be established around the nests. A qualified biologist will monitor nests weekly during construction to evaluate potential nesting disturbance by construction activities. The biologist will delimit the buffer zone with construction tape or pin flags within 250 feet of the active nest and maintain the buffer zone until the end of the breeding season or until the young have fledged. Guidance from CDFW will be requested if establishing a 250-foot buffer zone is impractical. Guidance from CDFW will be requested if the nestlings within the active nest appear disturbed.	California Department of Fish and Wildlife / San Mateo County Planning and Building Department	Prior/ during construction.	Verify completion of weekly surveys contingent on results of survey detailed in Mitigation Measure 4.3-4a.	
	<b>Mitigation Measure 4.3-4c:</b> Trees anticipated for removal should be removed outside of the nesting season (February 1 and August 31). If trees are anticipated to be removed during the nesting season, a pre-construction survey shall be conducted by a qualified biologist. If the survey shows that there is no evidence of active nests, then the tree shall be removed within ten days following the survey. If active nests are located within trees identified for removal, a 250-foot buffer shall be installed around the tree. Guidance from CDFW will be requested if the 250-foot buffer is infeasible.	California Department of Fish and Wildlife / San Mateo County Planning and Building Department	Prior to construction.	Verify completion of survey.	Complete. Biological surveys completed in April 2019. Additional surveys may be required if additional tree removal occurs.
<b>Impact 4.3-6:</b> Construction of the	<b>Mitigation Measure 4.3-6:</b> Prior to the issuance of grading permits and removal of any trees, a certified	Applicant / California	Prior to issuance of	Verify completion of surveys and	Complete. Arborist report completed

Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
<p>Proposed Project has the potential to remove trees protected within the tree preservation ordinance specified in the San Mateo County Significant Tree Ordinance.</p>	<p>arborist or registered professional forester shall conduct an arborist survey documenting all trees with trunk circumferences of 38 inches or greater and their location, as well as any Tree Communities or Indigenous Trees regardless of size. The report shall be submitted to the County Planning Department. The applicant shall not remove any trees without prior approval from the County Planning Department. All recommendations of the arborist report shall be implemented prior to the issuance of building permits for development on the project site. The arborist report shall specify measures including, but not limited to the following:</p> <ul style="list-style-type: none"> <li>• To the extent feasible, trees anticipated for removal shall be removed outside of the nesting season for birds. Taking into account the nesting season for the white tailed kite, the nesting season shall be defined as February 1 to August 31.</li> <li>• The project proponent shall plant replacement significant and/or indigenous tree species recommended by the County at a 3:1 ratio within the project site.</li> </ul>	<p>Department of Fish and Wildlife / San Mateo County Planning and Building Department</p>	<p>grading permits.</p>	<p>submittal of letter reports.</p>	<p>October 2018. Additional Arborist reports prepared in September 2019 and August 2022 to inform Tree Protection Plan.</p>
<p><b>Impact 4.3-7:</b> Development of the Proposed Project has the potential to contribute to the cumulative loss of special-status wildlife species or their habitat in the region.</p>	<p><b>Mitigation Measure 4.3-7:</b> Implement <b>Mitigation Measures 4.3-1</b> through <b>4.3-6</b>.</p>	<p>See Above</p>	<p>See Above</p>	<p>See Above</p>	<p>See Above</p>

Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
<b>GEOLOGY AND SOILS</b>					
<p><b>Impact 4.4-1:</b> Earth-moving activities associated with construction of the Proposed Project have the potential to result in soil erosion or the loss of topsoil.</p>	<p><b>Mitigation Measure 4.4-1a:</b> Implement Mitigation Measure 4.6-1 (Section 4.6; Hydrology and Water Quality) to identify and implement erosion control BMPs within the SWPPP prepared for construction activities in accordance with the State’s Clean Water Act NPDES general permit for construction activities. Implementation of these BMPs would ensure that temporary and short-term construction-related erosion impacts under the Proposed Project would be reduced to a less-than-significant level.</p>	<p>Applicant / San Mateo County Planning and Building Department</p>	<p>See Mitigation Measure 4.6-1 (Prior to and during Construction)</p>	<p>Submit NOI to SWRCB. Verify that a SWPPP has been prepared and implemented</p>	<p>Ongoing.</p>
	<p><b>Mitigation Measure 4.4-1b:</b> The applicant shall obtain a San Mateo County Grading Permit which includes the requirement of an Erosion and Sediment Control Plan. This Erosion and Sediment Control Plan shall be prepared by a licensed civil engineer or certified professional soil erosion and sediment control specialist. The plan shall show the location of proposed vegetative erosion control measures, including landscaping and hydroseeding, and the location and details of all proposed drainage systems. The plan shall include sufficient engineering analysis to show that the proposed erosion and sediment control measures during preconstruction, construction, and post-construction are capable of controlling surface runoff and erosion, retaining sediment on the project site, and preventing pollution of site runoff in compliance with the Clean Water Act.</p>	<p>Applicant / San Mateo County Planning and Building Department</p>	<p>Prior to issuance of a grading permit.</p>	<p>Verify that site-specific erosion control and sediment plans and post construction plans have been prepared and implemented.</p>	<p>Complete. Grading permit was approved July 28, 2020</p>
<p><b>Impact 4.4-2:</b> The Proposed Project has the potential to result in structural damage and injury from seismic activity and related geologic hazards.</p>	<p><b>Mitigation Measure 4.4-2a:</b> Grading and building designs, including foundation requirements, shall be consistent with the findings of the geotechnical investigation, the California Code of Regulations, and the California Building Code.</p>	<p>Applicant / San Mateo County Planning and Building Department</p>	<p>Prior to issuance of grading and building permits.</p>	<p>Project design review/grading and building standards.</p>	<p>Complete. Grading permit was approved July 28, 2021</p>
	<p><b>Mitigation Measure 4.4-2b:</b> The project applicant shall comply with all recommendations contained within the site-specific Geotechnical Investigation conducted by Michelucci &amp; Associates (2013) (FEIS; Appendix E).</p>	<p>Applicant / San Mateo County Planning and Building Department</p>	<p>Prior to issuance of grading and building permits.</p>	<p>Project design review/grading and building standards.</p>	<p>Complete. Grading permit was approved July 28, 2022</p>

Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
	<b>Mitigation Measure 4.4-2c:</b> The applicant shall retain a qualified engineering geologist. All grading and installation of fill shall be performed under the observation of the qualified engineering geologist.	Applicant / San Mateo County Planning and Building Department	During grading/ construction.	Verify site-specific grading standards.	Ongoing.
<b>Impact 4.4-3:</b> The Proposed Project could potentially result in shallow landslides due to the depth of unconsolidated colluvium on the project site.	<b>Mitigation Measure 4.4-3a:</b> Implement Mitigation Measure 4.6-2 (Section 4.6; Hydrology and Water Quality) to ensure that the site storm water drainage system (including individual systems for each residence) shall not allow discharge of uncontrolled runoff onto the site slopes. Concentrated runoff shall not be allowed to flow over graded slopes or areas of thick soil, colluviums, or fill.	San Mateo County Planning and Building Department / Homeowners Association	See Mitigation Measure 4.6-2 (During Project operations)	Project design review/Project operations.	Ongoing.
	<b>Mitigation Measure 4.4-3b:</b> Implement Mitigation Measure 4.4-2c to ensure the recommendations of the Geotechnical Investigation regarding subdrains and surface drainage are included in the project design.	Applicant / San Mateo County Planning and Building Department	See Mitigation Measure 4.4-2c (During grading/ construction)	Verify site-specific grading standards.	Ongoing.
<b>Impact 4.4-4:</b> Development of the Proposed Project in combination with future projects in the region could result in cumulative effects associated with geology and soils.	<b>Mitigation Measure 4.4-4:</b> Implement <b>Mitigation Measures 4.4-1 through 4.4-3.</b>	See Above	See Above	See Above	See Above.
<b>HYDROLOGY AND WATER QUALITY</b>					
<b>Impact 4.6-1:</b> Construction activities could substantially degrade surface water and/or groundwater quality, which could violate water quality	<b>Mitigation Measure 4.6-1:</b> The applicant shall comply with the SWRCB NPDES General Permit for Discharges of Storm Water Runoff Associated with Construction Activity (General Permit). The SWRCB requires that all construction sites have adequate control measures to reduce the discharge of sediment and other pollutants to streams to ensure compliance with Section 303 of the	Applicant/State Water Resources Control Board	Prior / during Construction.	Submit NOI to SWRCB. Verify that a SWPPP has been prepared and implemented.	Complete- NOI was filed on September 18, 2019. SWPPP dated September 9, 2019; Amendments were filed on 1/14/21 and 11/4/21

Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
standards.	<p>Clean Water Act. To comply with the NPDES permit, the applicant will file a Notice of Intent with the SWRCB and prepare a SWPPP prior to construction, which includes a detailed, site- specific listing of the potential sources of stormwater pollution; pollution prevention measures (erosion and sediment control measures and measures to control non- stormwater discharges and hazardous spills) to include a description of the type and location of erosion and sediment control BMPs to be implemented at the project site, and a BMP monitoring and maintenance schedule to determine the amount of pollutants leaving the Proposed Project site. A copy of the SWPPP must be current and remain on the project site. Control measures are required prior to and throughout the rainy season. Water quality BMPs identified in the SWPPP shall include, but are not limited to, the following:</p> <ul style="list-style-type: none"> <li>• Temporary erosion control measures (such as silt fences, staked straw bales, and temporary revegetation) shall be employed for disturbed areas. No disturbed surfaces will be left without erosion control measures in place during the winter and spring months.</li> <li>• Sediment shall be retained onsite by detention basins, onsite sediment traps, or other appropriate measures.</li> <li>• A spill prevention and countermeasure plan shall be developed which would identify proper storage, collection, and disposal measures for potential pollutants (such as fuel, fertilizers, pesticides, etc.) used onsite. The plan would also require the proper storage, handling, use, and disposal of petroleum products.</li> <li>• Construction activities shall be scheduled to minimize land disturbance during peak runoff periods and to the immediate area required for construction. Soil conservation practices shall be completed during the fall or late winter to reduce erosion during spring runoff. Existing vegetation will be retained where possible. To the extent feasible, grading activities shall be limited to the</li> </ul>				

Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
	<p>immediate area required for construction.</p> <ul style="list-style-type: none"> <li>• Surface water runoff shall be controlled by directing flowing water away from critical areas and by reducing runoff velocity. Diversion structures such as terraces, dikes, and ditches shall collect and direct runoff water around vulnerable areas to prepared drainage outlets. Surface roughening, berms, check dams, hay bales, or similar devices shall be used to reduce runoff velocity and erosion.</li> <li>• Sediment shall be contained when conditions are too extreme for treatment by surface protection. Temporary sediment traps, filter fabric fences, inlet protectors, vegetative filters and buffers, or settling basins shall be used to detain runoff water long enough for sediment particles to settle out.</li> <li>• Construction materials, including topsoil and chemicals, shall be stored, covered, and isolated to prevent runoff losses and contamination of groundwater.</li> <li>• Topsoil removed during construction shall be carefully stored and treated as an important resource. Berms shall be placed around topsoil stockpiles to prevent runoff during storm events.</li> <li>• Establish fuel and vehicle maintenance areas away from all drainage courses and design these areas to control runoff.</li> <li>• Disturbed areas shall be revegetated after completion of construction activities.</li> <li>• All necessary permits and approvals shall be obtained.</li> <li>• Provide sanitary facilities for construction workers.</li> </ul>				
<p><b>Impact 4.6-2:</b> Urban runoff resulting from the development of impervious surfaces and urban land uses on the project site has the potential to degrade</p>	<p>Mitigation Measure 4.6-2a: Upon acceptance of the design concept, a maintenance agreement shall be developed between the County and the Homeowners Association (HOA) or equivalent entity requiring the HOA or equivalent entity to complete the following tasks and provide the following information on a routine basis. These requirements apply only to the bioretention</p>	<p>San Mateo County Planning and Building Department / Homeowners Association</p>	<p>During Project operations.</p>	<p>Project design review/Project operations</p>	<p>Complete. Recorded in August 2022.</p>

Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
water quality and violate water quality standards or waste discharge requirements.	treatment system area of the project site and are as follows: <ul style="list-style-type: none"> <li>• Maintenance of soils and plantings, including routine pruning, mowing, irrigation, replenishment of mulch, weeding, and fertilizing with a slow-release fertilizer with trace elements</li> <li>• Removal of obstructions and trash from bioretention areas;</li> <li>• Use of only pesticides and fertilizers that are accepted within the integrated pest management approach for use in the bioretention areas;</li> <li>• Repair of erosion at inflow points;</li> <li>• Monthly review and inspection of bioretention areas for the following:                             <ul style="list-style-type: none"> <li>○ Obstruction of trash,</li> <li>○ If ponded water is observed, the surface soils shall be removed and replaced and subdrain systems inspected, and</li> <li>○ Condition of grasses;</li> </ul> </li> <li>• Distribution of the following:                             <ul style="list-style-type: none"> <li>○ A copy of the storm water management plans shall be made available to personnel in charge of facility maintenance and shall be distributed to the subcontractor representative engaged in the maintenance or installation of the bioretention system, and</li> <li>○ Material presented in the integrated pest management program will be made available to personnel in charge of facility maintenance and shall be distributed to the subcontractor representative engaged in the maintenance or installation of the bioretention system.</li> </ul> </li> </ul>				
	<b>Mitigation Measure 4.6-2b:</b> Upon acceptance of the design concept, a maintenance agreement shall be developed between the County and the HOA or equivalent entity requiring the HOA or equivalent entity to complete the following tasks and provide the following	San Mateo County Planning and Building Department / Homeowners	During Project operations.	Project design review/Project operations	Complete. Recorded in August 2022.



Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
	<p>information on a routine basis. These requirements apply to all common areas of the project site and are as follows:</p> <ul style="list-style-type: none"> <li>• Drainage inlets shall be inspected monthly and kept clean of any trash that may have accumulated. It is the responsibility of the property manager/owner to have those inspections performed, documented, and any repairs made.</li> <li>• Landscape areas shall be covered with plants or some type of ground cover to minimize erosion. No areas are to be left as bare dirt that could erode. Mounding slopes shall not exceed two horizontal to one vertical.</li> <li>• Pesticides and fertilizers shall be stored as hazardous materials and in appropriate packaging, over spraying onto paved areas shall be avoided when applying fertilizers and pesticides. Pesticides and fertilizers shall be prohibited from storage outside.</li> <li>• Landscape areas shall be inspected and all trash picked up and obstruction to the drainage flow removed on a monthly basis minimum. The project site shall be designed with efficient irrigation and drainage to reduce pesticide use. Plants shall be selected based on size and situation to reduce maintenance and routine pruning.</li> <li>• Integrated pest management information shall be provided to the building management.</li> </ul>	Association			
	<p><b>Mitigation Measure 4.6-2c:</b> Infiltration systems shall be designed in accordance with the following procedures outlined in the California Storm Water Best Management Practice Handbooks to reduce runoff and restore natural flows to groundwater:</p> <ul style="list-style-type: none"> <li>• Biofilters and/or vegetative swale drainage systems will be installed at roof downspouts for all buildings on the project site, allowing sediments and particulates to filter and degrade biologically.</li> <li>• Structural source controls, such as covers, impermeable surfaces, secondary containment facilities, runoff diversion berms, sediment, and</li> </ul>	Applicant / San Mateo County Planning and Building Department	During Project design phase and during construction activities.	Verify that infiltration systems are designed accordingly and that construction BMPs are implemented.	Ongoing.

Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
	grease traps in parking areas will be installed. <ul style="list-style-type: none"> <li>Designated trash storage areas will be covered to protect bins from rainfall.</li> </ul>				
<b>Impact 4.6-3:</b> Development of the Proposed Project would substantially alter the existing drainage patterns and may cause flows to exceed the capacity of existing stormwater drainage systems, result in substantial pollution on or off site, or result in flooding on or off site.	<b>Mitigation Measure 4.6-3a:</b> Upon acceptance of the design concept, a maintenance agreement shall be developed between the County and the HOA or equivalent entity requiring the HOA or equivalent entity to complete and provide the documentation of annual inspection and cleaning of each of the 19 individual lot storm drainage systems. The inspection shall be performed during the dry season and shall include removal of all trash and obstructions from area drains, cleanouts, and catch basins	San Mateo County Planning and Building Department/Homeowner's Association/Community Development Department	During Project operations.	Project design review/Project operations.	Complete. Recorded in August 2022.
	<b>Mitigation Measure 4.6-3b:</b> The 15-inch diameter stormwater drain pipe flowing at 2 percent that crosses Ascension Drive at Enchanted Way shall be replaced with a 21-inch diameter pipe. The 30-inch diameter stormwater drain pipe flowing at 1.3 percent shall be replaced with a 36-inch diameter pipe sloped at 2 percent. Stormwater drain pipe infrastructure improvements shall adhere to all applicable regulations and ordinances.	Applicant / San Mateo County Planning and Building Department	During construction.	Site inspection to verify compliance.	Complete.
<b>Impact 4.6-5:</b> Implementation of the Proposed Project would neither degrade groundwater quality nor substantially deplete groundwater supplies or interfere substantially with groundwater recharge such that there would be a net deficit in aquifer volume or a lowering of the local groundwater table.	<b>Mitigation Measure 4.6-5: Implement Mitigation Measures 4.6-1, 4.6-2a, and 4.6-2b.</b>	See Above	See Above	See Above	See Above
<b>HAZARDS AND HAZARDOUS MATERIALS</b>					
<b>Impact 4.7-1:</b>	<b>Mitigation Measure 4.7-1:</b> The project applicant shall	Applicant / San	During	Site inspection to	Ongoing.

Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
Construction of the Proposed Project would include the routine transport, storage, and handling of hazardous materials, which has the potential to result in a public health or safety hazard from the accidental release of hazardous materials into the environment.	ensure through the enforcement of contractual obligations that all contractors transport, store, and handle construction-required hazardous materials in a manner consistent with relevant regulations and guidelines, including those recommended and enforced by the San Mateo County Planning and Building Department, Office of Environmental Health Services Division, and Office of Emergency Services. Recommendations may include, but are not limited to, transporting and storing materials in appropriate and approved containers, maintaining required clearances, and handling materials using approved protocols.	Mateo County Planning and Building Department / County of San Mateo Office of Environmental Health Services Division / San Mateo County Office of Emergency Services	construction.	verify compliance with mitigation measures during construction.	
<b>Impact 4.7-2:</b> Construction of the Proposed Project has the potential to release hazardous materials into the environment through reasonably foreseeable upset or accident conditions, which may create a significant hazard.	<b>Mitigation Measure 4.7-2:</b> The project applicant shall require through contractual obligations that the construction contractor(s) marks the areas planned to be disturbed in white paint and notify Underground Service Alert (USA) one week prior to the beginning of excavation activities. This will be completed so the entire construction area is properly surveyed in order to minimize the risk of exposing or damaging underground utilities. USA provides a free "Dig Alert" service to all excavators (contractors, homeowners and others), in northern California, and will automatically notify all USA Members (utility service providers) who may have underground facilities at their work site. In response, the USA Members will mark or stake the horizontal path of their underground facilities, provide information about, or give clearance to dig. This service protects excavators from personal injury and underground facilities from being damaged. The utility companies will be responsible for the timely removal or protection of any existing utility facilities located within construction areas.	Applicant	One week prior to excavation activities		Ongoing.
<b>Impact 4.7-3:</b> The Proposed Project has the potential to expose people or structures to a significant risk of loss, injury, or death involving wildland fires.	<b>Mitigation Measure 4.7-3a:</b> The applicant shall ensure through the enforcement of contractual obligations that the following measures are implemented by contractors during project construction: <ul style="list-style-type: none"> <li>• Staging areas, welding areas, or areas slated for development using spark-producing equipment shall be cleared of dried vegetation or other materials that could serve as fire fuel. To the extent</li> </ul>	San Mateo County Planning and Building Department	During construction.	Site inspection to verify compliance with mitigation measure during construction.	Ongoing.

Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
	<p>feasible, the contractor shall keep these areas clear of combustible materials in order to maintain a fire break.</p> <ul style="list-style-type: none"> <li>Any construction equipment that normally includes a spark arrester shall be equipped with an arrester in good working order. This includes, but is not limited to, vehicles, heavy equipment, and chainsaws.</li> </ul>				
	<p><b>Mitigation Measure 4.7-3b:</b> The building plans of the Proposed Project shall be reviewed by a representative from County Fire/CAL FIRE to ensure that regulations in the County's Fire Ordinance are met and the project complies with County Fire/CALFIRE requirements. The development of the Proposed Project shall be in compliance with Chapter 15 of the County General Plan with respect to residential uses adjacent to open space areas where wildfire is a threat.</p>	<p>Applicant / San Mateo County Planning and Building Department / County Fire/CAL FIRE</p>	<p>Prior to issuance of building permits.</p>	<p>Project design review/Chapter 15 County General Plan.</p>	<p>Ongoing.</p>
<p><b>Impact 4.7-5:</b> The Proposed Project in combination with future growth and development in the project vicinity would result in cumulative effects associated with hazards and hazardous materials.</p>	<p><b>Mitigation Measure 4.7-5:</b> Implement <b>Mitigation Measures 4.7-1</b> through <b>4.7-3</b>.</p>	<p>See Above</p>	<p>See Above</p>	<p>See Above</p>	<p>See Above</p>
<p><b>NOISE AND VIBRATION</b></p>					
<p><b>Impact 4.8-1:</b> Construction of the Proposed Project has the potential to generate a substantial temporary or periodic noise level greater than existing ambient levels in the project vicinity.</p>	<p><b>Mitigation Measure 4.8-1:</b> The project applicant shall ensure through contractual agreements that the following measures are implemented during construction:</p> <ul style="list-style-type: none"> <li>Construction activities shall be limited to occur between the hours of 7:00 A.M. to 6:00 P.M. Monday through Friday, and 9:00 A.M. to 5:00 P.M. on Saturdays. Construction activities shall not occur on Sundays, Thanksgiving, or Christmas. The intent of this measure is to prevent construction activities during the more sensitive time period and</li> </ul>	<p>Applicant / San Mateo County Planning and Building Department</p>	<p>During construction.</p>	<p>Site inspection to verify compliance with mitigation measures during construction.</p>	<p>Ongoing.</p>

Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
	<p>minimize the potential for effects.</p> <ul style="list-style-type: none"> <li>• Stationary equipment and staging areas shall be located as far as practical from noise-sensitive receptors.</li> <li>• All construction vehicles or equipment, fixed or mobile, shall be equipped with properly operating and maintained mufflers and acoustical shields or shrouds, in accordance with manufacturers' recommendations.</li> <li>• Construction activities shall conform to the following standards: (a) there shall be no start-up of machines or equipment, no delivery of materials or equipment, no cleaning of machines or equipment and no servicing of equipment except during the permitted hours of construction; (b) radios played at high volume, loud talking and other forms of communication constituting a nuisance shall not be permitted.</li> <li>• The general contractors for all construction activities shall provide a contact number for citizen complaints and a methodology for dealing with such complaints such as designating a noise disturbance coordinator.</li> </ul> <p>This noise disturbance coordinator shall receive all public complaints about construction-related noise and vibration, shall be responsible for determining the cause of the complaint, and shall implement any feasible measures to be taken to alleviate the problem. All complaints and resolution of complaints shall be reported to the County weekly.</p>				

Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
<p><b>Impact 4.8-2:</b> Construction of the Proposed Project has the potential to expose existing sensitive noise receptors to construction traffic noise in excess of the County’s noise standards.</p>	<p><b>Mitigation Measure 4.8-2:</b> Implement <b>Mitigation Measure 4.8-1.</b></p>	<p>See Above</p>	<p>See Above</p>	<p>See Above</p>	<p>See Above</p>
<p><b>PUBLIC SERVICES, UTILITIES, AND RECREATION</b></p>					
<p><b>Impact 4.10-2:</b> The Proposed Project would require the construction of new and relocation of existing water supply facilities, the construction of which could cause significant environmental effects.</p>	<p><b>Mitigation Measure 4.10-2a:</b> Residents of the Proposed Project shall comply with all requirements of Cal Water’s Water Shortage Contingency Plan as mandated by Cal Water and BSD. These requirements may include, but are not limited to the following:</p> <ul style="list-style-type: none"> <li>• Voluntarily reduce water consumption at single-family residences;</li> <li>• Adhere to the minimum allocation given to single-family residential customers or pay penalty rate applied to service bill for use that is in excess of customer’s allocation; and/or</li> <li>• Comply with orders prohibiting the use of water for specific activities, such as a prohibition of potable water use for landscape irrigation.</li> </ul>	<p>Cal Water Bayshore District</p>	<p>Project <b>operations.</b></p>	<p>Cal Water Shortage Contingency Plan.</p>	<p>To be implemented Post-Construction</p>
	<p><b>Mitigation Measure 4.10-2b:</b> Pumping facilities shall be installed at the existing water tank owned by Cal Water to provide adequate water pressure for residential and fire protection uses. Cal Water shall be contacted to review pumping facilities design and ensure compliance with applicable standards. The project applicant shall fund the development of these facilities.</p>	<p>Applicant/ Cal Water Bayshore District</p>	<p>During construction.</p>	<p>Site inspection to verify compliance with mitigation measures during construction.</p>	<p>Ongoing</p>

Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
	<p><b>Mitigation Measure 4.10-2c:</b> Two existing water mains shall be relocated such that they are within the right-of-way of the proposed private street or at the property boundary so as to allow ease of maintenance of the water mains. New Cal Water easements shall be established on the project site to replace the existing Cal Water easements. The two water mains include an 8-inch diameter water main connecting the water tank to the water main located on Parrot Drive and a 10-inch diameter water main connecting the water tank to the water main located on Bel Aire Drive.</p>	<p>Applicant/ Cal Water Bayshore District</p>	<p>During construction</p>	<p>Site inspection to verify compliance with mitigation measures during construction.</p>	<p>Complete.</p>
<p><b>Impact 4.10-3:</b> The Proposed Project would exceed the wet weather capacity of the wastewater conveyance system and would require upgrades to existing wastewater treatment facilities, the construction of which could cause significant environmental effects.</p>	<p><b>Mitigation Measure 4.10-3:</b> The applicant shall offset the increase in sewer flow generated by the Proposed Project by reducing the amount of existing I&amp;I into the CSCSD sewer system. The offset amount shall achieve a zero net increase in flow during wet weather events with implementation of the Proposed Project. This shall be achieved through the construction of improvements to impacted areas of the sewer system, with construction plans subject to CSCSD approval and required to be in compliance with applicable regulatory requirements. Construction of improvements, as approved by the CSCSD, shall be completed prior to the start of the construction of the residences.</p>	<p>Applicant / Crystal Springs County Sanitation District</p>	<p>Prior to construction</p>	<p>Approval of sewer system construction improvements.</p>	<p>Complete.</p>
<p><b>Impact 4.10-4:</b> The Proposed Project would require the expansion of existing stormwater drainage facilities, the construction of which would cause significant environmental effects.</p>	<p><b>Mitigation Measure 4.10-4:</b> Implement <b>Mitigation Measures 4.6-3a</b> and <b>4.6-3b</b>.</p>	<p>See Above</p>	<p>See Above</p>	<p>See Above</p>	<p>See Above</p>

Impact	Mitigation Measure	Responsible for Implementing & Monitoring	Mitigation Timing	Monitoring Schedule	Completion Status
<p><b>Impact 4.10-5:</b> The Proposed Project would generate a demand for fire protection services, which could require the construction of new or expanded facilities that may cause significant environmental impacts.</p>	<p><b>Mitigation Measure 4.10-5:</b> The applicant shall ensure that fire sprinklers with appropriate flow rates are installed for all structures that would be developed as a part of the Proposed Project, per County Fire/CAL FIRE’s alternate materials and methods request.</p>	<p>County Fire/CAL FIRE</p>	<p>During construction.</p>	<p>Site inspection to verify compliance with mitigation measures during construction.</p>	<p>Ongoing.</p>
<p><b>TRANSPORTATION</b></p>					
<p><b>Impact 4.11-3:</b> Implementation of the Proposed Project would not conflict with adopted policies, plans, or programs, including those related to safety and performance, regarding public transit, bicycle, and pedestrian facilities but does have the potential develop unsafe pedestrian and bicycle facilities.</p>	<p><b>Mitigation Measure 4.11-3:</b> Either provide street lighting on the private streets to a level of 0.4 minimum maintained average foot-candles with a uniformity ratio of 6:1, average to minimum or ensure street lighting is consistent with safety standards of the County-governed Bel Aire Lighting District.</p>	<p>Applicant and Bel Aire Lighting District</p>	<p>During construction.</p>	<p>Site inspection to verify compliance with mitigation measures during construction.</p>	<p>Ongoing.</p>
<p><b>Impact 4.11-4:</b> Implementation of the Proposed Project has the potential to substantially increase hazards due to the design of the new private street and proposed intersection with Bel Aire Drive.</p>	<p><b>Mitigation Measure 4.11-4:</b> Within the corner sight triangles at the new street intersection there should be no walls, fencing, or signs that would obstruct visibility. Trees should be planted so as to not create a “wall” effect when viewed at a shallow angle. The type of shrubbery planted within the triangles should be such that it will grow no higher than three feet above the adjacent roadway surface. Trees planted within the sight triangle areas should be large enough that the lowest limbs are at least seven feet above the surface of the adjacent roadway. Street parking should be prohibited within the bounds of the sight triangle.</p>	<p>Applicant and Bel Aire Lighting District</p>	<p>During construction.</p>	<p>Project design review.</p>	<p>Ongoing.</p>